

THE MARINE REVIEW

VOL. XXXIV.

CLEVELAND, DECEMBER 6, 1906.

No. 23

Naval Architects and Marine Engineers


Mr. William Gatewood's paper upon the "Construction of a Fireproof Ferry Steamer" was as follows:

The purpose of this description is to place before the society the particulars of an adaptation of fireproof construction in the building of the Jamestown, an excursion steamer for the Potomac river.

The vessel was built by the Newport

officers, and a large open deck for passengers, covered by awnings. The propelling machinery consists of compound inclined engines, 30 in. and 64 in. in diameter with 66 in. stroke, operating feathering paddle wheels, 17 ft., 3 in. outside diameter. There are four single ended Scotch boilers. The vessel is lighted by electricity. A speed of nearly 19 miles was obtained on

ing, as the use of the spaces rendered desirable. In the machinery space, the floors are of ribbed plate, set on steel angle supports. The main bulkheads are of steel plate, in thickness varying from 3-16 in. to 5-16 in. and stiffened with steel angles; and the main divisional bulkheads on the lower deck are also of steel plate $\frac{1}{8}$ -in. thick with angle stiffeners. The minor



FIREPROOF EXCURSION STEAMER JAMESTOWN.

News Ship Building & Dry Dock Co., from designs prepared by them to meet the requirements of the Norfolk & Washington Steamboat Co., and was put in service in June last.

The vessel has a length between perpendiculars of 250 ft., length over all of 262 ft., beam over guards of 63 ft., beam molded of 38 ft., and depth molded of 14 ft., 6 in. Plates I to IV show the general arrangement of the vessel. Below the main deck are the barroom, pantry, galley and quarters for the crew. On the main deck are dining room, lobby, parlors and deck space for passengers, both open and enclosed. On the saloon deck are parlors, a few staterooms, toilets, a large enclosed cabin, and some open deck for passengers. On the shade deck are the pilot house and rooms for deck

the trial trip in Chesapeake Bay.

By the term "fireproof," is not meant that the vessel is incapable of destruction by fire, but that the amount of combustible material has been limited to such an extent, and what remains is so protected and distributed that the chances of a fire starting on board are greatly reduced; and the spread of a fire would be practically impossible even should one get a start.

No trouble was experienced in this connection with the hull below the main deck, as it was constructed of steel throughout.

The lower deck is built of steel plating 3-16-inch thick laid on beams spaced 27 inches to 30 inches apart, and covered with linoleum, brick, mosaic tiling or interlocking rubber til-

divisional bulkheads on this deck are of corrugated steel plate of No. 18 U. S. S. gauge, with steel angle boundaries.


The main deck is built of steel plating $\frac{1}{4}$ -in. thick, on steel bearers spaced 24 to 36 in. apart, with the stringer somewhat heavier. The runners under this deck are of steel channels and the beam stanchions are of iron pipe. The covering on the main deck is of rubber tiling or linoleum. The adherence of the rubber tiling or linoleum to the steel deck was obtained by the use of the special cement which it is customary to use for this purpose. The linoleum on this deck where it is exposed to the weather, is secured in addition by thin galvanized steel strips placed on top along the edges and across the joints,

and secured through to the plating by brass machine screws. This latter arrangement is indicated by sketch No. 1 on plate V, and was considered necessary on the exposed deck on account of the liability of water soaking under the edge of the linoleum

5-32-in. thick, with stiffeners alternately angles and tee bars, the latter serving as butt straps and fitted with flanges outside, giving a panel effect. The casings are lined in way of the boiler rooms with No. 24 U. S. S. gauge steel, to which is secured as-

flanges of the angle or tee bar stiffeners for appearance sake, as shown by Sketch No. 4.

It was at first considered practicable to build the saloon and shade decks of light steel riveted to steel beams, but after several experimental




LOWER DECK, STEAMER JAMESTOWN.

and thus spoiling the adhesion.

As was anticipated, much trouble was experienced in settling upon the design above the main deck. The following construction of the various parts above this deck was finally de-

bestos air cell 1-in. thick to prevent the radiation of heat into the passenger quarters outside. This construction is shown by sketch No. 3 on plate V. It will be noticed that small iron clips were riveted to the stiffeners to

sections had been built it was decided that exposure to the sun and weather, and the difficulties attendant upon buckling due to the riveting of thin material, would require a thickness of plating of not less than 3-16-in. The weight of 3-16-in. plating rendered the use of such thick plating at this height out of the question on account of the reduction in stability which would have been caused thereby. It was decided, therefore, to use steel angle beams turned upside down, with a pine nailing strip bolted to the vertical flange and resting on the horizontal flange, and on this to lay $\frac{7}{8}$ -in. pine decking. The under surface of the decking was then covered with thin sheet steel, and a cornice of the same material was fitted over the nailing strip and on the other side of the beam as well, to give a finish. This steel ceiling was not smooth but was rolled with shallow corrugations. The cornice and ceiling were secured by wire nails. As will be seen by reference to sketch 5 on plate V, there is



MAIN DECK, STEAMER JAMESTOWN.

termined upon, and seems to have been satisfactory.

The waist or bulwark is built of $\frac{1}{4}$ -in. thick steel plate with wood rail on top, stiffened by the bracketed steel angle supports of the saloon deck, and by intermediate angle stiffeners. Abreast the wheels and in way of the toilet and parlors amidships, the side was extended to the saloon deck by plating 3-16 in. thick, with angle stiffeners.

Where the houses on this deck do not extend to the side, they are built of 5-32 in. thick plating, with angle stiffeners bracketed to the main deck.


The finish inside of these houses was obtained by steel ceiling of No. 24 U. S. S. gauge, secured by brass wood screws to wood grounds bolted to the stiffeners. The wood grounds serve also as guides for the windows. The window sashes are of oak, and the usual wood blinds are replaced by roller curtains. The arrangement of this ceiling is shown by sketch No. 2. The edges of the ceiling were crimped to make a neat finish.

The machinery casings are of steel

take the screws for securing the ceiling, and the use of wood for this purpose in this location was thus avoided.

Air cell asbestos is also fitted under the main deck over the boiler-room, engine-room and galley, resting on metal strips secured to the bottom flange of the beams, to help prevent

Transactions Society Naval Architects and Marine Engineers, Vol. 19, 1909.



MAIN DECK, STEAMER JAMESTOWN.

the transfer of heat through this deck, a result accomplished on other vessels by their wood decks.

Boundary bulkheads on the main deck are constructed in a similar manner to the casings, and sheet steel pilasters are fitted over the standing


no wood left exposed on the under side of these decks. Steel face plates, stringer plates and tie plates are fitted for these decks, and the runners under the beams are of steel bulb angles, with iron pipe stanchions.

Linoleum was used as floor cover-


ing on the saloon deck where not exposed to the weather, that fitted in the main saloon being of the standard battleship grade, of a thickness exceeding $\frac{1}{4}$ -in. The covering to be used on the exposed portions of the saloon and shade decks was, how-

posure. It was finally decided to cover the wood decking with canvas to secure water-tightness, and on this to lay interlocking rubber tiling. This presents an elegant surface, and in general seems to have served the purpose, although some difficulty was ex-

where the surface can be kept coated with shellac. The floor of the main saloon of this vessel, which is fitted with heavy linoleum, makes an excellent surface for dancing. If linoleum is laid on weather decks it would seem necessary to fit metal strips over all



SALOON AND SHADE DECK, STEAMER JAMESTOWN.



MIDSHIP SECTION, STEAMER JAMESTOWN.

ever, a subject of much consideration. The usual canvas was not considered a satisfactory covering on account of the danger from fire, as lighted cigar ends, etc., have been known to cause trouble on canvas decks. It was thought that some form of asbestos tiling could be used for this purpose, samples were tested and found to be unsuitable, as the asbestos tiles were not tough enough on the surface to stand the wear; and the adhesion between the tiles and the cement used in laying was also defective after ex-

perienced on the shade deck, due partly to lack of care in laying and partly to the action of the weather. On account of the weight and expense, the use of interlocking rubber tiling for this purpose leaves much to be desired, even though satisfactory adherence to the deck is obtained. In this connection the suitability of heavy linoleum for this purpose will probably be shown by the small amount which was laid on the exposed main deck of this vessel. Heavy linoleum makes a fine deck covering for protected decks

the joints, and the surface could hardly compare with that of the interlocking rubber tiling as fitted on this vessel. Sketch No. 6 shows the method adopted for ending the wood deck and its covering at the edge of the waterway at the side of the vessel.

The house on the saloon deck is built of 5-32-in. steel plates, stiffened with angles and lined with No. 24 gauge sheet steel in a similar manner to the house on the main deck, and considerable care was taken to bracket the stiffeners to the beams, so that

the rigidity of the structure might be maintained, although the material was so thin. By reference to sketch No. 2 on plate V will be seen how the drip from the windows was led into the waterway behind the ceiling and taken off by scuppers at intervals; and also how the lower portion of the ceiling was made separate so as to be more readily removable for access to this waterway. Divisional bulkheads on all the decks are built of No. 18


thin metal rendered very necessary the elimination of this cause of corrosion.

The use of wood in the furnishing of the vessel was reduced to a practicable minimum. Bedsteads are of brass or enameled iron, plumbing is of the open type, and clothes lockers are of sheet metal.

The electric wiring is led in steel conduit.

The life preservers, where stowed overhead, are held up by heavy twine

own warship construction. The first battleships of the Indiana class had corrugated bulkheads. The appearance of a corrugated bulkhead, however, is not entirely satisfactory, and on some later ships in whose design I was concerned, we had a system of building up light plates with stiffeners of semi-cylindrical form, which, however, we were unable to get down to a weight equivalent to the weight of the wooden bulkheads formerly used. There



DETAILS OF CONSTRUCTION, STEAMER JAMESTOWN.

gauge sheet steel, corrugated for stiffness, with corrugations about 1¼-in. deep and 8 in. apart.

The pilot house and officers' rooms on the shade deck are built in a similar manner to the house on the saloon deck, with corrugated metal partition between the rooms. Some slight trouble has been experienced with the compass on account of its proximity to so much steel work and it is not quite as quick moving as usual. The expense entailed would not permit of the construction of the pilot house of brass, the only other fireproof material available, as is done on the recent vessels of our navy.

The stairways are constructed of metal and the steps are covered with ribbed sheet rubber. Sketch No. 7 shows the construction. The rails on the stairways are of galvanized iron pipe, and around the wells metal grille work is fitted.

The guard rails are of pipe, with pipe stanchions and with galvanized wire mesh panels.

In connection with the painting, it may be noted that cork was liberally used, as condensation and "sweating" are thereby reduced, and the use of

instead of the usual wood battens.

The construction of this vessel may be summarized as being of steel, the use of wood having been eliminated as far as practicable, and most of the wood that is used is covered with non-inflammable material.

DISCUSSION.

Mr. J. H. Linnard—It is very interesting to us who are engaged in the design of warships to listen to improvements which have been effected in the particular class of vessels which have been under consideration this morning. Of course, for warships the problem of making fireproof construction has been one which has been considered for a much longer period, but has not as yet led to satisfactory results in many respects. We have also in warships the freedom of design involved in the fact that we can compel people to live in the structures we build. One of the difficulties apparent in the passenger boats is that if you do not make the steamer to suit the people who are to go on the steamer, you do not get the people there, which is a very severe limitation on design. The use of corrugated bulkheads dates from a comparatively early period in our

was not a very large increase, however, but it must be admitted that the wooden bulkheads formerly used on warships were much heavier than those used on merchant vessels, particularly coast and Sound steamers. One matter, perhaps, to which the least satisfactory solution has been given, and I notice the same has been the case with merchant ships, is that of providing a suitable deck that is really fireproof and not excessive in weight. That is due to the fact that the decks have to sustain concentrated loads and the beams which support the flat surface cannot be spaced very closely, and yet the deflection that is obtained with any light steel plate is inadmissible. I think perhaps some of the steel plates which have been used in the boats described here this morning will be found objectionable.

Mr. Gatewood states that the interlocking tiling which was used on the weather decks has not proven satisfactory, and I would be glad to learn if they have yet determined on the substitute they will use for the interlocking tiling on the weather decks. It is true that linoleum, used on most of the warships for the interior, is not

fireproof, but still I think it is not a material that will lead to conflagrations or the rapid running of fire along the decks. Its thinness prevents its gathering the mass of flame and heat that is necessary to produce a conflagration. As far as I am aware, materials that have been produced, of various patent or proprietary names, Xylolith and others, laid on decks, have not proven satisfactory. They generally crack and lead to corrosion under the material.

The president—If there is no further discussion on these papers, we will ask the gentlemen who presented them to close the discussions.

Mr. William Gatewood—In reply to the discussion in connection with the matter of fireproof construction, the only point on which I will dwell is the question of fireproof tiling. We have adopted rubber tiling on ferryboats, double deck boats. A year or so ago a fire occurred on one of the boats and it was reported that the rubber tiling in the saloon deck saved the boat, which indicates that the rubber tiling is fireproof and satisfactory. On the Jamestown, no substitute for the rubber tiling, which we will remove from the exposed deck, has yet been settled upon, and it is possible that no substitute will be provided, but that canvas will remain the cover on the exposed deck. We regretted not to be able to build a steel deck for the upper works of this vessel, but there is no doubt that the weight involved would have been detrimental to the boat, and under the circumstances the vessel is of such construction that there is practically no danger of fire while the vessel is in commission.

The president—The chair ventures to suggest to Mr. Gatewood the desirability, if it meets with his good judgment, of replying to some of the questions asked of Mr. Du Bosque in the general discussion particularly with regard to the additional weight of the construction of the Jamestown and the additional cost. Possibly Mr. Gatewood will make that addition to his discussion when it is sent to him for revision.

Mr. Du Bosque—Mr. President, first I want to say that I regret very much, that what we expected was going to happen has happened. We were told when we started to design a fireproof ferryboat that everybody in the harbor would be down on us; it would be used as an illustration and give notoriety to the matter of fireproofing of ferryboats, and the public would ask—why are not all the ferryboats made fireproof? Unfortunately, the

public cannot see these things in the practical light. Developments begin very slowly; we cannot start out at once and build the most perfect watch or the most perfect locomotive; you have never seen such a thing, and we all know that we must creep in these things. Unquestionably, there is a desire for fireproof boats, and it seems to me there is no easier or more practical place to try the problem than on a ferryboat. To my mind it is the easiest kind of a boat to which to apply fireproof construction, and therefore we thought we were not going amiss in making this step. I think that there is no one, no matter how deeply he has studied the subject, who would prepare the designs and enter into a contract for a fireproof boat like the magnificent Pilgrim and Puritan or the Hendrik Hudson, or boats of that type; but I think the time is not far distant when such a condition will prevail.

To answer the questions which have been asked, in detail, I will say in reply to Mr. Forbes, I thought I had clearly stated that the total cost of the boat was increased seven per cent; that refers to the total cost of the boat. The steel joiner work, if it might be so termed, probably cost twice as much as much as the wood-work would cost. The steel moldings are obtained from the Dahlstrom Door Co., of New York, they are the only concern that make this product. Two or three gentlemen referred to the difficulty of holding the joints and of the method of making the joints of this molding. Our thought was that material, if it is not under strain, will not have its joints disturbed, and these moldings are applied with that thought. They do nothing but act as a border to this asbestos panel which has sufficient strength in itself to hold itself in place. There may be some distortion, but that we will find out with experience. It do not think there will be. The joints are made exactly as in the case of a wooden molding. We use a hack saw with extremely fine teeth and cut them off at any angle or in any shape. In reply to Capt. Miller, I will say that the material weighs 4½ lbs. per square foot, which is about 1½ lbs. more than one-inch wooden border of the same size would weigh. It is much lighter than the panels which we have hitherto used on our ferryboats, because in endeavoring to obtain some sort of fireproof construction we have for the last seven years used a combination of plaster held in place with wire gauze, which is very heavy. These panels weigh only half as much as

that form of construction. As for experiments, a quite elaborate test of the insulating quality of this material was made by the Fire Underwriters' Association, of Baltimore, and it was considered by our company to be a sufficient evidence of its fire-resisting qualities. As to the question of moisture, I immersed a piece of this molding in water for six weeks. It absorbed about 1½ per cent of moisture in the first ten hours, and nothing afterwards. That it is fireproof is determined by trying to burn it; you cannot. It does not disintegrate under any heat to which it was applied, which was a torch, a Wells burner. I set a piece of the board up vertically and had a Wells burner which would deliver a flame of about six feet. I placed the burner in front of the board, not more than a foot away, so as to get not only the heat, but the force of the flame, and after six or seven hours there was no evidence of disintegration except the blackening of the face of it.

In regard to Prof. Maclean's inquiry, we are now undertaking to design a double deck ferryboat of fireproof construction and have every confidence we will carry it through. Touching on that subject, when I look at the Hammonton, I think I was a novice when I designed it; there are so many places where it can be improved, and so many places where it can be altered and made stronger and built more cheaply; but it was our first effort and the best we knew of at that time. Experience has taught us where a much greater economy in weight and cost can be obtained.


In reply to the next question, as to what ferryboats are equipped with walls and ceilings in the spaces which are occupied by the vehicles, including automobiles, I will say that the Long Island Railroad Co. has two of these boats running on their ferry. It would be a good idea for Mr. Maclean to take a look at them. I will say that the watertight doors in the bulkheads are watertight. After a great deal of persuasion from the New York Ship Building Co. and against our wish, they insisted on using the navy standard for making the doors watertight. So far as the stability of the boats from collision is concerned, that has been worked out, we think, satisfactorily. Any one compartment can be flooded to the water line without any danger of the boat sinking. That is what our rules now require, and ample calculations have been made to determine that fact. Mr. Gatewood has informed Mr. King that rubber tiling will not burn; it is about 96

per cent clay. So far as any inconvenience from sitting on these steel moldings is concerned, I do not think any one in this room would know they were steel from sitting down on them

to be said—the reason that the Fall river line has not had any trouble from fire, is because they have been so eternally vigilant in their fire patrols. Nobody ever woke up at night

on the sides is where the iron work cannot be got at to paint, so that we do not expect what might be called interior corrosion. Mr. Dickie has also walked on the upper deck of this

Hudson River Day Line Steamboat New York.



HUDSON RIVER DAY LINE STEAMBOAT NEW YORK.

or looking at them. They are molded to the same shape as the wooden moldings we always used, and painted liberally; just now, in this cold atmosphere, and the cabins not heated, they might feel cold, but they are so thin they will surely assume the tempera-

ture of the surrounding air, and I do not think any one will know they are not wood when he sits down upon them. One word in reference to partitions. I think you are on the wrong tack when you try to use any kind of metal partitions. A partition, a wall, should not be made a supporting structure. It is something to keep your eye from going into the next room, or air circulating from one room to another, or something of that kind; simply a division plate and many materials can be used for that. The way to improve on fireproof construction is to depart entirely from everything that has been taught us by naval architects, and take a few lessons from bridge builders. A boat builder has got to follow out the designs that bridge builders follow. I think if any of us, who think we are naval architects, would look at the framing of a windmill we would say—how in the world does it stay there? Yet it does, it looks as if it was put up on strings. There has been a rational system in the employment of the section of metal in the case of a windmill.

In reply to Mr. Dickie, there are




PLATE 3.—STEAMBOAT NEW YORK.

very few places on this ferryboat where the paint cannot be applied without taking down something else to


boat, and I do not think he has found any vibration there. I have tried to discover this vibration, with three or four others alongside of me, and we have not succeeded. We think it is entirely too stiff, and on another boat we will make it lighter. In reply to Mr. Wheeler, I will say the fire which occurred on the New Jersey Central boat was not such a serious fire as he was led to believe. The fire may have looked as if it was on the deck of the boat, but it was not; it originated in a locker beneath the staircase, which the porters use for stowing away mops and brooms, and the stuff which they use for cleaning the cabins; it is supposed that one of the materials they used for cleaning the brasswork, being of a very inflamma-

ture of the surrounding air, and I do not think any one will know they are not wood when he sits down upon them. One word in reference to partitions. I think you are on the wrong tack when you try to use any kind of metal partitions. A partition, a wall, should not be made a supporting structure. It is something to keep your eye from going into the next room, or air circulating from one room to another, or something of that kind; simply a division plate and many materials can be used for that. The way to improve on fireproof construction is to depart entirely from everything that has been taught us by naval architects, and take a few lessons from bridge builders. A boat builder has got to follow out the designs that bridge builders follow. I think if any of us, who think we are naval architects, would look at the framing of a windmill we would say—how in the world does it stay there? Yet it does, it looks as if it was put up on strings. There has been a rational system in the employment of the section of metal in the case of a windmill.

I do not know how to reply to Capt. Taylor. He says he does not approve of this fireproofing business, and yet as these fires occur on his boats he wants to know how to make them fireproof. I think in his case this is

get at it. I think Mr. Dickie is very familiar with this boat, as he is stationed at the ship yards, and I believe if he will think it over he will realize that only behind some of these panels

ble nature, caught fire spontaneously, as there was no evidence to trace any one as having been in the closet at that time, though there was ample evidence to show that the fire was started



in the closet. Since then the closets on the ferryboats are lined with asbestos material. In reply to another gentleman, we are using sand all over the ferryboats, provided in buckets, principally brought about by the fact that the only known way to extinguish a gasoline fire is to sprinkle sand over it, and all boats are equipped with a sand tank on each end for that purpose. I think that covers the ground.

The president—There has been no discussion ever taken place in this society of greater importance to the public than this one this morning, and it is undoubtedly in accordance with your wishes that a vote of thanks should be extended to the gentlemen who contributed these interesting papers.

Mr. W. P. Stephens—I believe I have attended every session of this society since it was organized, and I think I am safe in saying that this is the first session at which nothing has come up in connection with the gentle art of killing people. I do not want to depreciate the naval end of it, but we have devoted the whole morning to the art of saving people; and I wish to move a vote of thanks to these two gentlemen for the very valuable papers which they have presented, and which we hope is the beginning of a much broader movement in this direction. (Motion seconded.)


The president—In putting this mo-

discussion. We all know that many of these gentlemen have considered this subject in view of the grave responsibilities that have fallen upon them, with great care and for many

say Aye; contrary-minded please say No. The motion is unanimously carried.

PROF. JAMES E. DENTON'S PAPER.

Prof. James E. Denton's paper on the




years, and that their consideration of the question has not only been influenced by such things as has brought about the building of this ferryboat, but by their sense of responsibilities,

"Performance of the Paddle-Wheel Steamboat New York of the Hudson River Day Line," was then read as follows:

"Ever since the advent of the Clermont made the Hudson river the birth-place of steam navigation as a remunerative art, the passenger traffic of this river has practically adhered exclusively to the use of the single-cylinder, vertical, low-pressure, paddle-wheel engine which Fulton adopted.

"In the development of this type of engine in day-passenger service on six feet of draft, the advent of the Mary Powell, in 1861, represents the maximum speed attained with radial paddles, and a diameter of wheel sufficient to afford a speed of about 20 statute miles without exceeding 25 revolutions per minute.

"In the further development for speed since the date of the Mary Powell, the New York, built in 1887, represents the best which has been accomplished, with wheels about as large as those of the Mary Powell, but fitted with feathering paddles. In the latest development represented in the recent advent of the New York's magnificent sister boat, the Henrick Hudson, the historical type of engine is supplanted by the high-pressure, inclined, compound system using feathering paddle-wheels of so small a diameter that an engine speed of upward of 40 revolutions per minute is required. I have therefore ventured to think it appropriate at this time to present the re-




tion the chair feels it will be in accordance with the feeling of the members that we should also express our obligation to those in responsible positions who have taken part in this

and their investigation of their subject has been diligent and continuous and entirely without regard to questions of cost. All those in favor of extending this vote of thanks please

sults of speed and power trials of the New York made at the request of the owners, as a contribution to the information desired in designing the new boat.

"The tests were made during the spring

at right angles to them, about 700 ft. from the shore, a course is afforded 0.85 statute miles in length by the coast survey chart, with a depth of water increasing from 48 ft. at 96th street to 68 ft. at 129th street.



of 1903, just after the boat had left the dry dock for the season's service. They consisted of a progressive speed test with opposite runs over a straight course off 96th street, and a continuous river test from New York City to Poughkeepsie."

GENERAL DESCRIPTIONS AND DIMENSIONS.

The general appearance of the New York is shown by Plate 1. The hull is of steel, with lines as per Plates 2 and 3. The engine is of the single-cylinder, walking-beam type, to which slightly superheated steam at about 40 lbs. pressure is supplied by three return-flue boilers operated under natural draft and artificial draft when necessary by air at about 1.5 in. pressure delivered into closed ash-pits.


Diameter of cylinder	75 in.
Stroke of cylinder	12 ft.
Heating sur. of boilers, tot..	5,499 sq. ft.
Grate surface of boilers, tot..	228 sq. ft.
Length of hull on water line..	330 ft.
Draught from top of keel	6 ft.
Beam on water line	40 ft.
Area of midship section	216 sq. ft.
Displacement	1,240 gross tons
Block coefficient	0.584
Wetted surface	11,250 sq. ft.
Outside diameter of paddles..	29 ft. 10 in.
Diam. to center of trunnions..	27 ft. 0 in.
Width of paddles	3 ft. 4 in.
Length of paddles	12 ft. 6 in.
Number of paddles	12
Dip of paddles	4 ft. 5 in.

PROGRESSIVE SPEED TRIAL.

This was made over a course which I have frequently used in previous tests, lying between 96th street and 129th street.

The lines of these streets are parallel and clearly defined, so that by running

Opposite runs were made at four speeds, commencing at about fifteen revolutions per minute, and ending with about twenty-eight revolutions, the lat-



ter being the highest speed that could be maintained by the boilers (see boiler pressure, column 4, Table A.) The detailed speed data are given in Table B, and the complete results in Table A.

The trial speed, column 11, Table A, is deduced for each separate run, by applying to the apparent speed the time value given by the curve of Plate 4. The latter represents a smooth line parallel to the mean tide computed in column 8 of Table B, but lying below these values at the higher speeds, to allow for the increasing slip shown by the slip curve of Plate 5, the effect of which can be computed by a modification of the tide formula attached to Table B. As, however, fractional revolutions are not determined, this refinement is rather chimerical.

Curves of speed, horsepower, and mean effective pressure on revolutions are shown by Plates 5, 6 and 7, and horsepower on statute miles by Plate 8.

Simple indicator cards are given in Plate 9, and their uniformity during each run is shown by Table C.

RIVER TRIAL.

This was a continuous run from Desbrosses street to Poughkeepsie, a distance of 74.21 statute miles as determined by carefully scaling the path of the boat on standard charts. The trip was timed so that the boat carried a flood tide throughout the run. The run was made in the exceptional time of three hours, thirteen minutes and twenty seconds, notwithstanding the speed was handicapped by abnormally low steam pressure over a considerable fraction of the trip and by several slow-downs.

The detailed data are shown in Table D, and also graphically by the Nicholson

log chart, Plate 10. The latter shows very strikingly how impossible it is to maintain a steady speed in a crooked stream like the Hudson river.

Column 7 of the table gives an ap-

proximate indication of the great variation of tide involved in a river trip. For instance, in the narrowest part of the river approaching West Point where the depth (column 14) is over 100 ft., the tide is so strong that the speed along shore (column 8) is 25.42 miles, whereas the true speed as deduced from the progressive trial (column 16), or from the Nicholson log, column 9, is only about 21.5 miles.

unsatisfactory means of determining the true capacity of the boat.


DISCUSSION.

Vice President Stevenson Taylor (in the chair)—It is a great pleasure to receive a paper from Prof. Denton, and we are sorry he is not here himself to present the paper. If there is no discussion upon this paper I would like for the sake of the record to call attention to the fact that the steamer New York, as described by Prof. Denton, is different from the steamer as at first constructed; in other words, there were 30 ft. added to her length, put in at the widest part of the boat, which has changed the result some, but not very materially, when you consider the change in the boat and the greater carrying capacity. The dimensions originally, in 1887, were: Length of hull on water line, 300 ft., now 330 ft.; beam on water line, 40 ft., now 40 ft.; draught from top of keel during tests, 5 ft. 10 in., now 6 ft.; displacement, 1,000 gross tons, now 1,240 gross tons; block co-efficient 0.584, now .56; outside diameter of paddles, 30 ft. 2 in., now 29 ft. 10 in.; diameter to cen-

ter of trunnions, 27 ft., now 27 ft.; width of paddles, 12 ft. 9 in., now 12 ft. 6 in.; dip of paddles, 4 ft. 2 in., standing, 4 ft. 6 in., running, now 4 ft. 5 in.

During the month of May, 1888, over

SAMPLE INDICATOR CARDS OF PROGRESSIVE SPEED TRIALS




a range two miles on the Hudson river, one mile up and one mile back, 22.8 statute miles per hour were traveled, the engine making 30 $\frac{3}{4}$ revolutions per minute, and developed much more power than was developed at the time of Prof.

was a great struggle to get 1 horse-power out of 1 sq. ft. of grate area, but you will see by Prof. Denton's own figures that he has exceeded that, showing 31.25 H. P. developed for quite a period of time on 228 sq. ft. of grate area, making 13.7 H. P. per sq. ft. of grate area, and not having a compound or triple-expansion engine either.

One other point in his paper I think deserves particular attention, that trials of speed, while they may produce sensational records, are not a very satisfactory means of determining the average capacity of the boat. You will see from time to time, as I have for the last thirty years now, a statement of the extraordinary speed of steamers made on the Hudson river, in times gone by, and no steamer at the present time really averages the speed of these other steamers. I think you will invariably find, if you look up the facts, that the steamers made the fast runs under exceptional circumstances, with a strong favorable tide and an exceptionally strong favorable wind. The effort has always been made on the Hudson river to make the steamers fast by selecting particular tides and winds, so that Prof. Denton's comments are particularly appropriate and well worth remembering when you read about the so-called actual speed of steamers in the years gone by.

Mr. J. R. Andrews—I would like to make a suggestion, if it meets with the approval of the members. In view of the very able and comprehensive manner in which the secretary of state, Mr.



NICHOLSON LOG HUDSON RIVER DAY LINE STEAMBOAT NEW YORK.

It also appears that the highest revolutions did not occur during the period of highest steam pressure, and the highest speed of boat did not coincide with the highest revolutions per minute.

These inconsistencies, which are caused by variable conditions of current and channel show that long distance river trials of speed, while affording opportunity for sensational records, are an

Denton's trial. The average of three runs, one run of one mile, and two runs of two miles, was 22.50 statute miles per hour, with 29.66 revolutions per minute, which was a better performance than at present, due, of course, to the same power or greater power and lighter weight. I wish to call your attention to one particularly strong feature of this style of steamboat and machinery. It

Root, has advocated the passage of the subsidies bill, which I think is of great interest to all naval architects, I would like to make a motion that a committee be appointed to draft suitable resolutions of thanks to the secretary, and that something of that kind be engrossed and forwarded to the secretary on this subject. I would like to hear an expression of opinion of the members on this

point, and if they agree with my suggestion, I would like to see something of that kind done before the meeting is closed.

The Vice President—Will you kindly present that at the close of this paper—it is not germane to this subject.

Mr. Andrews—I thought you had finished with the discussion.

The Vice President—I am through, but perhaps the members of the association are not. I will ask the president to resume the chair, as he referred to Secretary Root in his opening speech and is better able to preside during any discussion of that subject.

Mr. G. W. Dickie—Does the lengthening of that vessel account for the unusual position of the wheels?

The Vice President—The lengthening was put in between the boilers and wheels.

Mr. Dickie—Was there any observation made in regard to what effect that had, where the crest of the wave generally occurred?

The Vice President—You will notice, if you compare the figures I gave and the figures given by Prof. Denton, that the wheels have been reduced in diameter, due to that fact.

Mr. Dickie—I did not notice it, but it is important.

Mr. D. W. Taylor—I would like to ask a further favor from Prof. Denton, which would add to the value of the paper for the records of the society. I notice on Plate 10 he gives curves of speed based on depth of water, but apparently that has not been extended into very shallow water. Apparently there is nothing shallower than 40 feet. I refer to the last page of the paper. As this class of steamer frequently runs in shallow water, in fact more often in shallow water than deep water, I think it would add to the value of the paper if some further data were given, if Prof. Denton can supply it, which would connect a little more the revolutions with the depth of the water. That is the only suggestion I wish to make in connection with the paper.

In connection with your remarks, Mr. Chairman, about the speed of the Hudson river boats, as the Mary Powell is referred to in this paper, and we have all heard, or very many of us here have heard so much about the speed of the Mary Powell, I would say that I have had an opportunity in the last year or so of trying a model of the Mary Powell. There is some doubt as to what the lines of the Mary Powell were. I was given the lines of what was supposed to be the Mary Powell and we tried them, and it is true, comparing the results of that model and the results of other river craft, she showed up exceedingly well, perhaps the best

model of that type we have ever tried, which confirms to some extent the popularity of that type of steamboat.

The Vice President—There has not been any doubt of that in my mind. I think it will be very difficult for Prof. Denton to give you what you ask, for the depth of water mentioned, so that you can compare the speed and the depth of water at the same time, on account of the crooked courses followed by the boats in traversing the Hudson river. Is there any further discussion? If not, I think a motion to pass a vote of thanks would be in order.

Mr. Dickie—I move that a vote of thanks be passed to Prof. Denton for his interesting paper. (The motion was seconded and duly carried.)

The Vice President—I will now ask the President to resume the chair.

(President Bowles in the chair.)

The President—Gentlemen, you heard the suggestion of Mr. Andrews, and the matter is open for discussion.

Mr. Dickie—I suggest that Mr. Andrews repeat what he said.

The President—Mr. Andrews, will you be good enough to again lay that matter before us?

Mr. J. R. Andrews—My idea was that it would be fitting for this society to convey a set of resolutions, properly prepared, to Secretary Root, voicing the sentiments of the society on the very able speech made by him at Kansas City before the Trans-Mississippi Commercial Congress. The speech was reported very fully in yesterday's *Sun*, and the reasons which he gives that some assistance should be given the shipowners and shipbuilders in this country are so logical that it seems to me it is a matter of a great deal of interest to this society. Personally I should like to see some notice taken of it. I make this simply as a suggestion.

Mr. Aldrich—Can we not accept that as a formal motion? If so, I second it.

The President—It is moved and seconded that a committee be appointed to draft suitable resolutions for this purpose. Those in favor say aye; those opposed, no. (The motion was carried.) The Chair will announce the committee later. This session will now stand adjourned until ten minutes of two.

A NEW FLOATING WORKSHOP.

A remarkable vessel for the royal navy is, says the *Glasgow Herald*, being fitted out alongside the ship yard of Sir James Laing & Sons, Sunderland. She is the sequel to an experiment made some time ago, when an old cruiser was converted at Portsmouth into a floating workshop, under the name of the *Vulcan*, to attend on a fleet at sea for the execution of re-

pairs. The experiment has evidently been very successful, as the vessel at Messrs. Laing's is specially built for the same purpose on much extended lines. It would, in fact, not be inapt to describe her as a sea-going dock yard, so extensively is she being fitted with shipbuilding and engineering machinery. The men working on her say there is not a machine to be found in a ship yard or marine engine works that is not represented on board. Considerable secrecy has been preserved with regard to the vessel, all the officials concerned in her construction having been sworn under the officials secret act. She was launched without ceremony some months ago, and named the *India Brahma*, a name which might suggest that she was meant for an eastern trader, but her internal fitting is now so far advanced that her purpose is obvious, and she is now officially referred to as *H. M. S. Cyclops*. Externally what most distinguishes the vessel is the number of funnels, and the position of some of these. The latter are to carry the smoke from the foundries and workshops below. The vessel is of 11,000 tons, and her dimensions are: Length, 460 ft.; breadth, 55 ft., and depth, 40 ft. She has huge hatchways leading to decks below almost for her full depth. At the lowest level is a fully equipped foundry, with cupolas, where damaged parts of machinery can be replaced by new castings. The capacity of the foundry is adequate to deal with moderate-sized shaftings. On a higher deck is a boiler shop, where boiler and ship plates can be dealt with, and where there are shearing and punching machines just the same as in a shipyard. Then there are carpenters', blacksmiths', and armorers' shops, fully equipped fitting works, and electricians' and coppersmiths' departments. There is a crane which travels all round the ship, to lift the repairs to and from the works below. The vessel has a large ice-making plant, and a set of gigantic condensers capable if need be of supplying a fleet with fresh water. An important part of the ship is the electricity generating station. All the machines and cranes will be worked by electric motors, and the vessel will be fitted with wireless telegraph apparatus. She will carry a crew of about 300 men, mostly artificers, and is expected to be ready for sea about Easter.

Mr. James J. Gilroy, of South Brooklyn, has the contract to install two new Roberts safety water-tube boilers in Commodore Benedict's steam yacht *Oneida*.

BRAZING.

BY E. A. SUVERKROP.

In spite of the fact that there are hundreds of brazed flanges on the average steam ship it is surprising how few engineers know anything at all about the job. This is no doubt due to the feeling among engineers in general of "every man to his own job." The ability to do a fair job of smith work is no doubt of great assistance to the engineer at times and why should he not be able to do a fair job of brazing? Brazing is considerably easier than smith work. I would undertake to make a good brazer of any intelligent man in from twenty minutes to an hour, but who could make a smith of a man in that time?

I will first take the general principles of brazing under consideration. Brazing is the joining together of two pieces of metal by means of another metal having a lower melting point. It is practically the same as soft soldering excepting that it is done at a higher temperature and the solder or spelter used in an alloy of copper, tin and zinc or copper and zinc instead of tin and lead. The joints to be brazed should be as nearly clean bright metal as the job permits. Grease and dirt are antagonistic to a good job. The parts to be brazed should be securely held in relation to each other, either by pins put through them or by wiring to each other or by other means. The heat applied should also be clean. Hard coal fires are fairly good, a fire of soft coal charred is also good, but perhaps the best is a gas and air blast. Gasoline or oil blast also give good results.

In brazing a flux must be used. Formerly borax in one form or another was the only thing that would do. Some brazers used it powdered, some in crystals, some mixed it with water, some didn't. Some melted it in a crucible; it was then called "burnt" borax. It was then broken to various degrees of fineness according to the individual whim of the brazer, each one of whom would declare that his way of breaking the borax was the prime reason why he produced good work. The drawback about borax is that while it is a good flux it becomes as hard as glass after the job is cold. In this state it is difficult to remove and ruins the hardest file. A better flux than borax in any form is boric (also called boracic) acid. It comes in crystals or powder. I prefer the crystals for some work as the powdered form is apt to curl up and blow away while the crystals do not. Boric acid does not form a hard scale and if you know how to

handle it does not leave any scale; that cannot be almost rubbed off with the hand.

In jointing up ready for brazing the joints need not leave room for the brass to run in. They can be drive-fits, for if the heat and flux and spelter be applied in the right manner the brass will run into the tightest joint. The beginner however, better not fit his pieces too tight; just make them an easy drive fit, put one or more pins in to hold the pieces together.

We will assume that we have a steel flange to braze on a steel pipe. The flange has been bored or filed to fit on the end of the pipe which has also been filed or burned bright, the joint is clean, bright metal to metal. The job should be put in the fire so that the pieces are heated as evenly as possible. In this case we will assume (what is generally the case) that the flange is heavier than the pipe. It stands to reason that it will not heat as quickly as the pipe which is lighter, we therefore heat the flange first, placing it in the hottest part of the fire. While the heat is coming up the brazer applies the flux to the joint with a brazing "spoon." I generally make my brazing spoons out of a piece of $\frac{1}{4}$ or 5-16 inch iron rod of suitable length, say two feet, with the end heated and beaten out flat about $\frac{5}{8}$ -inch wide by $1\frac{1}{2}$ inches long. As the heat increases and the flange and pipe become a dull red the flux melts and runs all over the job, some of it runs into the joint where we want it but the bulk of it is lost. As it is cheap this does not signify. When the job reaches a so-called cherry red, that is to say, a heat at which one would temper a chisel, it is time to put a little spelter on as this heat is very near the melting point of the spelter. The spelter is applied with the spoon together with more flux and is guided into the top of the joint by the spoon. In a few moments the brazer will notice that the spelter has begun to flow and run about all over the joint almost the same as mercury. The heat is kept on a little longer, say a minute or so according to the size of the job, while more spelter and flux is applied. The job is then lifted from the fire, being handled carefully so as not to jar it, and while still red hot the flux is brushed off with a steel brush. This treatment applies especially when borax is used as it eliminates a good deal of hard work later. The job is then allowed to cool till it is at such a temperature (a dark red) that immersion in water will not harm it. It

is then put into a saturated solution of sal soda water or strong soap water. When cool the scale is easily brushed off, leaving the steel and brass clean and bright.

The spelter to be used varies according to the material on which it is to be used. On steel any kind of brass can be used, as the melting point of any brass is below that of any steel. I have also brazed steel with copper when no brass was at hand.

For brass and copper a soft brass with a low melting point must be used and great care must be exercised in order to avoid melting the job itself, especially so if it is brass, as the chances are that there may not be much difference between the melting points of the job and the spelter.

It is often desirable to repair a piece of cast iron that has been broken. A great number of very good brazers assert that cast iron cannot be brazed, and an equally large number of people having some patent process or another assert that it can but only by their particular method. Both are wrong. Cast iron can be brazed with common brass and common borax or boric acid. There is no mystery about it. The joint should be thoroughly clean, the pieces should be firmly pinned together so that they cannot alter their position with relation to each other, the heat should be applied slowly and steadily while plenty of flux and spelter are applied and the job should not be hurried in any way. Let the job stay in the fire for a long time, to use a blacksmith's phrase, "Let it soak in the fire." A braze made in this way will be just as good if not better than one made by any of the patented or secret (?) processes.

A DISCOVERY THAT WILL STARTLE THE ENGINEERING WORLD.

M. W. H. Hunter, engineer of the Manchester Ship Canal Co., in his inaugural address as president of the Manchester Association of Engineers, spoke of a new relation between engineering and the general community. He also alluded to a new and important source of energy, and concluded: "I speak with some measure of confidence when I say that it is possible that at no distant date the engineering world will be startled by the revelation of a discovery relating to motive power of such sort and of such far-reaching consequences, that if I were permitted to describe it to you, you would agree that it may of itself go far to establish the proposition which I have submitted to you this evening."



DEVOTED TO EVERYTHING AND EVERY
INTEREST CONNECTED OR ASSOCIATED
WITH MARINE MATTERS ON THE
FACE OF THE EARTH.

Published every Thursday by

The Penton Publishing Co.

CLEVELAND.

BOSTON	NEW YORK
DULUTH	PHILADELPHIA
CHICAGO	PITTSBURG
CINCINNATI	

*Correspondence on Marine Engineering, Ship
Building and Shipping Subjects Solicited.*

Subscription, \$3.00 per annum. To Foreign
Countries, \$4.50.
Subscribers can have addresses changed at will.

Change of advertising copy must reach this office
on Thursday preceding date of publication.

The Cleveland News Co. will supply the trade
with the MARINE REVIEW through the regu-
lar channels of the American News Co.

European Agents, The International News Com-
pany, Breems Building, Chancery Lane,
London, E. C. England.

Entered at the Post Office at Cleveland, Ohio, as
Second Class Matter.

December 6, 1906.

PRESIDENT ROOSEVELT ON AMERICAN SHIPPING.

(Extract from his annual message to Con-
gress, Dec. 4, 1906.)

"Let me again call the attention of the congress to two subjects concerning which I have frequently before commu-
nicated with them. One is the question of developing American shipping. I trust that a law embodying in substance the views, or a major part of the views, expressed in the report on this subject laid before the house at its last session will be passed. I am well aware that in former years objectionable measures have been proposed in reference to the encouragement of American shipping; but it seems to me that the proposed measure is as nearly unobjectionable as any can be. It will, of course, benefit, primarily, our seaboard states, such as Maine, Louisiana and Washington; but what benefits part of our people in the

end benefits all, just as government aid to forestry and irrigation in the west is really of benefit, not only to the Rocky Mountain states, but to all of our country. If it prove impracticable to enact a law for the encouragement of shipping generally, then, at least, provision should be made for better communication with South America, notably for fast mail lines to the chief South American ports. It is discreditable to us that our business people, for lack of direct communication in the shape of lines of steamers with South America, should in that great sister continent be at a disadvantage compared to the business people of Europe."

A DESERVED REBUKE.

For years there have appeared in the newspapers of the country items foretelling the intention of Congressman Burton to "fight the ship subsidy bill." He has been held up as the bugaboo man to the friends of American shipping, as the dragon for whose advent we must "watch out!" Congressman Burton seems to have enjoyed the prominence his foretelling has given him, and to have reached the conclusion that the fate of the shipping bill was in the hollow of his hand. THE MARINE REVIEW cannot have it understood too plainly that we concede to Congressman Burton a perfect right to oppose the passage of any measure that he deems against public policy, inclusive of the ship subsidy bill. It is his privilege, too, which we do not wish to deny him, but which, on the contrary, we are perfectly willing he shall indulge himself in to the limit, of exploiting his opposition to the shipping bill however and whenever he chooses. We only say that, in going out of his way to announce for years in advance of the consideration of such a measure in congress, at least in the house of representatives of which he is a member, his opposition to it, he invites attention from its friends and advocates which the ordinary congressman would not receive. In the case in point on last Friday Mr. Burton announced in an interview published in the *Washington Post* his unalterable opposition to the shipping bill, saying, "I am against the bill, as I always have been, and will oppose it as vigorously as I can."

The attention of Senator Gallinger was called to the above quoted statement upon his arrival in Washington on the day of its publication, and he was asked if he had any comment. He did. And his comment was equally as explicit as that of Congressman Burton's. He pointed to the fact that Mr. Burton, as chairman of the rivers and harbors committee of the house of representatives, was seeking to secure the passage of a river and harbor improvement bill involving the expenditure of about \$75,000,000, a measure that would have to run the gauntlet of the senate committee on commerce which favorably reported the shipping bill that passed the senate last winter. That in that committee the proposed river and harbor improvement bill would receive the closest scrutiny. Announcing himself as a friend of river and harbor improvement, Senator Gallinger, who is a member of the senate commerce committee, stated that "there is no logical reason why we should continue to spend hundreds of millions of dollars on our rivers and harbors, largely for the benefit of foreign shipping interests, and refuse to appropriate a dollar for the rehabilitation of the American merchant marine." This serves notice upon Mr. Burton, and his friends, that if further large outlays are to be made for deepening our channels, American-built ships, protected against the subsidized foreign competition which has driven them from the seas, must be aided by our government to use them.

It was time that Mr. Burton realized that his committee on rivers and harbors is not "the whole thing," as one might imagine that it was from the frequency and extent of the space he as its chairman has received in the press. It is worth while to remember that that veteran champion of American shipping, Senator William P. Frye, is the chairman of the senate commerce committee, to which the river and harbor improvement bill is referred. With Senators Frye and Gallinger on watch, aided by the support and sympathy of the other members of the senate commerce committee, it is quite time that the American side of river and harbor improvement was announced in order that it may receive due consideration. Senator Gallinger's statements will come as

a relief to the country at large, and prove to be most interesting reading, we doubt not, to Congressman Burton.

DEBATING SHIP SUBSIDIES.

In a circular issued by the state superintendent of public instruction of the state of Washington, addressed to the accredited high schools of the state, we learn that the subject of subsidizing our ships will be debated to a finish by the debating teams of each of the thirty-one high schools of that commonwealth. Following is the proposition: "Resolved, That the best and most practicable method of upbuilding the American merchant marine is the system of subsidies to American-built ships." On Dec. 15 the first debate begins. The winning teams must hereafter again debate the proposition with each other, until one team is triumphant. During the course of the debate it is expected that the winning teams may be compelled, a number of times, to take both the affirmative and the negative side of the question. A public-spirited citizen, whose name is not announced, has offered a prize of \$100 for the best debating team, and another prize of \$50 for the best debater, in the contest. The committee in charge of the contests is Prof. A. R. Priest, of the State University, Prof. Charles Timblin, of the State College, and Prof. J. H. Morgan, of the Ellensburg normal school. Copies of the circular may be obtained by addressing Hon. R. B. Bryan, superintendent of public instruction, Olympia, Wash.

Doubtless these debates have been stimulated by the offers of the Merchant Marine League, of Cleveland, O., of \$1,000 in four prizes for the four best essays on how to build up our shipping in the foreign trade. League officials inform us that the demand for literature and documents from the state of Washington is unprecedented. A few weeks ago we stated that the entire class in economics in one of the state colleges were contestants for the Merchant Marine League's prizes, and now the entire state's high schools are to discuss the subject to a finality that should leave but little to be said.

We confidently predict the victorious affirmation of the proposition.

FREIGHT SITUATION.

The lake season is closing practically featureless. Weather conditions moderated at upper lake ports during the early part of the week, making the loading of ore somewhat easier than last week. Owing to the domination of the contract system the ore rate has remained practically stationary throughout the season and there is little doubt but that the rate of 75 cents from the head of the lakes, 70 cents from Marquette and 60 cents from Escanaba will be the prevailing rate next year. In fact, some shippers have already closed their business for next year upon that basis and undoubtedly before the year is out all the leading shippers will have entered into contracts.

The ore shipments for November were 3,734,067 tons, making the total movement up to Dec. 1, 36,973,002 tons. As this is only a few cargoes short of the 37,000,000-ton mark, the total shipments for the year will probably be about 37,300,000 tons. With the all-rail shipments added, the total movement may reach 38,000,000 tons.

Coal rates for the first week in December were advanced 10 cents to the head of the lakes. The grain trade advanced to 2 cents, but the amount available is not large. Following are the grain shipments from Duluth last week:

Receipts.		Shipments.	
Dec. 1.	Nov. 24.	Dec. 1.	Nov. 24.
Wheat, 2,246,364	2,060,765	2,672,592	2,020,897
Corn,
Oats, 68,975	6,737	176,533	94,950
Barley 488,524	548,748	741,200	923,222
Rye, 18,420	16,839	28,349
Flax, 1,304,985	106,840	734,450	1,557,365

MARINE INSURANCE SEASON.

According to one of the most prominent marine underwriters, the lake business this past season has been a losing one. For one cause or another, he says, the vesselmen have looked to the underwriters to pay for everything, and the natural result is that this has been the case since the Zimmerman-Saxona collision right down to the loss of the Theano, the sinking of which means another \$150,000 in the loss column.

The heavy losses have been added to by the abrogation of the insurance clause known as the "deductible average." Where there was an incentive before to keep vessels off the bottom and out of harm's reach, the knowledge that the boats would not have to pay for any part of the damage has had a demoralizing effect. At least this is what may be inferred from the talk of the underwriters.

Just how the insurance men abrogated the deductible average is an interesting story, the main feature of which is hard competition. It appears that the foreign companies led

the van by doing away with the clause, and in order to get a fair share of the business, it seems that the domestic companies had to follow suit or get lost in the race for business. But this is only one feature.

According to the underwriters, the deductible average was the best safeguard the vesselman has ever had, principally because the boats are not insured against loss of time while in dry docks; with the average to think of, extraordinary care would be used in operating a boat when slight damages would necessarily come out of the boat itself, without it, the underwriters say; but the profits of a season are eaten into when a boat is docked, even though the wear and tear on the boat is paid from the insurance, as does not always happen when the crew is shown to have been overzealous.

That the owners have reached the limit in size is the firm opinion of many of the marine insurance men. For this reason, it is stated the next evolution will be a thorough study of permanency, durability, safety in construction and skill in management. Experience along these new lines, it is declared, may show the owners that the present leviathans are not needed, that they are really too big. It may also result in bringing the business back to its normal state.

Just what causes so many accidents the underwriters are not prepared to state, but it is a significant fact that one man in figuring over collisions, said he could not recall any instance where boats came together from any unavoidable cause. Urging its force strongly, this same man declared the late W. B. Robinson, supervising inspector, spoke truly when he said captains should be punished by imprisonment instead of loss of their license when avoidable collisions occur.

An overamount of zeal to outdo the other fellow is acknowledged to be the cause for numerous accidents, and so long as the underwriter pays, there has never been much worry. The captains say they are not to blame because their owners haul them over the coals if they do not make fast time and keep even with the other fellows, or more often ahead of them. But the underwriter says this is poor policy, because boat property rapidly depreciates and should be protected on the theory that it is more valuable when in operation than in dry dock or at the bottom of the lake. In thinking of their immediate benefit, the vesselmen lose sight of their prospective disadvantage.

"In The Merchant Service."

Fire-and-boat drill was over on the Hamilton, and the crew had dismissed to their quarters.

The engineers had foregathered in the Third's room, and were sprawling about in the usual attitude of reckless abandon, which denotes the fact that the owner of the room is busy elsewhere. The Third was having seven-bell lunch.

time, and fire-drills were just coming into force.

"Our skipper, a very dignified little man, not long in command, hailed with delight the order from the office to have fire-and-boat drill every Sunday morning at sea—weather permitting, of course.

"He intended making an event of it.

"Well, we sailed in due course, and the

parade, and a more piratical looking crew never shipped across the 'Western.' I guess they must have had a tarpaulin muster, on a share-and-share alike basis.

"Some little time before the drill came off, Graham made the necessary preparations below, opening up the usual deck connections on the pump.

"I say *the* pump, as we were not so lavishly provided with pumps then as we are today, and our donkey had to fill the bill as sanitary, bilge or deck pump as occasion required.

"Now, after setting the pump all ready for action, Graham went out to the fire room to hustle along the already hustling watch. Perhaps he was a couple of points behind—he usually was.

"But the Junior on watch, Brown, was having trouble with his bilges, and, fearing the gradual accumulation of water in his wells, *he* set the pump ready for bilge work, if necessary.

"Thereby hangs a tale.

"The passengers got wind of the fact that a muster was coming off, and had collected on the promenade deck under the bridge, prepared to take a lively interest in the proceedings. Any break in the monotony of the trip was welcome.

"Below on the main deck, the sailors were lined up with a couple of hoses, our gang manning the geared pumps on deck.

"Under the fo'castle head, the doctor and some of the other auxiliaries had their quarters, and when their doors were closed, a large expanse of beautiful white bulkhead was exposed to view. Against this bulkhead it was decided to play the hoses, for effect, you understand.

"When the eventful moment arrived, the stewards appeared on deck armed with fire hatchets and buckets, and a 'hush of expectancy fell on the throng.'

"Suddenly the alarm bell rang out—away down below could be heard the tinkle of the telegraph, and immediately after the faint beat of the fire pump.

"'Here she comes,' sang out the bo'sun's mate. The sailors took a deep breath and a firmer grip. The hoses squirmed and stiffened out as the water arrived—a magnificent flow of muddy-brown bilge extract, interspersed with portions of grease and coal dirt.

"If I remember rightly, there was also a smell.

"For a few seconds everyone just gaped, till the spell was broken by the bo'sun's mate dropping the nozzle of the hose. His action was followed with great promptitude by the sailors supporting him in the rear.



LINED UP.

They were discussing in a leisurely manner the late drill, each man having some caustic remarks to make on the various crews of their numerous boats—barring his own, of course.

It was no occasion for the characteristic argument, so, when the Second smiled reminiscently, and displayed other symptoms of having another of his yarns to spin, he found an attentive audience.

"Talking about fire-drills," he commenced, "I will never forget the first fire-drill it was my painful duty to take part in.

"I was on the old East Indian at the

eventful Sunday arrived, bringing with it all sorts of preparations for the successful carrying through of the drill at ten o'clock.

"The Third, Graham, was on watch at that time, so I had the task of rounding up the boiler-room gang to muster. Our 'Old Man' had a preliminary inspection down in the fo'castle, and a motley bunch our crowd looked when lined up.

"The company hadn't raised the firemen to the dignity of a uniform then, so they had rigged themselves out in the best their kits contained. All sorts of jumpers, guernseys, and caps were on

"The hose on hitting the deck took charge, and proceeded to deliver a 30-ft. stream of bilge water to all the points of the compass in as many seconds.

"Some of the more daring deck hands tried to regain possession of the nozzle by stealthily pouncing on it from the rear, but the hose was having the time of its life and absolutely refused to be knelt on.

"The other hose, meanwhile, was hoisted over the rail and allowed to waste its sweetness on the nautical desert air.

"The Chief, just as soon as he recovered from his surprise, started aft in a kind of dignified hurry to where the old pump was getting in its deadly work. I stayed behind to keep a wary eye on our gang, as their expressions of deep melancholy foretold the preliminary canter of their risible faculties.

"Diving through the engine-room door, the 'old man' leant over the rail, and shaking his fist at Graham, who was peering up through the gratings from below, yelled in a voice choked with emotion for the pump to be stopped.

"Graham, seeing his violent gesticulations, and not having received the pre-arranged signal to stop the pump naturally enough concluded that more pressure was wanted on the hose.

"Running round to the back of the engine room, he gave the old pump full steam and 'let 'er rip.'

"Then the Chief, having seen the Third run round to the pump, hurried forward again, panting with the unusual exertion.

"Instead of finding the trouble past, as he expected, he found the passengers and crew watching from various places of refuge the efforts of a solitary sailor trying to drag the writhing hose to the rail.

"He gave one gasp and stopped short on the deck, and I am also afraid he said 'damn.'

"Then I started off to the engine room through the flying spray. When I reached the starting platform I found Graham anxiously watching the pump, which was rocking back and forth with tremendous efforts, his hand on the steam valve. We shut her down and swapped explanations.

"On deck the hose gave a last dying wriggle, and straightened out flat on the deck. Its work was done.

"Then the passengers crept cautiously forth to gaze on the scene of devastation, and we chased our men, who were laughing uproariously, to their quarters.

"The sailors were turned to, to remove what traces they could of the bilge discharge from the bulkhead, rigging and deck.

"Of course, the Third appeared in due time 'on the carpet,' and the following

facts were brought to light:

"As I told you the pump was originally set with sea suction and discharge to deck open. Brown altered it to bilge suction and discharge overboard, without mentioning the matter to Graham.

"Graham passing the pump a few minutes later noticed the discharge, and mildly astonished at his (as he thought) blunder set the discharge for the deck.


"Our first fire drill was a rank failure as a fire drill, but as a never-ending

peared on deck carrying a borrowed oil-skin coat and a huge umbrella; the idea!"

THE "STAND-BY" MAN.

METEOR AT SEA.

Chief Engineer A. R. Powell, of the Phoenix Liner St. Andrew in describing the meteor sighted at sea on their west-bound voyage said: "I was on deck at sunset, standing abaft the engine room, when the meteor was sighted. There were two or three



TROUBLE WITH HIS BILGES.

topic of conversation and unseemly jest it was a huge success.

"The following Sunday we had another trial, and this time pulled it off without a hitch. I am afraid that this fact rather annoyed the passengers, who had mustered in full force on the promenade deck, even to the lame and the halt.

"Probably they expected a repetition of the previous drill, at any rate they were doomed to disappointment.

"The skipper and the 'Old Man' had made up their minds that there would be no hitch this time, which in all likelihood accounted for the glare the skipper gave one jovial passenger who ap-

members of the crew in my vicinity at the time, one of them drawing my attention to the 'stream of fire,' as he called it.

"It was falling with great velocity, and by the erratic course of the tail of fire in its wake was probably disc shaped. I can only guess at its tremendous size by the commotion made on plunging into the sea, when it took the water about a mile and a half off our port beam. Of course, if it had been nearer, I would have been better able to judge, but it was quite near enough to satisfy any curiosity I might have had on the matter."

AROUND THE GREAT LAKES.

The Detroit & Cleveland line declared the usual semi-annual dividend of four per cent, payable Dec. 15.

The Canadian steamer Turret Crown missed the harbor of refuge in the storm at Grand Marais last week and went on the beach.

The harbor committee at Holland, Mich., has inspected the piers since the last severe storm and find that a new north pier is necessary.

The Toledo Ship Building Co. will repair the vessels Simon J. Murphy and the Harvard, of the Pittsburg Steamship Co.'s fleet, during the winter.

The directors of the Detroit & Buffalo Steamboat Co. have declared a dividend of five per cent, payable Dec. 15, making eight per cent for the year.

The steamer Tecumseh, released from the south passage Lake Erie by the tug Home Rule, is at the Ecorse yard of the Great Lakes Engineering Works for repairs.

The schooner Queen of the Lakes, owned by Richardson & Son, Kingston, Ont., sunk opposite Sodus Point last week, the crew taking the small boats as she went down.

Capt. Harris Baker, of Detroit, who purchased the hulk of the steamer Fisk, which burned near Beldore's six weeks ago, will begin the work of recovering the wreck at once.

The steamer Conestoga, rebuilt at the Ecorse yard of the Great Lakes Engineering Works for the Crosby Transportation Co., has left for Lake Michigan with a cargo of salt.

The steamer Mataafa, which was wrecked in the big November gale a year ago off Duluth, has been floated out of dry dock. She will not, however, go into commission this year.

The Great Lakes Towing Co. has succeeded in lightering the cargo of the wrecked steamer Conemaugh, ashore off Pelee island. The cargo of dry goods was valued at over \$50,000.

Capt. James Davidson has announced that the steamer Panama which was driven ashore near Ontonagon about a week ago has been abandoned as a total loss. She carried no insurance.

The steamer Northern Queen, bound for Duluth with a cargo of general merchandise, ran on Point Abbey during a heavy storm. Her forward compartments are reported full of water.

Several well known mariners got together in Buffalo recently and organized a new society which will exist during the time that they lay up their boats. The headquarters is to be known as 'Grand Marais.'

The steamer Chisholm was released from the bank near the county building at Houghton after 30,000 bu. of her cargo of grain had been lightered. Later the

grain was reloaded upon her, as she had not been damaged.

Capt. Cyrus H. Sinclair, representative of the underwriters, has returned from the wreck of the Conemaugh on Pelee island, and is of the opinion that the boat can be floated and saved if the work is done right away.

While the stern of the car ferry Ash-tabula was raised so that repairs could be made to her propeller wheel, several cars loaded with coal broke from their fastenings and did considerable damage at the forward end of the boat.

The Port Huron Contracting Co., Port Huron, Mich., successors to the Port Huron Ship Building Co., is reported as about ready to resume operations at the old yards on Black river and will build dredge hulls.

The two steamers building at the Bay City yard of the American Ship Building Co. for the Gilchrist Transportation Co., of Cleveland, will be named after Gen. George Garretson and Henry P. McIntosh. The Garretson will be launched on Dec. 22.

While bound from Ludington to Manitowish, the rudder chain of the steamer Pere Marquette No. 6 parted when the ship was abreast of Point Sable and she narrowly escaped running on the Leach. She was taken to Ludington for repairs by the aid of a hand steering gear.

The crew of the steamer J. L. Weeks re-christened her at Buffalo about ten days ago, giving her the euphonious name of "Two Weeks." The reason for this was that the boat was held in port for about two weeks at the American Mailing Co.'s new plant above the Ohio street bridge.

President Livingstone, of the Lake Carriers' Association, has received a dispatch from the Canadian minister of marine at Ottawa stating that the wishes of the Lake Carriers in respect to the Bar Point gas buoy will be complied with and the buoy will be allowed to remain until the boats stop running.

Twenty loaded freight cars broke loose from their fastenings on the Ann Arbor car ferry No. 1 this week while the ship was being tossed in heavy seas. The crew had hard work to keep the cars from being dumped into the lake, and as it was several thousand dollars worth of damage was done. The car ferry was bound from Manitowoc to Franklin.

A meeting of masters of lake vessels was held in the Duluth office of the Pittsburg Steamship Co. on Monday last to discuss aids to navigation with a view to reporting such suggestions as they might agree upon to the Lake Carriers' Association. Their recommendations will be embodied in a report which

the Lake Carriers' Association will make to the general government.

The dredge constructed for the Empire Engineering Co., of New York, by the Manitowoc Dry Dock Co., Manitowoc, Wis., is enroute to its destination in tow of the steamer Parks Foster. A stop was made at Detroit to pump out water which had found its way into its hold, owing to the heavy sea encountered in Lake Michigan. She will be taken apart for towage through the Erie canal.

The tug James R. Sinclair was launched from the repair yard of the Great Lakes Towing Co. on the Chicago river on Saturday last and was marked by two unusual events, the first that she was launched stern first instead of sideways, as is the ordinary custom on the lakes, and the second that she was christened by a man. It was intended to have Mrs. Sinclair name the new boat, but owing to illness the tug was named by her son, Cyrus H. Sinclair. The tug is 68 ft. long, 17½ ft. beam and 11½ ft. deep. She is the first steel craft ever to be built on the Chicago river.

The steamer George W. Peavey, which became disabled in the Detroit river, reached Buffalo recently and was taken in tow by two Great Lakes tugs. She will be put in No. 1 dock at the plant of the Buffalo Dry Dock Co. There is not much time left in which to make repairs, but it is safe to say that she will undoubtedly be rushed for another cargo, at least. The dry dock company is making quite a reputation for itself in this respect. John A. Weisbeck will represent the owners in the survey to be held on the Peavey when she is put in dock.

That the entrance to the harbor of Duluth is unsatisfactory from the vessel standpoint was again emphasized last week when the Anchor liner Susquehanna struck the bottom in the heavy sea that was running. Her stern struck the bottom in the trough of one of the big waves just as she was fairly between the piers and as a result control was lost for a very brief time, during which she hit the south pier with her stern and later the north pier with her bow. Fortunately the Susquehanna was not appreciably injured, but the incident was potential in revealing the possibilities of grave danger. Mr. Harry Coulby, president of the Pittsburg Steamship Co., happened to be in Duluth at the time and declared that the Duluth ship canal ought to be closed and a wider and more centrally located one cut through Minnesota Point with a V-shaped breakwater inside the bay.

The two lake-built steamers Minnetonka and Minnewaska, which were bought in by the American Ship Build-

ing Co. from the American Steamship Co., for whom they were originally built, and which were sold by Mr. J. C. Wallace, of the American Ship Building Co., to the United Steamship Co., of San Francisco, organized by Arthur Hill, of Saginaw, and James Jerome, of San Francisco, have been renamed Santa Maria and Santa Reta. They were built on the lakes for salt water service and were towed through the Canadian canals in two sections. After they were sold to the United Steamship Co. they were remodeled at Newport News into oil tank steamers and were chartered to the Union Oil Co., of San Francisco, for a period of ten years to carry oil to the Panama canal. The interesting point about these two steamers at present is that the Detroit Trust Co. is trustee for an issue of \$200,000 worth of bonds upon these steamers. The issue is well secured, however, as it is understood that the earnings under the charter will amply repay both principal and interest and yield a satisfactory dividend as well to the stockholders of the steamship company.

NAVIGATION OF STEAM VESSELS.

United Harbor No. 1, American Association of Masters, Mates and Pilots, held open meetings at the Teutonia Assembly rooms, New York city, on the afternoon of Monday, Nov. 12, 1906, and evening of Tuesday 13th inst. The object of the meetings was to discuss the laws governing the navigation of steam vessels and explain the difference between the construction placed on the laws by the steamboat inspection service, and the customs followed by licensed officers in the navigation of their vessels, and make recommendations, if possible, for amendments to the different laws governing the navigation of steam vessels. It was also hoped that these meetings would promote a more friendly feeling between the licensed officers, superintendents, and owners. The meetings were well attended, there being a large muster of association men. There were also several owners and superintendents interested in the work of the association, among the audience.

The meeting room was decorated with the great flag and bunting of the association, and at intervals an excellent musical program was discussed, the utmost good feeling prevailing.

Mr. Irvine B. Grace and Capt. Luther B. Dow were in the chair. Capt. John C. Sylvia, president of the association, gave a brief history of the organization, spoke on the duties of the licensed officer, and said a few words in praise of the local steamboat

inspection service. Captain Luther B. Dow, general manager of the association, spoke at some length on the increasing traffic in the harbor of New York, and the difficulties experienced in endeavoring to follow out the rules under certain circumstances. Some of these rules, made law by congress when steam-boating was still in its infancy, are impracticable now, and particularly so in the busy harbor of New York. On the great lakes at present, they have certain benefits denied the sea ports.

Supervising Inspector General George Uhler gave a brief history of the laws governing the navigation of steam vessels, and the introduction of the bells, lights, and steam whistles system of signaling. He spoke of the tremendous traffic on the great lakes, and the increase in the number and size of ships there in the last five years. There, also, they are having increasing difficulty in endeavoring to abide by the rules laid down in by-gone years, when ships were small and fewer of them.

Mr. U. Irvine Coones spoke briefly on shipping and commercial interests coming under his notice as a marine underwriter, his experience dating back to the old fast clippers and wooden-hulled steam boats.

Capt. Ira Harris read a paper of general interest to the members and visitors, and advised licensed officers that it is better to endeavor to live up to the existing rules than have none. He spoke in praise of the good work of the association, saying that the value of these meetings was recognized by the secretary of the department of commerce and labor.

Mr. N. L. Cullen, vice president, spoke on the good work accomplished by the association since its commencement, and advised the continuance of the good feeling among licensed officers in the performance of their duties in the harbor of New York.

Captain H. O. Nicholson, marine superintendent, spoke briefly to members on the rules of the road.

One of the events of the evening meeting was the presentation of a magnificent loving cup to Captain Dow, as a token of the deep regard and brotherly love of United Harbor No. 1.

BATTLESHIP BUILT IN JAPAN.

Tokio, Nov. 15.—The first-class battleship Satsuma was launched today in the presence of the emperor. The greatest enthusiasm was manifested. The newspapers here reflect the epoch-making nature of the event, as indicated by the unprecedented presence of the emperor, and eulogize the

success of the naval constructors. It is taken for granted that the vessel is the equal of and perhaps superior to anything afloat.

The keel of the Satsuma was laid on May 15, 1905, so that she has taken a good deal longer to build than the British Dreadnought. The greatest secrecy has been maintained in regard to this, the largest battleship in the world. Japan did not even admit that a battleship was being built in a Japanese yard, though it is now known that another vessel like the Satsuma is in course of construction, and that two even larger vessels are planned.

According to unofficial reports the Satsuma is 482 ft. long, has 83½ ft. beam, and has a tonnage of 19,200. The tonnage of the Dreadnought is 18,000, but the British battleship is 500 ft. long.

The armament of the Satsuma is to consist of four 12-in. guns, twelve 10-in. guns and twelve 4.7-in. guns. She is to have a speed of nineteen knots. The Dreadnought carries ten 12-in. guns.

The Satsuma is the first battleship built in Japan. Various lessons learned in the recent war have been utilized in her construction. She was built by Japanese labor exclusively.

ARMORED CRUISER CALIFORNIA'S TRIAL.

San Francisco, Nov. 18.—Sirens on the new armored cruiser California sounded all the way along the water front as the fine vessel was returning from her official government trial at sea, announcing that the warship had made a record worth talking about. The California went direct to an anchorage off the Union Iron Works. She had left the spot soon after 8 o'clock in the morning, proceeding to sea and taking a course that extended perhaps forty miles to the westward.

The California was required to make an average of 22 knots an hour for four hours. She did better than this, having averaged 22.22 knots. The highest speed attained was 22.32, and this was kept up for a period of fifteen minutes during the run. A heavy swell prevailed, which probably prevented the cruiser reaching a higher mark of speed. But her average of 22.22 is nearly a quarter of a knot better than is required, and places the California in the class of very successful armored cruisers.

Fred A. Gardner, chief engineer of the Union Iron Works, who was on board during the run, expressed himself as highly pleased with the vessel. There were no accidents during the trial and the machinery worked perfectly.

THE SULZER-DIESEL REVERSIBLE COMBUSTION MARINE ENGINE.

We here give an illustration of the reversible Sulzer-Diesel marine engine of 100 H. P. exhibited in the section for marine and river transports of the Milan Exhibition, 1906. The excellent results which have been obtained with stationary internal combustion engines have made it desirable to introduce same for ship propulsion purposes. Typical ma-

ers and gas producers. The engine room may thus be one-third smaller than for steam plants. Again, when the engine does not work, no stand-by losses need be taken into account.

Among the oil engines it is claimed that the Diesel engine excels by using heavy and cheap mineral oils or residues which cannot be utilized in other engines. The liquid fuel is supplied directly by the combustion cylinder, where it is ignited by means of highly com-

have been working for weeks without stopping, and with the even loads under which marine engines work no difficulty is expected from this quarter.


One great advantage of the Diesel engine is its constant readiness. It can easily be started up in two or three minutes without any preliminary manipulations being required.

So far the Diesel engine has mostly been built as a four-stroke engine, consequently its cylinder dimensions are considerably larger than those of a double acting steam engine of the same output. The comparison does, however, not come out quite as unfavorable for the Diesel engine as at first sight one might be led to believe. The average indicated pressure in the Diesel engine is about twice as high as in a modern steam engine, and even taking into consideration the ten or twelve per cent higher efficiency of the double acting steam engine (against the four-stroke engine) the average effective pressures are still higher for the latter (1.8 against 1). For the same speeds the respective cylinder volumes work out at $1 : 1.4 = \text{about } 1 : 2\frac{1}{4}$.

The Diesel engine can be built on the two-stroke principle and does not in any way imply reduced thermal or mechanical efficiency. Its cylinder volume is only about ten or fifteen per cent larger than for steam engines of the same output. Of course, the weight of the fly-wheel of the internal combustion engine must be added, but this, again, is considerably smaller for the two than for the four-stroke engine.

The dimensions of the connecting rod, the shaft and frames are greater for Diesel engines than for steam engines, the combustion pressure being higher than the corresponding initial steam pressure. But even allowing for this, as well as for the weights of the injection and starting vessels, the total weight of the Diesel engine equipment is considerably smaller, owing to the absence of the condensing and boiler plant, feed pumps, forced draft, and ash hoisting devices. In ships of the same dimensions and speed when driven by Diesel engines the advantages are: (1) reduction in the weight of machinery; (2) reduction in the weight of fuel; (3) reduction in the size of the engine room and tank rooms. The result is that ships can be built with finer lines, which, again, reduces the output required of the engines, or gives the ship a higher speed with lesser weight of the tanks, and with higher speed the radius of action can be considerably increased.

To fully utilize all the above advantages, it is necessary to build the Diesel engines on similar lines as marine steam engines, that is to say, it must be made



SULZER-DIESEL REVERSIBLE COMBUSTION MARINE ENGINE.

rine engines with the propeller direct-coupled to the engine and which can be reversed and controlled like a marine steam engine have, however, so far not been heard of. Further, the combustion engines are far ahead of the steam engines with regard to fuel consumption. For the same output the weight of fuel is, in the case of gas and oil engines, one-third to one-half, and in the case of the Diesel engines one-fourth to one-sixth of what it would be for steam engines. The combustion of the fuel in the cylinders of internal combustion engines can be made so complete that the exhaust gases are practically invisible, a great point, especially for the navy, where the smoke when running the steam engine under heavy overloads must be considered as a great disadvantage. A further advantage is the easy and speedy way in which the liquid fuel can be taken on board by means of centrifugal pumps or compressed air, likewise the transport from the tanks to the engines by the same means is as simple and clean as possible. The liquid fuel can be stored in ballast tanks or between double bottoms. Besides the reduction in weight and space required for the liquid fuel as against coal, the weight taken up by the machinery is considerably less, owing to the absence of boil-

pressed air of high temperature. The quantity of fuel required to give a certain output can be exactly regulated, which is not the case with suction gas plants. If the fuel supply to the cylinder has once been adjusted, it is quite independent of the engine driver, and in no way affected by the temperature of a gas producer or a carburetter.

The reliability of the ignition is, ensured through the compression taking place regularly in the working cylinder itself, whereas in the internal combustion engines it is effected by means of electrical or tube ignition. Further, there is no sudden increase of pressure during the ignition period; the combustion takes place at constant pressure, and as the compressed air and liquid fuel are taken to the cylinders separately premature ignition is avoided and the reliability of the engine considerably increased. The flashing point of the Diesel engine fuel is so high that danger from explosion or fire need not be taken into consideration, nor are there any poisonous gases, as, for instance, in the case of gas producers. Again, the combustion in the Diesel engine is so complete that it is not necessary to examine the cylinders, pistons and valves. There are said to be Diesel engines, which under varying loads

reversible. With a few exceptions nearly all gas and oil engines hitherto used for driving ships were of the non-reversible type, working in connection with a reversing clutch or reversing propellers; the few reversible engines, mostly of the four-cycle type, which have been brought upon the market, had to be provided with six to eight cylinders, all



so endangering the engine itself. The uncoupling, together with the reversing motion, further, requires a comparatively long time, and the propeller itself is not under the driver's control during this time. The transmission of power through friction couplings is not always reliable, and it is out of the question for larger engines and the same ap-

QUALIFICATIONS OF MARINE ENGINEERS.

The board of trade, says the Glasgow Herald, have under consideration at the present time suggestions which they have solicited from some of our engineering associations regarding the provisions of a new bill to regulate the certificates of competency of sea-going engineers. It is a general recommendation that qualifications for a third-class certificate should be stated in the bill, and that first or second class engineers should have served an apprenticeship of a nature previously set forth. The third class certificate as engineman should be granted after service at sea of not less than two years as stoker, and not less than two years as greaser or donkeyman; and a good general knowledge of the working of engines and boilers should be shown by means of examination. A certificated engineman should not be eligible for a certificate as first or second engineer unless he had served a proper apprenticeship, a scheme for which had been submitted to the board of trade by the consultative committee. It was also recommended that steamships below 100 nominal horse power should carry at least one first class or second class engineer or a certified engineman. Finally, it is proposed that engineers or enginemen who contribute to breakdown at sea should have their certificates dealt with as severely as are those of deck officers under corresponding circumstances.

THE NEW EXPRESS CUNARDERS.

Although the great turbine Cunarders, the Lusitania and Mauretania, are in general respects sister ships, there are some points in which they differ. These have to some extent a bearing on the all-important question of speed. The Mauretania is six inches deeper in her draught, and some seven tons longer in her gross tonnage than the Lusitania. Messrs. Swan, Hunter & Wigham Richardson, the Tyne builders, and John Brown & Co., Clydebank, have taken different lines in regard to the shape of the stern and the dimensions of the propellers. Further, the stem of the Mauretania differs in some material way in shape from the Lusitania. The propellers of the Mauretania are further apart longitudinally, and the discs overlaps a little, while there is no overlapping in the Lusitania. A good deal of importance is attached to these points by architects, and the results will be interesting to note at the time of the trials.




SULZER-DIESEL REVERSIBLE COMBUSTION MARINE ENGINE.

working on one crank shaft, or with a reversible auxiliary pump or similar devices. The reversible engines require to be uncoupled before reversing, and to be recoupled after the reversion has taken place, as they cannot start under considerable load. The disadvantages connected with the above mentioned sys-

plies to reversible propellers. The new reversible Sulzer-Diesel marine engine works on a similar principle as the original Diesel engine and is a reversible two-stroke engine. The reversing devices are of very simple and reliable design, as the two-stroke principle allows of reversing the starting and fuel valve only, and does not necessitate the reversing of other parts. As a rule the engines consist of four cylinders, thus ensuring great reliability in starting, and at the same time an even turning movement. The flywheel is very much lighter than for other internal combustion engines hitherto used for ship propulsion purposes.

The Sulzer-Diesel marine engine can be built up to 1,000 and more B. H. P. and recent tests on an engine of 100 B. H. P. show a fuel consumption which is only slightly higher than that of a four-stroke Diesel engine. The makers are Messrs. Sulzer Brothers, engineers, Winterthur, Switzerland.



SULZER-DIESEL REVERSIBLE COMBUSTION MARINE ENGINE.

tems render it impossible to use same when dealing with large powers, so, for instance, uncoupling the propeller by means of the friction clutch when reversing may cause the engines to race,

Cargo handling is one of the specialties on the great lakes, especially as concerns bulk freight. Recently at the Mare Island navy yard, however, with a Brown hoist using the one-ton tub, 419 tons were discharged from the French ship Biarritz, loaded with Cardiff coal, in nine hours. Every tenth tub was weighed. The drop was 208 ft. from the ship's hatch. To handle the 419 tons, 438 hoists were made.

SEEN AND HEARD IN THE ENGINE ROOM.

The steam yacht Psheclair was on her way down the bay toward the measured course between Scotland light and Fire island for the builders' speed trial trip.

Inquisitive readers are hereby incidentally advised that the yacht's unusual name does not appear in any dictionary of mythology.

Psheclair is simply a combination of part of the names of the owner's wife and daughter.

Upon arriving at the place whence the start is to be made, a gang of picked firemen immediately fill the furnaces (almost up to the crown sheets) with picked coal.

Large fans situated in the upper part of the fire room are then set in motion—an exceedingly rapid motion.

These whirling fans produce the forced draft in this air tight fire room.

The Psheclair carries tubular boilers; the kind in which steam is very readily made. But also, perhaps on the principle of "easy come, easy go," in these boilers the steam is wont to drop on the slightest pretext—or no pretext at all.

It was for this reason that the wily engineers had given instructions to the firemen to so "fix" the fires that they should not need an addition of fuel during the trial trip—or, in other words, arrange it so that the fire doors need not be opened while the run is made. Under the boilers, then, at the commencement of the trial trip, was a substantial body of live fuel, and on top of this as much "green," picked hard coal as could possibly be crowded in by expert shovelers. The forced draft did the rest, and the firemen were not in the least inconvenienced by the unusual pressure to which their bodies were subjected. Not a shovel was touched, nor a door opened, and when, at the conclusion of the successful trial, the Psheclair's head was pointed for the Narrows there remained yet sufficient "body" to the fires under her boilers to make the steam necessary for leisurely jogging to the mooring.

Some one defined "charity" as "the egotism of the altruistic." An egotism of the altruistic is now the term applied to the municipal ferryboats running between New York City and Staten Island. Says the New York *Tribune* of Nov. 28—(in the news columns)—"the ferryboats have been running at top speed since the service was inaugurated, and the heavy pressure under which they have been driv-

en has caused defects in their boilers, condensers and engines to develop."

In short, last year's bill for repairs was \$100,000.

That is a great deal of money; in fact, it is such a large sum that the *Tribune* of the same date, Nov. 28, deems fit to say something editorially anent this matter.

The editor has presumably interviewed some one, been told that the condenser tubes leak—and:

"All we are told is that the salt water in the condensing pipes leaks into the boilers, where it creates an excess of steam."

Thus, according too the *Tribune's* editor, being "circulation water," as it is called, leaking into a boiler is conducive to increasing the steam pressure.

Said a South ferry engineer when shown the above editorial comment: "The *Tribune's* engineer must save lots of coal if he can substitute salt water drippings for high priced black diamonds." F. H.

THE HEATHEN CHINEE.

The chief engineer and staff of the steamer Montrose which arrived in New York from the far east, had a new brand of trouble to face in handling their Chinese crew on their voyage here. One of the officers brought aboard at Yokohama, a curio in the shape of a stuffed fish mounted on a stand. A human papier mache head, fearful and wonderful to behold, had been cunningly attached to the body thereof, the stand being mounted to ornament the mess room.

The "heathen Chinees" soon decided that the souvenir was an "evil joss" and would not have it on the ship at any price, demanding to have it thrown overboard, and absolutely refusing to work their fires. It was only the ship getting into heavy weather saved the situation, as the men preferred taking their chances with the joss to joining Davy Jones in his locker, but a new crew had to be signed in at the next port of call.

MARINE PATENTS.

Copies of these patents can be obtained by sending ten cents in stamps to Siggers & Siggers, patent lawyers, Suite 11, National Union Building, Washington, D. C.

- 836,543. Auxiliary Rudder. William M. Taylor, Mecklenburg county, Va.
- 836,524. Pneumatic Life-Saving Suit. Edward Morrell, San Quentin, Cal.
- 836,627. Means for Securing Logs in Rafts. Michael F. Brown, Seattle, Wash.
- 836,724. Ship's Progress Indicator. Thomas Whittle, Parhran, and William Cumming, Malvern, Victoria, Australia, assignors to said Whittle.

- 836,821. Boat and Propelling-Gear for Same. Gustaf Nelson, St. Louis Park, Minn.
- 836,892. Vessel Construction. Oswald S. Pulliam, Pittsburg, Pa.

THE POET AND THE TAR.

(Being a clash of soul and matter.)

THE POET.

"Oh, tell me, sailor, I pray,
Of the ocean sublime and blue,
Of the long, still nights,
When the Northern Lights
Do whatever it is they do.
Oh, tell of the radiant dawns;
Tell of Sitka and Singapore;
Of the creaking sails
And the spouting whales,
And the hurricane's fateful roar,
And the awesome thoughts in the sailor's mind
Whenever he leaves far, far behind
The lights of his native shore."

THE TAR.

"When I fust run away to sea
With a skipper called Mungo Nogg,
We wuz all of us full
From the Hook to Hull
Of the variegateddest grogs—
And the mate was a sawed-off runt,
But the cook was a tallish chap,
Yet the rest of us b'ys
Wuz of average size
Though our whiskers—"

THE POET.

"Oh, tell me, sailor, I pray,
Of the ocean profound and vast;
Of the cloudless sky
And the seagull's cry
As it circles about the mast.
Oh, tell of the stinging spray;
Of the dangerous, dripping fog—
And infuse the whole
With a dash of soul,
For you sound like a vessel's log.
What I want is the salt sea tang—in brief,
Let your Inner Self be you Leit-Motif,
And do not allude to grog."

THE TAR.

"When I next sailed away to sea
For a skipper we had Zeb Tate.
Who, concealed by a fog,
So diluted our grog
That our jags wuz a whole day late,
And the cook, he wuz six foot two,
But his dog he wuz two foot six,
Yet the average size
Of the rest of us b'ys—
(Not countin' Pop Squid—wuz—
Wot's the matter, poet—wot in—
Leggo my throat!)"
—Thomas R. Ybarra in the New York Times.

THE MAURETANIA.

(From an English newspaper, in Tyneside Dialect.)

At Waalsend thor's a greet big ship,
Myed by th' greet combine, man;
It beats them aall—just tyck ma tip—
A liner fast an' fine, man.
Its length is nigh eight-hundred feet,
Its speed thor's nyen afloat can beat,
It's champion o' th' Cunard fleet,
An' built upon th' Tyne, man.
She'll eary owre three-thousand folks
Across th' briny main, man;
An' gan along wi' powerful strokes
Just like a railway train, man.
Nigh thirty-thousand plates o' steel—
The figures myek wor poor heeds reel—
But it's a triumph aa can feel
Ov Tyneside hands an' brain, man.
Th' Garmans had th' fastest boat,
Until th' other day, man;
But when Waalsend gets hors afloat
She'll show them aall th' way, man.
Th' Kaiser haard, an' tworled his 'tache,
Said, "Gott in Himmel," blank an' dash—
"Dot ship ven launched would make a splash,"
An' leukt quite far fra gay, man.
Ye see it gov him quite a shock,
An' he began te sweer, man;
Least what he said it wasn't "hoch,"
But soonded rethor queer, man.
We've knocked th' "Kaiser Wilhelm" oot;
It's "second" noo thor is ne doot—
In Potsdam they aall haard th' shoot
When Waalsend gov a cheer, man.

J. E. S.

Navigation on the Erie canal from Tonawanda closed for the season on Nov. 25.

QUESTIONS FOR MASTERS AND MATES.—NO. 21.

310. You are on the course from Eagle Harbor to Whitefish Pt. The weather is thick and you figure that you are about 10 miles from Whitefish Pt., but you cannot hear the whistle. How would you verify your position by soundings? What soundings should you get if you were to the eastward of your course; what soundings and which kind of bottom should you get if you were to the westward of your course?

311. Can one depend upon the bearings taken of a fog whistle in a heavy fog? Why?

312. Having obtained the bearing of a fog whistle during a fog how would you verify your position?

313. In a fog Whitefish Pt. fog whistle bears due south from you and you figure that you are 4 miles off, how would you verify it? Supposing your patent sounding machine gave your depth at 38 fathoms, how far north of the point are you?

314. In approaching a fog signal from windward where could you pick up the whistle earliest, aloft or on deck?

315. Approaching a fog whistle from leeward where could you pick it up earliest, on deck or aloft?

316. On the course from Pt. Betsey to Milwaukee in thick weather, how would you determine whether you were making good this course? How would you know if you were fetching westerly of the course? When would you begin to use the lead?

317. To give satisfactory results in the performance of this work, what instrument is necessary?

318. How do you know the speed of your boat in a fog?

319. You are running along in a fog on your natural gait. You give your engineer a check whistle and he slows down, how do you know how fast your boat is running without a log?

320. Over a low lying fog you can see the steam rise from a fog signal but can see nothing else. Fifteen-second intervals elapse from the time you see the steam till you get the sound of the whistle, how far are you from the whistle?

321. Can you judge your distance from a fog signal by the power of the sound? Why is it that many times you can hear a fog whistle more distinct at a given distance away than at a given distance that is not so far away?

322. If you knew you were in

range of the sound of a fog whistle and you could not hear it what would you lay the cause to?

323. From the echo of your own whistle how could you determine approximately your distance off a high shore bank in foggy weather, with little or no wind?

324. What extra precautions do you take in a fog in the navigation of your boat?

QUESTIONS FOR WHEELSMEN AND WATCHMEN.—NO. 22.

221. What is the true bearing of Middle Neebish cut Rgs.?

222. If you had your boat heading on middle Neebish cut Rgs. and your compass reads W x N 34° N, how would you steer with same compass and boat in same trim from a point 1 mile north of Whitefish Pt. light to a point 4 miles NNE from Copper harbor?

223. What is the correct magnetic bearing of Neebish island Rgs.?

224. When wishing to make the turn at the intersection of middle Neebish cut and Neebish island ranges what mark can be used to port slowly on in order to bring stern of boat on Neebish island ranges?

225. What is the true bearing of Middle Hay lake Rgs.?

226. What is the correct magnetic bearing of Frechette Pt. Rgs.?

227. What is the true bearing of Six Mile Pt. ranges?

228. How is Little Rapids cut marked at lower and upper ends?

229. If you had stern of your boat on Bayfield Rock ranges and your steering compass reads W x N 14° N, how would you steer with same compass and boat in same trim from a point 1 mile north of Whitefish Pt. light to a point two miles NNE from Manitou island lighthouse?

230. With stern of your boat in line with Vidal shoal ranges, compass in pilot house reads S 76° W, and compass on top of pilot house reads S 79° W, what should either compass read in order to be correct? Which of the two compasses is the nearest to being correct, the one in the pilot-house or the one on top?

QUESTIONS FOR OILERS AND WATERTENDERS.—NO. 17.

161. What is the lowest temperature that feed water can be admitted into any marine boiler?

162. What marine boilers have no fusible plugs and why?

163. What are the proper dimensions of a fusible plug?

164. What should be the thickness

of a main steam pipe to carry 225 lbs. pressure per square inch?

165. What sized drill would you use to drill a new screwed stay bolt and how deep would you drill same?

165½. What will be the working pressure on a one-inch stay bolt fetched six inches by six inches centers?

166. What is the largest sized screwed stay bolt you may use?

167. What thickness should the strips be for a double-cut, riveted, seam steel plate one inch thick?

168. Suppose the boilers you were with carried 230 lbs. steam pressure per square inch, at what must your steam gauge correctly indicate beyond this pressure?

169. Where would you place a soft plug in a vertical tubular boiler?

COMMERCE OF LAKE SUPERIOR.

The report of the superintendent of Sault Ste. Marie canal shows that 5,787,320 tons of freight were moved through the canals during November, making a total movement to Dec. 1 of 50,192,835 tons. To arrive at the full season's movement, there must be added to this the December movement, yet to be computed, but the commerce is beyond all odds the heaviest that the canal has ever shown.

IN FAVOR OF SHIPPING.

At the annual meeting of the Boston Marine Society the following resolution was unanimously adopted:

That, we the Boston Marine Society, a society of upwards of 400 members, composed of shipmasters, merchants and others directly interested in the commerce of our country, do here, at our annual meeting, heartily and unanimously endorse senate bill No. 529 (known as the shipping bill) as passed by the senate.

It was also unanimously voted that a copy of the above vote be sent to each of the Massachusetts congressmen, and also to the Hon. Jacob H. Gallinger, of New Hampshire, chairman of the merchant marine commission.

The steamer D. R. Hanna left Lorain on her maiden trip Nov. 22, taking over 10,000 tons of coal to the head of the lakes. She will take wheat for storage at Buffalo on her last trip.

The executive committee of the Lake Carriers' Association met at Detroit last week but no business of a public character was transacted.

THE BELLEVILLE GENERATOR AND ECONOMIZER.

(From Navy and Army.)

About sixteen years ago it was generally recognized by those responsible for naval engineering design that a limit had been reached in both the pressure and weight of steam which could be safely produced in warships

number of small tubes containing water and steam, while the flames and hot gases from the fire pass around the outside of these tubes before reaching the up-take and funnel. Each tube is thus subjected to an internal pressure of steam or water, and engineering science tells us that the thickness of the material of which each tube is made varies directly as the

however, allowance has to be made for wear, and the lower rows of tubes next the fire in the Belleville generator are about 3-8 in. thick. The remaining tubes are thinner, generally about 1-5 in.

The modern Belleville boiler consists essentially of two principal parts—the generator, in which steam is formed from water partly filling the tubes,




Fig. I.—Front view as seen from the stokehold platforms, but with the furnace, ashpit, and some of the smoke-box doors removed to show the interior. A down-take is shown at each end of the steam chest.




Fig. II.—Side view in section, showing the flattened spiral construction of the tube elements, with the general arrangement of the baffles and feed pipes. The down-take pipe, conveying the water from the steam chest to the sediment chamber, is hidden by the casing.

from a cylindrical (tank) boiler of a limited size and weight. It was, and is still, possible to produce from cylindrical boilers the necessary power, but at the same time the weight of material would be about double that of the water-tube type, and either the tonnage displacement must also be very largely increased, or some of the armor and armament must be sacrificed.

In a water-tube boiler there are a

product of its diameter and the internal pressure. Thus a cylindrical boiler of about 15 ft. diameter, such as fitted in the "Hindustan," working under 210 lb. per square inch internal pressure, must have a thickness of about $1\frac{3}{4}$ in., while a Belleville boiler tube of 4 in. diameter is strong enough to resist a working pressure of 300 lbs. per square inch when only 1-18 in. in thickness. As a matter of fact,

and the economizer through which the water passes on its way from the feed-pump to the generator. The economizer is thus actually a feed water-heater, and its position above the generator ensures an economy by robbing the hot gases of part of the heat which would otherwise pass away up the funnel without being utilized. The early Bellevilles were not fitted with economizers, and are thus


about 20 per cent less economical than the modern types.

Fig. 1 shows a front view of the boiler with some of the smoke-box doors removed, to show the elements into which this class of boiler is divided. Each element is a sort of flattened spiral, composed of pairs of straight tubes, which are nearly horizontally arranged. Commencing from the lowest junction-box, Z, the tubes are inclined slightly upwards by raising opposite ends alternately (as shown in Fig. II). The junctions are formed by screwed joints at the ends of each two tubes, one of which is inclined downwards to the junction-box at the opposite end below, and the other upwards to the junction-box immediately above, and also at the opposite end. The system is exactly similar for both generator and economizer, but the tubes in the latter are only about 2 in. in diameter, which is about half that of the generator tubes. Each generator element is in open connection with a square-sectioned cross collecting pipe, G, which is called the feed-collector, at the bottom, and with the steam-chest or collector, V, through an up-take pipe, Y, at the top. The boiler shown in the illustration has nine generator and seven economizer elements, and at the stokehold end of each tube there is a small door, which is used for the examination and cleaning of the interior surface.

STERN WHEEL SHALLOW-DRAUGHT MOTOR BOAT.


Salvatore Orlando, engineer, of Leghorn, Italy, has designed a most serviceable stern-wheel boat which will overcome the difficulties hitherto experienced in navigating the inland waters of many districts in northern Italy. The canals and lakes are uniformly very shallow, the Lake Massacinecoli being only 8 ft. deep in the center, decreasing to 12 in. in depth towards the edge, while the canals have only a depth of 2 ft. in hot weather, and are invariably choked with weeds. The employment of steam propulsion, using screw propeller, is under the circumstances impossible and no attempt has hitherto been made in these waters to use either steam or motor barges. M. Orlando, however, faced the difficulty by experimenting with a small stern wheel boat, the screw propeller not being favored because of the likelihood of it becoming clogged by the weeds and growth in the water. His boat, as shown in the accompanying illustration, is of the following dimensions: Length between perpendiculars, 24 ft. 7 in.; length over all, 31 ft.; beam, 5 ft. 9¼ in.; displacement, 1,800 metric tons;

mean draught, 7.87 in. The machinery consists of a four-cylinder, 16-brake H. P. benzine motor, made by the Itala works, of Turin. The engines are placed well forward. In deep sea water, a speed of 8 knots was attained with this boat, but this speed was not reached in Lake Massacinecoli, while in the canals at their shallow summer level, a speed of only three or four knots was possible



STERN-WHEEL, SHALLOW DRAUGHT MOTOR BOAT.

These varying speeds led M. Orlando to use his boat in making experiments of the critical depth of water for given speeds, and the results are given below in his own words. "I first found over a measured distance the true speed of the boat in relation to the revolutions of the wheel, and got as results, 6.93 and 7.40 knots for from 49 to 52 revolutions, respectively. At the speed of



STERN-WHEEL, SHALLOW DRAUGHT MOTOR BOAT.

7 knots in water over 6 ft. 6 in. deep, the bow and stern waves took a well known form which was described by M. Marriner in his paper read before the summer meeting of the Institute of Naval Architects, in 1905. Our illustration shows the vessel moving in deep water. Steaming at 7 knots speed from the middle of the lake towards the shore, nothing particular was noticeable while the water was of a depth over 6 ft. 6 in.. On reaching shallower depths than this the stern waves increased in size, maintaining, however, the repeating form until on reaching the critical depth a very large stern wave suddenly formed, the stern of the boat dipped in a marked manner, and, owing to her very small inertia, and the great increasing of re-

sistance due to this wave, the boat's movement was nearly stopped. The critical depth, M. Orlando says, he has repeatedly measured with great care, and he finds that it is on an average, 4.68 ft. If, he says, we apply the formula $V^2 = C \times D$ where V is the speed in knots, and D the depth of water in ft., to this

(7)²
case we obtain $C = \frac{49}{4.68} = 10.47$. This,

he further says, agrees fairly with the figure 10 obtained by M. Marriner, and tends to confirm the conclusion that the critical depth depends upon the speed and not the size of the vessel.

PERSONAL.

H. H. Raymond, general manager of the Mallory line, New York, announces the following appointments effective Dec. 1: E. G. Warfield, freight traffic manager; W. J. Carroll, purchasing agent.

Mr. George McC. Jackson, formerly boilermaker on the U. S. M. S. St. Louis, has been appointed superintending boilermaker for the American line, succeeding the late Mr. James Edwards, who died recently at Southampton. Mr. Jackson is one of Harland & Wolff's young men, and is to be congratulated.

Charles E. and W. F. Peck announce the amalgamation of their firm with the firms of Albert Willcox & Co., and Walker & Hughes, forming the corporation of Willcox, Peck & Hughes, to continue their business as average adjusters and insurance brokers. The advantages secured by this consolidation are expected to result in more efficient and satisfactory service than ever before. The temporary offices of the marine and adjusting departments are at 27 William street, and the fire department at 58 William street. Branch offices will be maintained at Chicago, Cleveland, Buffalo, New Orleans, Minneapolis and Boston. The officers and directors of the new company are: Charles E. Peck, president; Wm. G. Willcox, Wm. A. Prime, and John C. Eustace, vice presidents; Joseph C. Hughes, treasurer; Gilbert W. Taylor, assistant treasurer; Percy S. Mallett, secretary. Directors: John C. Eustace, Charles Douglas Franks, Joseph C. Hughes, Percy S. Mallett, R. T. Marshall, E. P. Lenihan, Charles P. Molineux, Charles E. Peck, Wm. A. Prime, Charles Sayles, H. N. Townsend, R. L. Van Arsdale, Jr., Wm. G. Willcox, Charles F. Wrecks.

CHAMBERLAIN'S ANNUAL REPORT.

Secretary Metcalf, of the department of commerce and labor, has received the annual report of Navigation Commissioner Chamberlain which states that on July 30, 1906, the documented merchant vessels of the United States numbered 25,006 of 6,674,969 gross tons.

In the decade American shipping on the Pacific has doubled, shipping on the great lakes has increased 69 per cent and is now one-third of our total tonnage. On the Atlantic and Gulf American shipping has increased only 29 per cent. In ten years the world's merchant shipping has increased about 45 per cent. It now requires 177,200 men to man all our merchant vessels and yachts.

The year's construction was 1,221 vessels of 418,745 gross tons. Only three ocean steamers were built. On the great lakes 40 steamers of 232,366 gross tons were built, three each over 7,000 gross tons, the largest ever built on the lakes.

The tonnage built during the current fiscal year up to Nov. 19 aggregates 203,000 gross and if the present rate of construction is not checked by strikes or delays in furnishing structural steel, the output of our ship yards will be the largest in half a century and will be close to the output of 583,000 tons in 1855, the year of our greatest construction.

Work is more evenly distributed on the seaboard and on the lakes than for some years. Of thirty-two ocean steamers building on the seaboard only two are for foreign trade and these two will operate under the postal subsidy laws of 1891.

The assemblage of large bodies of trained mechanics in our ship yards creates a condition especially favorable to a legislative project to begin to re-establish the American merchant marine in foreign trade next year, and the enactment of the merchant marine commission bill, which has passed the senate, is recommended. An American ship cannot receive a subsidy unless it carries a certain proportion of naval reserves. These reserves are volunteers, not conscripts, and the success of the measure thus depends on the willingness of competent American seamen to enroll as volunteers under direction of the navy department. The bill is thus founded on national defense. The expenditures for naval reserves are to be fixed by congress on estimates of the secretary of the navy. Expenditures for ocean mail steamers are to be fixed by congress on estimates of the postmaster

general. The expenditures for general subsidies to cargo steamers and merchant sail vessels depend on numerous conditions, including carrying naval reserves, fixed in a written contract with the secretary of commerce and labor. Few federal appropriations are so rigidly safeguarded.

Quoting the resolution in favor of approved steamship communications adopted by the Pan-American conference at Rio de Janeiro last August, Commissioner Chamberlain publishes a full list of all the vessels in trade between the United States and South America during the first six months of this year. An American merchant steamer is never seen in the ports of Brazil, Argentina, Uruguay, Chile or Peru and only thirty-two American barks or schooners, manned by about 350 men, entered or cleared in six months in South American trade. Steam communication under any flag with South America from our Atlantic ports is virtually confined to New York, for while foreign steamers occasionally enter at Boston, Philadelphia or Baltimore, such entry is generally an incident to a voyage beginning or ending at New York. In trade with Brazil and Argentina are two 14-knot steamers, three 13-knot steamers and seven 12-knot, but the majority are slow cargo steamers. The report favors American mail lines to South America, provided in the merchant marine commission bill. The rate of \$15,600 proposed for a voyage to Buenos Aires is moderate. The British government for some years has paid \$12,600 a voyage for its mail line to Cape Town and the Argentine government is considering a proposition to pay \$25,000 a voyage from Buenos Aires to European ports. Each of these three routes in round numbers is 6,000 miles outward.

A square-rigged vessel has not been built in the United States since 1902, and of our once great fleet of ships, barks and barkentines, only 276 of 322,000 gross tons remain. Some of them will never make another voyage. The completion of the Tehantepec railroad next year will probably deprive such vessels of employment in moving the Hawaiian sugar crop. We must soon abandon the theory that training on a square-rigged ship is a necessary qualification of a deck officer of a steamer or the federal government must maintain square-rigged ships as training schools, alone or in co-operation with states, municipalities or steamship companies.

During the year 227,392 men have been shipped, reshipped or discharged by shipping commissioners. Of 126,

754 shipped, 37,676 were native and 23,456 naturalized Americans. Of the aliens 14,517 were British subjects, 13,454 Spanish (mainly in West Indian and Central American trades), 6,477 Norwegians, 4,368 Germans and only 530 French.

The bill to abolish the discrimination against coasting sail vessels in pilotage charges in the states from Virginia to Texas is favored.

The revised international rules for lights on fishing vessels, which were adopted last spring by the principal maritime nations should be approved at the coming session to secure uniformity and because the United States led in the movement to improve the rules of the road at sea.

Tonnage taxes aggregated \$967,322, the largest amount since the law was changed in 1884. American vessels paid \$84,902. During the year only twelve per cent of the exports and imports of the United States were carried in American vessels.

END OF THE CLYDE SHIP BUILDING STRIKE.

After being on strike seven weeks, the Clyde shipwrights have decided to take the advice of their leaders and return to work on the old terms. The Glasgow branches of the men's union voted on Wednesday, Nov. 14, and it was felt that such a majority had polled in favor of ending the strike that it could not be effected by the ballot of Greenock Paisley and Renfrew which was taken on the following day. The result just made known show that 2499 men had registered votes in favor of returning to work, against 1,631 who were determined to continue the useless resistance. Work will be resumed almost immediately, and a week hence it is expected the Clydeside yards will have regained something like their old atmosphere of industry and prosperity.

In this connection Messrs. W. Denny & Co., Dumbarton, have booked orders from Japan for two large turbine steamers for the ocean trade in the far east. They have also received an order for another steamer for New Zealand. In view of these and other contracts the end of the Clyde ship building strike is viewed with satisfaction.

The Atlantic Works, Inc., 28th street and Gray's Ferry road, Philadelphia, recently received an order from the Vinyard Ship Building Co., Milford, Del., for one of their B-17 adjustable bevel band saw machines, which they make especially for ship yard work.

ITEMS OF GENERAL INTEREST.

Prospects are good for the successful floating of the Allan liner Bavarian.

The new armored cruiser California has just completed a four hours' endurance run. She averaged 22.22 knots per hour.

The steamer W. S. Porter for the Associated Oil Co. has been completed at the yard of the Newport News Ship Building & Dry Dock Co.

Orders have been placed with the Fore River Ship Building Co., Quincy, Mass., for three new steamers for the New England Gas & Coke Co.

In addition to the capital stock of \$14,000,000, the Mallory Steamship Co., recently incorporated at Maine, will issue \$3,000,000 5 per cent twenty-five-year mortgage bonds.

The schooner Keewadin is at the yard of the New London Marine Iron Works, New London, Conn., undergoing repairs to her hull. She will also be given a new keel.

The battleship Minnesota, built by the Newport News Ship Building & Dry Dock Co., Newport News, Va., made her trial trip from Rockland, Me., recently at an average speed of 18 knots an hour, fully meeting her contract requirements. The Minnesota is the first battleship to have undergone a trial before being commissioned.

The steamer Hendrick Hudson, of the Hudson River Day Line, is being equipped with a Bullock telltale fire annunciator, a device invented by C. S. Bullock, of Stratford, Conn., which is finding much favor among vessel owners. The steamer Plymouth, of the New England Navigation Co.'s fleet, which is being rebuilt at Erie Basin by the J. N. Robins Co., will also be equipped with this device.

The Midvale Steel Co. has received an order from the Italian government for 2,100 tons of armor plate, its tender being \$100,000 less than that of the Italian Terni factory. This bid of the Midvale Co. is about \$131 per ton in excess of its bid of \$345 a ton for Class A armor under which is obtained half the contract for supplying the armor for the new United States battleships South Carolina and Michigan.

The Gas Engine & Power Co. and Charles L. Seabury & Co., Consolidated, Morris Heights, N. Y., are exceedingly busy with new construction, having under way at their yard a new 175-ft. steel twin-screw steam yacht and a new set of launches, life-boats and dinghies for F. H. Stevens' steam yacht Oweria; a 45-ft. auxiliary ketch for A. H. Hubbel, and a 36-ft. auxiliary ketch for L. Q. Jones. Both

of these boats will have Speedway gasoline engines, and are for use in southern waters, for which they will be ready by Dec. 1. Twelve Speedway gasoline engines were recently shipped to Buenos Ayres for motor boats in South America.

The Bureau of Yards and Docks has been awarded contracts aggregating about \$175,000 of work in the Charleston and Norfolk yards. C. L. Muralt, New York, was given a contract by the Charleston yard for \$85,000 for boilers and machinery, and the Norfolk yard has awarded the Heine Safety Boiler Co. contract for \$57,178 for boilers and \$30,500 to the D'Olier Engineering Co. for condensing apparatus and traveling crane.

The New Orleans & Tampa Navigation Co., of New York, which will operate steam vessels in the Gulf of Mexico between New Orleans and Tampa, was incorporated last week with a capital of \$500,000. The directors are: George L. Craig, of Toledo; R. L. Caples, of New York; George B. Wilson, of Passaic, N. J.; B. L. Whitlock, S. McLennahan, John J. O'Leary and Thomas H. Franklin, all of New York.

The Japanese Steamship Co., operating between San Francisco, Honolulu, Nagasaki and Hong Kong, will add two big steamers to its present fleet. The new craft are building in Japan and will be 575 ft. long, 63 ft. beam, 39 ft. deep, having a carrying capacity of 12,000 tons. The steamers will be equipped with Parsons turbine engines, capable of giving the vessels a speed of 19½ knots. The first of these vessels is to be put in commission in December, 1907, and the other some time in 1908.

Very recently the Barneson-Hibberd Co., of San Francisco, sold the once famous old sailer Two Brothers to the Pacific Freighting Co. for the sum of \$7,000. The vessel will be converted into an immense barge and will be used by the new purchasers between Puget Sound and Alaska. The Two Brothers was built at Farmingdale, Me., in 1868 by the Bradstreet Brothers, noted ship builders at that time, and has had an unusually interesting career, both in the Atlantic and Pacific.

Mr. Hollis Burgess has sold the gasoline launch Belterre, owned by G. H. Hamilton, of Allston, Mass., to Harry W. Dudley and J. Samuel Hodge, of Boston. He has also sold the cruising knockabout Paloma, owned by Norman S. Powell, of Boston, to John T. Arnold, of Providence, and two 18-footers, Wink, owned by George D. Bussey, of Winthrop, to F. L. Vulte, of New Rochelle, N. Y., and Chercot, owned by Dr. Morton Prince, of Boston, to R. T.

Paine 2nd, of Brookline, who has recently bought the Herreshoff 46-ft. sloop Humma.

Bids on contracts No. 25 and 27, New York state barge canal, opened by the superintendent of New York Public Works, were as follows: Atlantic, Gulf & Pacific Co., New York, contract No. 25, \$1,754,236; Kinzer Construction Co., Chicago, contract No. 27, \$972,210. The state engineer's figures on these two contracts were \$1,849,831 for contract No. 25 and \$993,920 for contract No. 27.

The new steel ocean-going tug Gypsum King, built by the Burles Dry Dock Co., of Port Richmond, S. I., had a successful trial recently. She is the largest and most powerful ocean tug on this coast, and will be used for towing barges between New York and Nova Scotia. She is constructed entirely of steel, is 163 ft. long, 29 ft. 6 in. beam, and 19 ft. 4 in. depth. Her engines, triple expansion, 1,200 H. P., will drive her 13 knots an hour. Her cost was \$130,000. The Gypsum King replaces a tug of the same name which was lost in the Bay of Fundy nearly a year ago.

The American Blower Co., Detroit, is doing a very large business with the ship building companies on its vertical self-oiling engines, types A and E. During the past year and a half it has furnished the Great Lakes Engineering Works, Detroit, with forty-nine of these engines and now has orders on its books for sixteen more. Out of the entire lot there has not been a single repair order. The company has just received a good sized order from the Canadian Ship Building Co., Toronto, Ont., for fans and engines. The first order, placed some time ago, was conditional on the satisfactory performance of the engines.

At the annual meeting of the stockholders of the Aurora Automatic Machinery Co., a subsidiary company of the Independent Pneumatic Tool Co., at its office at Chicago recently, the following officers were elected: John P. Hopkins, president; W. O. Jacquette, first vice president; J. D. Hurley, second vice president; C. E. Erikson, treasurer; A. B. Holmes, secretary. Directors: James B. Brady, W. O. Jacquette, John P. Hopkins, John D. Hurley, A. B. Holmes, M. S. Rosenwald, Simon Florsheim, J. J. McCarthy, C. E. Erikson. A quarterly dividend of three per cent on the stock of the company was declared.

The strike at the Wyandotte yard of the American Ship Building Co. has been settled.

with a mold for that purpose to suit the frame space. Molds are made for the flanges of clips to belt frames, brackets and clips connecting face bars to belt frames, stringer brackets and beams.

By this method all the work including the shell plating is laid off from the mold loft floor.

In Scotland the frames, beams and floor plates are put up and the same

The cost of this work is all governed from the midship size of material. If Fig. 101 was in line with the spar deck, it would be considered the spar deck and paid as such. The main deck ends would be paid the same as at amidships, so with all the different parts.

The bow framing and plating can be done on the larks one-third less than by the method practiced in Scotland.

PERSONNEL AT LORAIN YARD.

I am indebted to Mr. Robert Logan, general manager of the American Ship Building Co., for details of these articles and Mr. Frank La Marche, general superintendent and his assistants of the Lorain yard for their courtesy during my visits to the Lorain ship yard. The photo shows Frank La Marche and his assistants who built the J. Q. Riddle in forty-five working days. These men have been employed in the Lorain yard for a number of years and have a wide experience in ship building. No. 1 shows Mr. La Marche, No. 2, A. C. Paton, superintendent of construction and No. 3, Mr. Frank W. Brown, loftsmen.

These articles concern Mr. Paton and Mr. Brown more than any of the others.

Mr. Paton had a thorough training in Dumbarton, Scotland, in ship build-




Fig. 104 shows the plan of shell plate starboard H₁. Fig. 105 shows the shell expansion forward. Fig. 106 shows a mold for stem plate.

The stem plate mold represents the plate, Fig. 104, flattened out which is all there is to laying out a stem plate from the mold loft floor.

The plate edges are obtained from a level line about the center of the plate which are measured around the heel of the frame and the length of the plate over the stem is secured by putting the plate in the half breadth plan as shown by Fig. 104. The flanging of the stem plate is done in the bending rolls so that the amount of material necessary is easily obtained by flanging a piece of plate before putting the lines for the plate in the half breadth plan.

The most important thing in laying out a stem plate from the mold loft floor is to see that care is taken in drilling the holes square in the stem bar.

The safest plan is to have the stem bar drilled before the reverse stem plate is laid off, then the mold can be applied to the reverse side to test the fairness of the drilling of the stem.

The mold shows shell plate H₁, starboard and in this case there is no fear of the stem holes, seeing they are marked from this side but the holes on the port side of the stem may be angled enough to make bad holes if care is not taken in drilling the stem.




FIG. 105
paired up with ribbands as explained in the seventh article on shell plating and all the different pieces lifted from the boat and erected in rotation.

ing prior to coming to the United States; he was connected with the Cleveland Ship Building Co., from the beginning of their ship building ven-

ture and has remained with them ever since.

Mr. Paton has shown himself to be a very capable man in handling men

Mr. Brown has been brought up in the mold loft from the Cleveland Ship Building Co., Cleveland, to the Lorain yard and he certainly has made

He is a young man and of a very progressive nature with a splendid future ahead of him.


During my visits to the Lorain yard a vessel was on the stocks plated and no riveting done. The fairness of the holes was easily seen which went to show the stage of perfection the mold work had reached.

One thing that can be said for the foremen in the Lorain yard of the American Ship Building Co. is that they work well together and are always ready to help each other in whatever turns up for welfare of the employers' interest.


AUXILIARY STEERING GEAR.

It would seem as though no argument were necessary to prove the necessity of an emergency steering gear aboard ship. The control of a ship is completely at the mercy of its steering gear. As a matter of protection an emergency gear should be carried. Accidents to steering gear may happen without warning and if an emergency gear is not instantly available serious damage may be done to the ship. There are dozens of places in the restricted waterways of the lakes where strandings would inevitably occur should the steering gear give out.

The Akers Steering Gear Co., Old Colony building, Chicago, claim that they have the only successful emergency steering gear on the market. The company certainly submits evidence in support of its claims. Ever since the advent of the 5,000-ton ship it has been apparent that a second or emergency steering gear is necessary. Every other feature connected with the handling and navigation of the modern steamer has been improved upon with the exception of the most essential adjunct to uninterrupted control. Of late years both the number and size of ships on the great lakes has increased immensely, but the channels are the same as ever, limited as to room.




— Fig. 106. —



— Fig. 104. —

and he has the good will of every man under him. He has risen from great progress in the mold work. The neatness and accuracy of his work is




the old methods of ship building to the new and he deserves credit for the progress he has made in improving on the mold work and the high standard of work he puts out.

very creditable and the dispatch is wonderful.

In laying off and making the molds of the J. Q. Riddle he had as assistants, two men and two boys.

If two of the larger ships should collide and sink in any one of a dozen different places in the rivers, navigation would be completely suspended until they were removed—a matter of several days.



THE STAFF AT THE LORAIN YARD—NO. 1 IS MR. LA MARCHE, NO. 2 MR. PATON, AND NO. 3 IS MR. BROWN.

While no actual record has been kept, a large number of strandings and collisions have been due to derangement of steering gears. The regular steering gear with its almost clock-like mechanism is necessarily more or less complicated. A small pinion may bind or stick for only a brief period, a nut or key become loose, even the most trifling thing can happen to render the whole system temporarily inoperative. Under such conditions in a crowded channel, a complete and separate steering gear immediately available is absolutely necessary to prevent collision or stranding. Moreover, it is in these narrow channels with their sharp turns that the regular steering gear gets the hardest and most severe strain. It is natural that the man at the wheel should become nervous and turn the wheel much faster than the builder ever intended that the transmission and engine should be run. If any weakness exists, it is at this crucial time that it will make itself known. The most of these breakdowns are repaired in a few minutes by the engineer, but meanwhile the ship is drifting. If the ship is damaged, the underwriters of course pay the bills, but the vessel owner is not compensated for time lost—and time is a considerable item in the necessarily brief season of lake navigation. Every 24 hours' delay to a 10,000-ton steamer means a heavy loss to the owner. If the ship is equipped with

the Akers emergency gear, there is no danger of it passing from the control of the officer in charge at any crisis. The change from the regular steering gear to the emergency is quite simple, and is made in from ten to fifteen seconds from the bridge. The marine underwriters have had the Akers emergency gear carefully inspected and tested, and they have strongly endorsed and recommended same in a resolution passed at the last annual meeting of Inland Lloyds, and now give boats equipped with it a special note in the register. The new steamers Wm. A. Rogers, B. F. Jones, James Laughlin and Charles Weston are equipped with the emergency steam gear. It will also be installed in the steamers W. M. Mills, L. S. DeGraff, W. D. Kerr and the great passenger steamer now building for the Detroit & Cleveland line. The company has also recently received an order for the equipment of the new 10,000-ton steamer Wilton, building for the Shenango Steamship Co.

The Mianus Motor Co., Mianus, Conn., has just put out a catalog descriptive of their marine gasoline engines. Every part of the engine is intimately described and illustrated. The catalog will be sent to anyone upon request.

CARMANIA'S YEAR.

When the Cunard liner *Carmania* returns home from New York she will have completed a year's sailing, with results in excess of expectations, says the London correspondent of the *Glasgow Herald*, and comparable with the best first year's performance of any Atlantic liner. It has been decided that she will, on arrival a week hence, be taken off the station in order that a thorough examination may be made to ascertain the effect on the turbines of a year's working. During the year the turbines have not been touched, and have worked voyage after voyage almost without attention. As regards economy, there has been from the beginning a steady improvement. It was thought best to run the ship when new at a moderate speed. The consequence was that the economy was not so good as if the turbines had been driven at their maximum speed—a result which is inherent in the system. In recent voyages there has been a speeding-up, and now the coal consumption is practically the same as for the best quadruple-expansion engine—the difference is less than six per cent. When, next year, the turbines are worked at their maximum the *Carmania* will excel in economy even the *Caronia*.

PULVERIZED COAL ABOARD SHIP.

According to an announcement made at Buffalo last week by Mr. C. C. Card, general manager of the International Combustion Corporation of Buffalo, the problem of running lake freighters on an economical basis so far as fuel goes has been solved with the corporation's apparatus for burning pulverized coal. It is definitely asserted that boats can be run much cheaper on account of the saving in fuel and labor.


Where vessel owners have hesitated

By the Packard system of burning pulverized coal, the coal is ground so it will pass through a screen of from 40 to 60 mesh, where it has heretofore been considered necessary to grind the coal so fine that 95 per cent would pass through a 100 mesh screen. After being pulverized, the coal is fed into a hopper in front of the boiler at the bottom of which is a patent feeder that is positive in its operation, and which feeds the coal into a current of air produced by an ordinary centrifugal pressure fan. This air carries the

or have regular fuel docks where pulverized coal could be put aboard. This, however, is considered a minor detail in view of the complete success thus far achieved.

There are other advantages derived by using the Packard pulverized fuel burner. Eliminating smoke, as it does, its use will mean that the lake harbors will be kept free from smoke, the signals on the boats when they are passing at close hand will be more easily distinguished on account of the absence of smoke, and the boats, themselves, will always look more shipshape and clean than ever before. Realizing this, the management of some Cleveland boats are now figuring on installing them on some of those boats this winter.

The apparatus has been in successful use for the past five years under all the boilers and annealing furnaces of the Erie Malleable Iron Co., at Erie, Pa. The success there has resulted in its installation in other plants, and experts claim that it will be found not only on all the lake freighters, but also on the passenger steamers in the next few years. It is broadly claimed that the burner will revolutionize the burning of soft coal.



SHOWING INTERNATIONAL COMBUSTION CORPORATION'S APPARATUS INSTALLED UNDER A BABCOCK & WILCOX BOILER IN THE EDISON ILLUMINATING CO'S PLANT, AT DETROIT.

heretofore to put powerful engines in their boats because they require so much fuel to keep running, it now appears that all this is to be changed with the Packard system of burning pulverized coal. The boats will not only develop greater horsepower on a smaller amount of coal, but they will be fired by one man on a watch where three or four are now needed.

Figured on a conservative basis, the estimated saving on a lake freighter on the fuel by the use of the system would run 15 to 30 per cent over and above the present method of firing coal. This would include the saving in wages of the firemen whose services would be dispensed with. This would simplify lake navigation because the fuel problem is confessedly the most serious one to consider.

Owners by the use of the pulverized fuel burner will be able to inaugurate another economy in addition to saving the cost of labor. They will be relieved of the proposition of buying new grate bars every so often for the simple reason there are none in the burners. This is a considerable item in the course of a season.

coal into the furnace where combustion takes place under ideal conditions, viz., an extremely hot furnace, finely divided coal uniform in size, and a sufficient quantity of air to secure complete combustion.

Among the advantages claimed for burning pulverized coal by the Packard system, are that it is the most economical and complete method of burning coal; labor expenses are greatly reduced since one intelligent fireman can operate fifteen to twenty boilers, adaptability and ease of regulation to meet all requirements; decreased wear and tear of furnaces on boilers with no grate bars to burn out or renew; saving of time in starting up and rapid stoppage in case of necessity; less labor required to remove refuse; intimate contact of fuel with air whereby the minimum excess is employed over the theoretical volume in waste of heat thus avoided. And last but not least, since complete combustion is obtained, it is absolutely smokeless at all times.

In order to install the system on boats, it would either be necessary to have small grinding machines aboard,

TRADE NOTES.

The Rockwell Engineering Co., 26 Cortlandt street, New York, has recently put out a variety of bulletins descriptive of their various specialties, among them the Rockwell rivet heating furnaces, one of the most ingenious devices on the market. It will heat rivets up to 1½ in. diameter and will keep any gang supplied and may be operated with fuel, oil or gas. Other bulletins are devoted to the flue welding furnaces, brazing furnaces, metal melting furnaces, annealing and hardening furnaces, pot furnaces for lead and other soft metals, heating machines for annealing, hardening, tempering and coloring, and fuel oil burning appliances. All of these catalogs are excellent specimens of the printer's art and are well worth preserving.

The *American Wire Rope News* is a quarterly issued by the America Steel & Wire Co., Rookery, Chicago, Ill. The October quarterly is just out and contains considerable matter of interest to users of wire rope, especially an article devoted to derrick rope calculations. The quarterly contains a great deal of information and is rich in half-tone illustrations of standard constructions of American wire rope. The uses of rope are, of course, infinite, and this quarterly should be of interest to many lines of industry. It can be had for the asking.

DEC 8 08

THE NEW YORK
PUBLIC LIBRARY
ASTOR, LENOX AND
TILDEN FOUNDATION
\$1.00 a Year

10c. a Copy

ENGINEERS' NUMBER

THE MARINE REVIEW

VOL. XXXIV.

CLEVELAND, DECEMBER 6, 1906.

No. 23.

Great Lakes Dredge & Dock Company

RIVER AND HARBOR IMPROVEMENTS

**Foundations, Bridges, Piers, Breakwaters,
Lighthouses, Tunnels, Pneumatic
and Submarine Work.**


CHICAGO

DULUTH

CLEVELAND

TOLEDO

SAULT STE. MARIE



Morison Suspension Boiler Furnaces

For Land and Marine Boilers

Uniform Thickness—Easily Cleaned
UNEXCELLED FOR STRENGTH

Also Fox Corrugated Furnaces


Manufactured
by

THE CONTINENTAL IRON WORKS,

West and Cayler Sts., NEW YORK.

Near 10th and 23d Sts. Ferries
Borough of Brooklyn.

REGISTER




WALKER'S "Excelsior" Yacht-Log FOR YACHTS AND MOTOR BOATS

Sold by

M. Rupp & Co.,	New York
C. C. Hutchinson,	Boston
Riggs & Bro.,	Philadelphia
G. B. Carpenter & Co.,	Chicago
The Upson-Walton Co.,	Cleveland
G. M. Josselyn & Co.,	San Francisco
C. J. Hendrys, Son & Co.,	San Francisco
and other Marine Opticians.	

Thos. Walker & Son, Ltd.

58 Oxford Street
Birmingham, England.



The Nicholson Log

Not a luxury but a necessity on every ship. Be up to date and equip your vessels with this excellent device. The exact speed of the moment constantly before you and recorded on a chart. Also the distance run. Let us send you our catalogue.

NICHOLSON SHIP LOG CO., Cleveland, O.

SHIP MACHINERY, embodying the latest designs and many important patented improvements.

Sole builders of the Original and Only
**AUTOMATIC
STEAM TOWING MACHINE.**

Established:
1857

**AMERICAN
SHIP WINDLASS CO.**
Providence, R. I.


P. O. Box 53

We have completed our new Iron Foundry, and are prepared to execute orders for Castings, guaranteeing first-class work, prompt service and reasonable prices.

Send for illustrated
catalogue


Address FRANK S. MANTON, President

BROWNHOIST



GRAB BUCKETS

Whether used in Ore,
Coal, Limestone or sim-
ilar materials are equally
efficient and economical.



THE BROWN HOISTING MACHINERY CO.

Engineers, Designers and Manufacturers of Hoisting Machinery and its Equipment.

CLEVELAND, OHIO

NEW YORK

LONDON

PITTSBURG

THE BOILER MAKER

Can obtain from us everything
necessary to complete his work—
Tubes, Plates, Heads, Rivets,
Shapes, etc., for immediate ship-
ment when necessary. See our
Stocklists.

Scott's Tool Steel makes the best chisels.

THE
BOURNE-FULLER CO.
IRON STEEL
PIG IRON
COKE
Cleveland, Ohio


Pittsburg Office

1126 Frick Bldg.

THE "FAIVRETTE" Clam Shell Bucket

Best Digger on Earth

Built of
steel
through-
out in
all sizes
and
weights
for all
purposes



Simplest,
strongest
and
most
durable
Bucket
made

We also
build
Orange
Peel
Buckets

One of two 2 yard Buckets built for
Graves & Stephens, Cleveland, Ohio.

THE G. H. WILLIAMS CO.

Consulting Engineers, Designers and Build-
ers of Revolving Steam Derricks of all kinds.

1521 Rockefeller Building

Cleveland, Ohio.



The American Ship Building Company

MAIN OFFICE CLEVELAND, OHIO

Marine and
Stationary Engines

STEEL SHIPS

Boilers and
Auxiliary Machinery

Sole Agents for the Lakes for the Ellis & Eaves Induced Draft System, as applied to boilers, giving increased power and great economy.

WORKS AT CLEVELAND AND LORAIN



Detroit Ship Building Company

SHIP AND ENGINE BUILDERS

Sole Owners for the Lakes and Atlantic Coast of the HOWDEN HOT DRAFT SYSTEM as applied to Boilers, giving increased power and great economy.

Steel Ship Yard located at Wyandotte, Michigan
Wooden Ship Yards and Dry Docks, Foot of Orleans Street, and Foot of Clark Ave., Detroit, Mich.

Wm. C. McMillan, President.
M. E. Farr, V. P. and Treas.
E. Ketcham, Secretary.
Frank Jeffrey, General Supt.

WM. L. BROWN, Pres.


J. C. WALLACE, Vice-Pres.

R. C. WETMORE, Sec'y and Treas.

O. W. FREY, Ass't. Treas.

ALFRED G. SMITH, Gen'l Supt.

Chicago Ship Building Company



STEEL SHIPS

Passenger or Freight

ANY SIZE

Yards, Dry Docks and Repair Shops at South Chicago, Ill.



The Superior Ship Building Company

SHIP AND ENGINE BUILDERS

Large stock of material always on hand for Repairing Wooden and Metal Ships.

Dry Docks and Repairs of all kinds

Repairing promptly attended to, Night or Day.

WEST SUPERIOR

WISCONSIN

THE TOLEDO SHIPBUILDING COMPANY

BUILDERS AND REPAIRERS OF


SHIPS AND ENGINES

FRANK E. KIRBY, CONSULTING ENGINEER.

TOLEDO, OHIO

ALEXANDER MCVITTIE, PRESIDENT.
CHAS. B. CALDER, GENERAL MANAGER.

H. S. WILKINSON, SECRETARY.
L. C. SMITH, TREASURER.



Milwaukee Dry Dock Company

MILWAUKEE

WISCONSIN


SHIP REPAIRS OF ALL KINDS

We have two ship yards offering every facility for the repair of both steel and wooden vessels. South Yard Dock is 450 ft. long on keel blocks; 460 ft. over all; 60 ft. width of gate and 16 ft. over sill. West Yard Dock is 312 ft. on keel blocks; 45 ft. width of gate and 12 ft. over sill. Rudder pit in each dock.

Electric lights for night work.

MAIN OFFICE AT SOUTH YARD
Foot of Washington Street

Telephone Main 3



Announcement

Our plant having been thoroughly reorganized both as to management and equipment, we are enabled to do all kinds of ship repairs at reasonable cost to the owners, whose patronage is solicited with the guarantee of satisfaction in all particulars.

We call attention to our facilities for the construction of new vessels of all kinds, particularly dredging outfits, tugs, scows, fuel lighters, etc., plans for which we will furnish on application together with specifications and estimates of cost.

The Buffalo Dry Dock Company


BUFFALO, NEW YORK

EDWARD SMITH, President

EDWARD N. SMITH, Superintendent

WILLIAM KNIGHT, Ass't. Sec'y and Treas.

Office Telephone, 515 Seneca. President's Office Telephone, 2329 Seneca
President's Residence Telephone, 209 Bryant. Ass't Sec'y's Telephone, 324 North.
Superintendent's Telephone, Bryant 209.



Collingwood Shipbuilding Co.

COLLINGWOOD, ONTARIO.

STEEL & WOOD SHIPS

Marine and Stationary Engines
Boilers and Auxiliary Machines


Dry Dock 514 ft. Keel Blocks

ALEX. McDOUGALL
PRESIDENT

J. M. SMITH
MANAGER

OUR SHIPYARD

WITH ITS ACCOMPANYING DRY DOCKS
AND WORKS, WAS CAREFULLY DESIGNED,
EQUIPPED AND COMPLETED FOR THE



CONSTRUCTION AND REPAIRING
IN EVERY DETAIL OF

BATTLE SHIPS · ARMORED CRUISERS ·
PROTECTED CRUISERS · GUN BOATS ·
TORPEDO BOATS · TORPEDO BOAT
DESTROYERS · SUBMARINE BOATS ·
OCEAN LINERS · PASSENGER STEAM-
ERS · FREIGHT CARRIERS · ETC · ETC ·

NEWPORT NEWS SHIPBUILDING & DRY DOCK CO.
1 BROADWAY NEW YORK — NEWPORT NEWS, VA.

New York Shipbuilding Company

Main Office and Works, Camden, N. J.

New York Office, 12 Broadway



Launch of "Mongolia," Pacific Mail S. S. Co., 615 feet long, 65 feet beam, 51 feet deep.

Builders of

SHIPS, ENGINES, BOILERS AND HEAVY MACHINERY

Best Facilities for Repair Work

Pneumatic and Electric Tools; ample wharfage accommodation.

**One Hundred Ton
Crane**

**Repairs done under
Shelter**

CLYDE LINE "APACHE"

WARD LINE "MERIDA"

**THE
WM.
CRAMP
— & SONS —
SHIP & ENGINE BUILDING Co.**

ESTABLISHED 1830


I.P. MORRIS COMPANY KENSINGTON SHIPYARD Co
(ESTABLISHED 1829)

WARSHIPS AND MERCHANT STEAMERS
Pumping, Blowing and Hoisting Engines, Dry Docks
Vertical and Horizontal Turbines
Centrifugal Pumping Machinery
Marine Railway.
Repairs to all classes
of vessels

LARGE TURBINE

VIEW OF ONE OF OUR DRY DOCKS

Philadelphia



Electric Bell Bell-Buoy Vessel with Receiving Apparatus Lightship Bell

SUBMARINE SIGNALS

The United States Government is now ringing submarine bells in thick and foggy weather on these lightships.

Cape Elizabeth	Boston	Pollock Rip Shoals	Nantucket Shoals
Vineyard Sound	Brenton Reef	Cornfield Point	Fire Island
Sandy Hook	Overfalls	Fenwick Island	Five-Fathom Bank
Winter Quarter Shoal	Cape Charles	Tail of the Horseshoe	Diamond Shoal

Steamships equipped with submarine signal receiving apparatus:

No. German Lloyd	Hamburg-American	French	Cunard	White Star
Merchants & Miners	Metropolitan	Boston & Philadelphia	and other lines.	

For rates and information apply to

Submarine Signal Company **BOSTON**
MASS.

THE ROBERTS SAFETY WATER-TUBE BOILER CO.

Manufacturers of
High Grade

Marine Water Tube Boilers

Generators of the Highest Quality of Steam

OVER 1500 IN USE

Send for circulars
and stock sheet

MAIN OFFICE

39 Cortlandt St.

New York City

Phone 589 Cortlandt

Works: Red Bank, N. J.

Phone. 49 Red Bank

Cable Address
"Bruniva"

Quintard Iron Works Company

Office 742 E. 12th St.
NEW YORK

MARINE ENGINES, BOILERS MARINE TURBINES

Gas Works Apparatus,
Sugar, Cement, Mining, Dredging
and all kinds of Machinery.

N. F. PALMER, President


STEVENSON TAYLOR, Vice Pres.

GEO. Q. PALMER, Treas. and Genl. Mgr.

MARYLAND STEEL COMPANY

BUILDERS OF STEEL STEAMSHIPS,
TOW BOATS, SAILING VESSELS,
BARGES AND STEAM CRAFT
OF EVERY DESCRIPTION

STEEL FLOATING DRY DOCKS
CAPABLE OF DOCKING
THE LARGEST VESSELS




FLOATING DRY DOCK BUILT BY US FOR UNITED STATES GOVERNMENT

SPARROW'S POINT,
MARYLAND.

THE AKERS Emergency Steam Steering Gear

IS A MONEY SAVER.

See that it is included in your specifications before placing orders for new Ships.



We also install **Hand Emergency Gears** in Steamers plying on the open Lake, Car Ferries, Passenger Steamers, &c., having equipped twelve steamers in this service.

PATENTED 1900-02-04
OTHER PATENTS PENDING.

The Akers Emergency Steering Gear is the only reliable Emergency Steering Gear on the market. It will pay for itself in a short time by avoiding delays which are frequently occasioned by trouble with the regular Steering Gear.

If anything happens to the regular Steering Gear, Telemotor, or whatever transmission is used to connect Trick wheel on the bridge with Steering Engine, all that is necessary to throw the Akers Gear into service, is to turn the crank on the Emergency Wheel stand located on the bridge, thus dropping the chains free from regular Quadrant and throwing in the Emergency Gear.

The operation of changing from Regular to Emergency Gear requires from 5 to 15 seconds, making it practically instantaneous. The Akers Emergency Gear is being used successfully in 17 Ships; 5 of this number being Ore Carriers of 10,000 tons and over. We are installing this Gear in 3-505 footers now being built for the Weston Transit Co., 1-574 footer for the Shenango Steamship Co., also in the new Passenger Steamer for the D. & C. Navigation Co. **The Gear is a perfectly independent Steam Steering Gear.**

Write us for descriptive pamphlet.

AKERS STEERING GEAR CO.

1590 Old Colony Bldg., CHICAGO.



Welded skag of Clyde Line Steamer "Apache"

Owing to an accidental bending of shaft the propellor struck this Thermit welded skag about 45,000 blows in the course of eight hours. The propellor finally dropped into the sea, but the weld was absolutely uninjured. This is a notable triumph of repairs by the

THERMIT PROCESS
(reg. trade mark)

Write for descriptive booklet.

Goldschmidt Thermit Co.

43 Exchange Place, New York.

Wheeler Centrifugal PUMPS



For service in vessels where compact machinery of the highest possible efficiency is necessary.

Wheeler Centrifugal Pump

WHEELER MARINE TURBINE CONDENSERS

Surface Condensers, Feed Water Heaters,
Combined Auxiliary Condenser
and Feed Water Heater.

Catalogs


Wheeler Condenser & Engineering Co.

42 Broadway, N. Y. Works: Carteret, N. J.
Monadnock Block, Chicago.

CINCINNATI

ATLANTA

SAN FRANCISCO





We make a complete line of Punches
Shears, Plate Planers and Bending
Machinery for Shipyard Work.

WE CAN FURNISH OUR TOOLS EITHER
BELT, STEAM OR MOTOR DRIVEN.

The Cleveland Punch & Shear Works Co.
Cleveland, O.

"Our Name Denotes Quality"





Simple Reliable Durable

THE

PENBERTHY

Automatic Re-Starting Injector

Is the favorite today with over 450,000 engineers, because it never disappoints. It is known in every country under the sun as the world's standard injector.

Our catalogue of injectors, oilers and engine room specialties sent to any engineer on request. The Penberthy "Engineer and Fireman" sent three months Free to any engineer or fireman sending us his name and address

PENBERTHY INJECTOR CO.

Largest Manufacturers of Injectors in the World
351 Holden Ave., DETROIT, MICH., U. S. A.

Made in Canada by
The Penberthy
Injector Co., Ltd.
Windsor, Ont.

U.S. Automatic Injectors

The U. S. Automatic Injector isn't "*the Best*" simply *because* the U. S. Government adopted it. The U. S. Government adopted the U. S. Automatic because it is *the best*.

Scientific tests prove that the U. S. Automatic has 100 per cent efficiency, that it is ideally perfect, that there is absolutely no waste.

Continuous use has demonstrated the U. S. Automatic the most reliable and trustworthy Injector on the market. That's why over 200,000 engineers endorse it as the *Best*.

Note these Facts:—The U. S. Automatic has wider range, feeds hotter water, is the only injector with a drip cock—a mighty valuable feature, and the only injector accompanied by a bona fide certificate of range and capacity. Want more facts?

Write for the Engineer's Red Book—Sent Free!

This modest little booklet deals in facts—not theories. It has proved helpful to thousands of engineers. It will prove valuable to you. Free for the asking.



American
Detroit,



Injector Co.
Mich.

LUNKENHEIMER Brass "Pop" Safety Valves

POSITIVELY RELIABLE

**VERY SENSITIVE TO EXCESSIVE
PRESSURES**

**WILL NOT STICK,
POUND OR LEAK**

IF YOUR LOCAL DEALER CANNOT
FURNISH THEM, NOTIFY US



The Lunkenger Co.

LARGEST MANUFACTURERS OF HIGH-GRADE
ENGINEERING SPECIALTIES IN THE WORLD

General Offices
and Works: **Cincinnati, Ohio, U. S. A.**

Branches: **NEW YORK, 66-68 FULTON ST.**
LONDON, S. E., 35 GREAT DOVER ST.

M. R. 3



Modern Highway and Electric Railway Scherzer Rolling Lift Bridge open for the passage of large vessel. Superseded and replaced a center pier swing bridge.

More **90 SCHERZER** than **ROLLING LIFT BRIDGES**

have already been built, superseding and replacing swing bridges and other old types of movable bridges for railroads, electric railways and highways in the most progressive cities and harbors of the world.

HIGHEST AWARD

World's Fair, St. Louis, 1904


"Center pier swing bridges form **artificial obstructions**, blocking **navigation** and **commerce**. They are condemned, removed and replaced by modern **SCHERZER ROLLING LIFT BRIDGES** wherever **Manufacturing, Commerce, Transportation, Railroads** and **Ships** are valued, protected and advanced."

*Write us for photographs, information,
sketches and estimates*

THE SCHERZER ROLLING LIFT BRIDGE COMPANY

Main Offices: Monadnock Block, Chicago, U. S. A.

Cable Address: Scherzer, Chicago



Modern Railroad Scherzer Rolling Lift Bridge in the open position. Longest span Bascule Bridge in the world. Also Highway Scherzer Rolling Lift Bridge open further down the river.

Established 1869

Incorporated 1896

Atlantic Works Incorporated


Successors to Berry & Orton Company
Manufacturers of

**Machinery for Working Wood
also Band Saw Blades**

For use in Ship Yards, Car Shops, Railroad Shops.

Estimates furnished. Send for Catalogue.

**2870-72-74-76-78 Gray's Ferry Road
Philadelphia, Pa.**




Adjustable Bevel Band Saw

**will bevel both ways
at 45 degrees**

**Power movement to
change angles**

**Power feed in three
directions**





8' x 12' FLOAT—45 PERSONS—450 CUBIC BOAT FEET

WE CAN SAVE YOU**75% deck space 50% weight 90% cost of maintenance****THE CARLEY LIFE FLOAT**

Constructed of Copper, Cork, Canvas and Cordage.
Requires no davits or tackle.

Standard sizes range from six to sixty-seven persons capacity.

LIFE BOATS**LIFE PRESERVERS**

Send for Illustrated Catalogue.

CARLEY LIFE FLOAT COMPANY

F 4 & 5 Produce Exchange Building, New York.

**"RAINO"**
For Hard Service

"Raino" is a guaranteed absolutely waterproof cloth.

For ships' officers, yachtsmen, seamen, etc., it is the ideal waterproof garment.

"Raino" is very light, clean and neat looking. Far superior to either oilskins or rubber. It will not rot, nor is it stiff, heavy, oily or foul smelling.

After two years of the hardest kind of army and naval service tests in all parts of the world hundreds of officers declare it the most durable waterproof garment made.

"Raino" officer's Long Coat \$6.30 net
"Raino" Medium Coat..... 5.40 "
"Raino" Jacket..... 4.50
"Raino" Overalls..... 2.50 "
"Raino" Soft Squam Hat... 1.00

Write for Samples and Price List P.

E. A. ARMSTRONG MFG. CO.

(Makers of the famous Armstrong Uniforms.)

Write for prices on Uniforms.

315-321 Wabash Ave., Chicago.

ARMSTRONG GUARANTEE.

A week's trial. Rain, Hose or Shower. If not satisfactory express back at our expense. Money returned. Show our faith.

**Shoes That**

FEET
and
FANCY

retail for

\$3.50-4.00-5.00-6.00

and are for sale at the

EMERSON
SHOE STORES

in Cleveland, Toledo,
Buffalo, and Detroit

also in


Erie, Pa. G. W. Carter & Co.
Conneaut, O. E. Johnson.
Elyria, O. Wm. E. Smith.
Ashtabula, O. J. E. Scoville.
Painesville, O. Jones & Nye.

Lorain, O. Francis Bros.
Amherst, O. Jacob Baus.
Sandusky, O. W. O. Stubig.
Brooklyn, O. E. H. Wecke.
Elmore, O. A. Weis & Son.

Factory
at

The
Emerson Shoe
HONEST ALL THROUGH

Rockland
Mass.

**Pintsch Gas Lighted Buoys**

BURN CONTINUOUSLY

FROM 80 TO 365 DAYS AND NIGHTS WITHOUT ATTENTION AND CAN BE SEEN AT A DISTANCE OF SIX MILES.

Brilliant & Steady Illumination. Economical & Reliable in Operation.

Adopted by the English, German, French, Russian and United States Light House Departments for Channel and Harbor Lighting; over 1900 gas buoys and gas beacons in service.

Controlled by the

SAFETY CAR HEATING & LIGHTING COMPANY

160 Broadway,

NEW YORK CITY.


GREAT LAKES ENGINEERING WORKS

DETROIT, MICH.

ANTONIO C. PESSANO, President and Gen. Mgr.

GEORGE H. RUSSEL,
Vice President.

JOHN R. RUSSEL,
Secretary and Treasurer.



Steel Ship Builders

Floating Dock


Marine Engines

**Marine
Repairs**


**Hydraulic
Dredges**

**Hydro Carbon
System**

**Propeller
Wheels**



Hyde Windlasses and Capstans



Steamship Minnesota equipped with Hyde Windlass and Capstans.

Selected for the Minnesota and Dakota of the Great Northern Steamship Co.'s fleet—the largest vessels ever built in the United States. They are also being installed on nearly all of the vessels now building for the Navy Department, Revenue Cutter service, Lighthouse Board and the United States Coast Survey.

Reason—Their Superiority.

Send for Illustrated Catalog.

HYDE WINDLASS COMPANY

BATH, MAINE

Geo. L. McCurdy

169 Jackson Boulevard

CHICAGO ILLINOIS

INSURANCE

HULLS and CARGOES

DIRECT REPRESENTATIVE OF LEADING
AMERICAN AND FOREIGN UNDERWRITERS

THE OHIO MACHINE & BOILER COMPANY

108-114 River St., CLEVELAND, O.

BOTH PHONES.

Machinists, Boiler Makers and
Structural Iron Workers.
BOILERS, TANKS, STACKS,
and all kinds of heavy or light
RIVETED PLATE WORK

HEAVY FORGINGS

Special Machinery and Repairs
GENERAL JOBBING

We are particularly well equipped for vessel repair work, and our location advantageous. We install new furnaces (any kind) in marine boilers—12 Adamson type for passenger steamer "City of Buffalo," 4 for steamer "Gladstone," &c., &c., last season. Send us specifications, and get our figures before placing orders.

Special attention to quick repairs night or day.

WANTED and FOR SALE

PROPOSALS.

U. S. Engineer Office, Vicksburg, Miss., Nov. 20, 1906. Sealed proposals for the construction of six wooden, four creosoted or three steel material barges for use in the Third district, improving Mississippi River, will be received at this office until 12 o'clock, noon, Dec. 20, 1906, and then publicly opened. Information furnished on application. G. M. Hoffman, Capt. Engineers.

I HAVE VESSELS of most every kind—from 10 tons to 6,000 tons—to sell for their owners, at reasonable prices. Anybody wishing to buy or sell a boat should call on or write Fred A. Bradley,

11 Mooney-Brisbane Bldg.,
Buffalo, N. Y.

Insurance Agent.

FOR SALE.

VERTICAL ENGINE.

One triple-expansion marine type vertical engine, 11¼-inch, 18-inch, 29 x 18-inch stroke. Inquire, Public Lighting Commission, No. 40 Atwater Street East, Detroit, Mich.

Boilers for Sale.

Five Scotch Boilers, allowed 160 lbs. steam. Good as new. **ERIE MACHINERY CO.**, 729 Garfield Bldg., Cleveland, O.

STEAMER PEERLESS.

FOR SALE.—Steamer Peerless, fully equipped for freight and passengers. Address, D. E. Sullivan, suite 1212, Ashland block, Chicago, Ill.

For Sale.

1,000 h. p. fore and aft Neafie & Levy compound Engine; surface condenser; independent pumps.

Two 12-foot Scotch Boilers.

One 13½-foot Scotch Boiler.

One 10 16-25 x 16 triple expansion Engine.

Three 150-h. p. Almy Boilers.

One 200-h. p. Tregurtha Boiler.

One 14 30 x 24 fore and aft Engine and condenser.

One Williamson steering Engine.

One 10 k. w. electric lighting Set.

One 15 k. w. electric lighting Set.

One Providence Windlass, 50 fathoms 1½ in. chain.

Two thrust Shafts and Bearings, 8½ in. diameter.

MARVIN BRIGGS,

17 Battery place, New York, N. Y.

Steamer for Sale Cheap.

The lighthouse steamer Haze, 145 ft. long, 27-ft. beam, 9-ft. draught, 500 tons capacity, 300 horsepower engine and boiler, suitable for passenger or freight business, fully equipped. Steam capstan, donkey boiler. Jacob Ullman, 46 Lloyd street, Buffalo, N. Y.

FOR SALE.

To close the Estate of the late Wiley M. Egan, the undersigned will receive proposals for the purchase of all, or a two-thirds interest in each of the freight Steamers Philip D. Armour, John Plankinton, Wiley M. Egan and R. P. Fitzgerald.

All proposals should be submitted by Dec. 10, 1906. Right reserved to reject any and all bids. For further particulars address,

Arthur C. Helm, Managing Executor,
Estate of Wiley M. Egan, Dec'd.,
214 Postal Telegraph bldg.,
Chicago, Ill.

WANTED TO BUY FOR CASH Passenger Boat, length 70 to 80 ft. Beam 16 to 18 ft., light Draft. Must be good runner, single deck preferred. In writing give full description of Hull, boiler and engines. Address **L. E. Eggert**, Muskegon Heights, Mich.

WANTED.—A good stone scow, about 800 tons capacity or over. Give particulars and price. Apply Box 106.

GOULD'S NAUTICAL SCHOOL,
265 MARCY AVE., CLEVELAND, O.
Established 1894.

Full and complete instructions in Lake and Ocean Navigation; also the Laws of Magnetism as applied to the compass, its effects, adjustments, etc. Will open about Dec. 10th.

FOR SALE.

One fore and aft Compound Marine Engine with cylinders 27 and 50 by 40-inch stroke. Inquire of the Montague Iron Works, of Montague, Mich.

GREAT LAKES REGISTER

FOR THE
CLASSIFICATION OF STEEL AND WOODEN VESSELS.



COMBINED AND ISSUED IN CONNECTION WITH

BUREAU VERITAS

INTERNATIONAL REGISTER OF SHIPPING.

THE RATINGS OF GREAT LAKES REGISTER GO BEFORE AND ARE ACCEPTED BY THE LEADING UNDERWRITERS OF AMERICA AND EUROPE. VESSELS BUILT UNDER THE SUPERVISION OF ITS SURVEYORS WILL RECEIVE SPECIAL RATING, AND WILL ALSO BE PUBLISHED IN BUREAU VERITAS INTERNATIONAL REGISTER OF SHIPPING.

PLANS AND SPECIFICATIONS FURNISHED.

GREAT LAKES REGISTER SURVEYORS ARE ESTABLISHED AT ALL THE PRINCIPAL PORTS ON THE GREAT LAKES.

F. D. HERRIMAN, SURVEYOR GENERAL,
820-822 Perry-Payne Building, CLEVELAND, O.

CHARLES E. PECK. WILLIAM A. PRIME.
CHAS. E. & W. F. PECK
Insurance Brokers. Average Adjusters.

ESTABLISHED 1870.

NEW YORK, 58 William Street.

BOSTON, 153 Milk St.

BUFFALO, 914 The Fidelity Bldg.

CLEVELAND, 1006-1008 Rockefeller Bldg.

CHICAGO, 1114-15 Royal Insurance Bldg.

REPRESENTED BY

C. T. BOWRING & CO., (Insurance) LTD.,

5 and 6 Billiter Ave., LONDON,

and at "LLOYD'S" LONDON.

HULLS AND CARGOES.

We place insurances in the most advantageous markets, employing, in the interest of our clients and with equal facility, all Foreign and Home companies, at the best procurable rates and terms.

We Represent Only the Assured

Alphabetical Index of Advertisers

on page 65 this issue.

The Blue Book of American Shipping,
Marine Directory of the World, \$5.00

Engineering

In charge of Geo. W. Richardson, formerly Chief Electrician U. S. Navy.

**Navigation**

In charge of W. J. WILSON, Graduate of U. S. Naval Academy, Annapolis, Md.


LEARN RIGHT WHILE YOU'RE AT IT

A full and complete course of instruction in Lake and Ocean Navigation and Marine and Stationary Engineering. Also special branches taught those desiring to qualify themselves for better positions in the Marine Service. Students taught by correspondence. Students may begin at any time. Diplomas will be issued to all graduates passing satisfactory final examinations. Send for Circular.

CHICAGO NAUTICAL SCHOOL 11th Year

MASONIC TEMPLE, CHICAGO, ILL.


W. J. WILSON, Principal (Late Lieutenant, U. S. N.)

Dake Pilot House**Steam Steerer**

For Tugs and Steamers. Simple, Durable, Efficient and practically noiseless. Can easily be changed to hand gear if necessary.


DAKE ENGINE CO.,

Grand Haven, Mich.

DIXON'S GRAPHITE on the Marine

Dixon's Flake Graphite unlike oil does not injure boilers; in fact, it is an excellent preventive of corrosion. 12 pages in our new edition of "Graphite as a Lubricant" treat of marine lubrication. Get copy 77-C for yourself.

Joseph Dixon Crucible Co.
Jersey City, N. J.

**THIRTY YEARS' EXPERIENCE BUILDING****Engines and Propeller Wheels.**

H. G. TROUT,
King Iron Works,
226 Ohio St.,
BUFFALO, N. Y.

**The Water Light**

Self-Igniting Inextinguishable For

Life Saving	Salvage
Distress Signal	Submarine
Repairs and	General
Construction.	Illumination.

Send for Sample. Agents wanted.

Patentees and Manufacturers

THE MARINE TORCH CO.

BALTIMORE, MD.

Especially approved by The British Board of Trade, either of Life Buoy Lights or Deck Flare.

Sheriffs' Steam Steerer**FOR TUG BOAT USE**

Easy to adjust, and can be handled by any one.

MANUFACTURED BY

Sheriffs Mfg. Co.

MILWAUKEE, WIS.

Established 1854

Aids to Navigation

are of vital importance to vessel interests.

SCHERZER ROLLING LIFT BRIDGES

aid navigation and meet with the approval of all vessel interests, because of the wide and unobstructed channel provided for navigation, enabling vessels to pass easily and rapidly through the draw.

The Scherzer Rolling Lift Bridge Co.

Main Offices: 1616 Monadnock Block,
CHICAGO, U. S. A.

Charts for Sailormen

We carry in stock a complete line of mariners' charts covering nearly every waterway on the globe. They are bound (backed if desired) in pure linen and practically indestructible. Printed in colors. Mailed anywhere on earth

Here is the list of charts for the Great Lakes. Glance them over and see if you need any of them.

NAMES OF CHARTS

LAKE ONTARIO

Lake Ontario
St. Lawrence River Nos. 1, 2, 3 4, 5, 6
Coast-Charts Nos. 1, 2, 3, 4, 5
Oswego Harbor
Little Sodus Bay
Great Sodus Bay
Charlotte Harbor
Niagara Falls

LAKE ERIE

Lake Erie
Coast-Charts Nos. 1, 2, 3, 4, 5, 6, 7
Detroit River
Lake St. Clair
St. Clair River
Buffalo Harbor and Niagara River
Dunkirk Harbor
Erie Harbor and Presque Isle
Conneaut Harbor
Ashtabula Harbor
Fairport Harbor
Cleveland Harbor
Lorain Harbor
Huron Harbor
Sandusky Bay
Maumee Bay and Maumee River

LAKE HURON

Lake Huron and Georgian Bay
South End of Lake Huron
Saginaw Bay
Straits of Mackinac
Coast-Charts Nos. 5, 6, 7, 8
Sand Beach Harbor of Refuge
Saginaw River
Tawas Harbor
Thunder Bay
Presque Isle and Middle Island
St. Marys River Nos. 1, 2, 3
St. Joseph Channel and Western End of North Channel

LAKE MICHIGAN

Lake Michigan
North End of Lake Michigan

South End of Lake Michigan
Beaver Island Group
Grand and Little Traverse Bays
Coast-Charts Nos. 1, 2, 3, 4, 5, 6, 7, 8, 9
South End of Green Bay
North End of Green Bay
Manistique Harbor
Charlevoix Harbor
South Fox Island Shoals
Manitou Passage
Frankfort Harbor
Manistee Harbor
Ludington Harbor
Muskegon Harbor
Harbor at Michigan City
Lake Front, Chicago
Milwaukee Harbor
Sheboygan Harbor
Manitowoc Harbor
Sturgeon Bay, Canal, and Harbor of Refuge
Head of Green Bay
Little Bay de Noc
Portage Lake, Manistee Co.

LAKE SUPERIOR

Lake Superior
Lake Superior Nos. 1, 2, 3
Coast-Charts Nos. 1, 6
Coast-Chart No. 8, including Isle Royal
Grand Island
Marquette and Presque Isle Harbors
Huron Bay and Huron Islands
L'Anse and Keweenaw Bay
Portage Lake and River
Copper Harbor
Agate Harbor
Eagle Harbor
Eagle River
Ontonagon Harbor
Apostle Islands Nos. 1, 2
Duluth and Superior Harbor
Agate and Burlington Bays (Two Harbors)


Write to the

BOOK DEPARTMENT

The Penton Publishing Company

Cleveland

Dredge Deck Engine for Handling Dump Scows




Wire lines are used with this machine, instead of Manila, and we have the testimony of those using them, that they will **SAVE THEIR COST IN ONE SEASON**. Built in two sizes. (The cut shows small size.)

We also build **STEAM SCOW WINDERS** for raising the hopper doors by power. **WILL WIND UP A TEN HOPPER SCOW IN TEN MINUTES.**

Write for circulars and particulars.

SUPERIOR IRON WORKS,
Superior, Wis.

THE MOSHER PATENT WATERTUBE BOILER




Simplest, lightest most compact boiler made. Most accessible for cleaning and repair. Five vertical rows or as many as 45 tubes may be cleaned or withdrawn by removing the cover from a single hand hole. Largest grate surface on a given floor space. No joints in the fire. All joints expanded. Greater steam room and water capacity than any other boiler. Built in sizes up to 2000 H. P. Mosher Boilers have been supplied for eleven torpedo boats and the monitor Florida of the U. S. Navy, amounting to over 26,000 H. P., six torpedo boats for the Russian Navy two gun boats for the Mexican government, one cruiser and one

torpedo boat for the Brazilian government; the steam yachts Arrow, El-lide, Feiseen, Wauneta, Presto, and numerous other yachts and vessels.

SEND FOR DESCRIPTIVE CATALOGUE.

MOSHER WATERTUBE BOILER CO., No. 1 Broadway, N. Y.



350 STEAM VESSELS


Now Equipped With

ALMY'S PATENT
SECTIONAL
Water Tube Boilers

Bear Evidence of Their
Excellent Qualities

ALMY WATER-TUBE
BOILER CO

PROVIDENCE, R. I.




Taylor Water Tube Boiler Co.

Vertical Tubes, sectional, large steam space and liberating area. Fire box, combustion chamber, and course for the furnace gases similar to the Scotch Marine. Free circulation type.

Send for full description.

322 Franklin St.
DETROIT, MICH.



MARINE BOILERS

OF ALL TYPES

KINGSFORD
FOUNDRY &
MACHINE
WORKS,

Oswego, N. Y.


Northwestern Steam Boiler & Mfg. Co.

DULUTH, MINN.

Manufacturers of
BOILERS, ENGINES
AND MACHINERY

Special facilities for Marine Work. Repairs promptly attended to Night or Day.


We carry a complete line of Marine and Engineers' Supplies.



TELEPHONES: OFFICE AND WORKS, 615.
RESIDENCE CALLS: M. A. RYAN, Pres. and Gen'l Mgr., 776-R.
J. H. OPPERMAN, Secretary, 579-R; E. KRIZ, Superintendent, 557-M.

LAKE ERIE BOILER WORKS

RICHARD HAMMOND, President



THE BEST EQUIPPED PLANT IN
AMERICA FOR THE MANUFACTURE
OF MODERN MARINE BOILERS

BUFFALO, N. Y.

BUYERS' DIRECTORY OF THE MARINE TRADE.

For a more complete classification than that represented by advertisers in The Marine Review, see the BLUE BOOK OF AMERICAN SHIPPING, Marine and Naval Directory of the United States, published by The Marine Review, Cleveland.

[See accompanying Index of Advertisers for full addresses of concerns in this Directory.]

AIR COMPRESSION, HOISTS.

Great Lakes Engineering Works....
.....Detroit.

AIR PORTS, DEAD LIGHTS, ETC.

Marine Mfg. & Supply Co.....
.....New York.

AIR PUMPS AND APPLIANCES.

Fore River Ship & Engine Co.....
.....Quincy, Mass.
Great Lakes Engineering Works....
.....Detroit.

ANCHORS.

Bowers, L. M. & Co.....
.....Binghamton, N. Y.

ANTI-FRICTION METALS.

Cramp, Wm. & Sons....Philadelphia.

ARTIFICIAL DRAFT FOR BOILERS.

American Ship Building Co.....
.....Cleveland.
Detroit Ship Building Co....Detroit.
Great Lakes Engineering Works....
.....Detroit.

ASH EJECTORS.

Great Lakes Engineering Works....
.....Detroit.

ATTORNEYS AND PROCTORS IN ADMIRALTY.

Gilchrist, Albert J.....Cleveland.
Goulder, Holding & Masten.....
.....Cleveland.
Hoyt, Dustin & Kelley....Cleveland.
Jenkins, Russell & Eichelberger....
.....Cleveland.
Kremer, C. E.Chicago.
MacDonald, Ray G.....Chicago.
Maytham, Frank.....Buffalo.
Shaw, Warren, Cady & Oakes.....
.....Detroit.
White, Johnson, McCaslin & Cannon
.....Cleveland.

BAROMETERS, MARINE GLASSES, ETC.

Ritchie, E. S. & Sons.....
.....Brookline, Mass.

BENDING MACHINES

Cleveland Punch & Shear Works
Co.Cleveland.

BLOCKS, SHEAVES, ETC.

Boston Lockport Block Co.....
.....Boston, Mass.

BLOWERS.

American Blower Co., Detroit, Mich.

BOAT BUILDERS.

Drein, Thos. & Son.....
.....Wilmingon, Del.
Kahnweiler's Sons, David.....
.....New York.
Truscott Boat Mfg. Co.....
.....St. Joseph, Mich.

BOILER COMPOUNDS.

The Bird-Archer Co.....New York
Dearborn Drug & Chemical Works..
.....Chicago.
State Manufacturing Co...Cleveland.

BOILER MANUFACTURERS.

Almy Water Tube Boiler Co.....
.....Providence, R. I.
American Ship Building Co.....
.....Cleveland.
Atlantic Works..East Boston, Mass.
Briggs, Marvin.....New York.
Chicago Ship Building Co..Chicago.
Cramp, Wm. & Sons..Philadelphia.
Detroit Ship Building Co....Detroit.
Fletcher, W. A. & Co.....
.....Hoboken, N. J.
Fore River Shipbuilding Co.....
.....Quincy, Mass.
Great Lakes Engineering Works....
.....Detroit.
Kingston Foundry & Machine
WorksOswego, N. Y.
Lake Erie Boiler Wks.....Buffalo
Maryland Steel Co.....
.....Sparrow's Point, Md.
McLaughlin Iron Wks ..Ashtabula, O.
Milwaukee Dry Dock Co.....
.....Milwaukee.
Mosher Water Tube Co..New York.
Newport News Ship Building Co..
.....Newport News, Va.
New York Shipbuilding Co.....
.....Camden, N. J.
Northwestern Steam Boiler & Mfg.
Co.....Duluth, Minn.
Ohio Machine & Boiler Co.....
.....Cleveland.
Quintard Iron Works Co.....
.....New York.
Roberts Safety Water Tube Boiler
Co.New York.
Superior Ship Building Co.....
.....Superior, Wis.
Taylor Water Tube Boiler Co....
.....Detroit.
Toledo Ship Building Co.....Toledo.

BOILER RIVETS.

Bourne-Fuller Co.....Cleveland.
BOILER STAYBOLTS, IRON OR
STEEL, HOLLOW OR
SOLID.
Falls Hollow Staybolt Co.....
.....Cuyahoga Falls, O.

BRASS AND BRONZE CASTINGS.

Cramp, Wm. & Sons....Philadelphia.
Fore River Ship & Engine Co.....
.....Quincy, Mass.
Great Lakes Engineering Works..
.....Detroit.
Lunkenheimer Co.....Cincinnati.

BRIDGES, BUILDERS OF.

Scherzer Rolling Lift Bridge Co....
.....Chicago.

BUCKETS, ORE AND COAL.

Brown Hoisting & Conveying Ma-
chine Co.....Cleveland.
G. H. Williams Co.....Cleveland.

CABIN AND CABINET FINISHING WOODS.

Martin-Barriss Co.....Cleveland.

CANVAS SPECIALTIES.

Baker & Co., H. H.....Buffalo.
Bunker, E. A.....New York.
Upson-Walton Co.....Cleveland.

CAPSTANS.

American Ship Windlass Co.....
.....Providence, R. I.
Dake Engine Co.....
.....Grand Haven, Mich.

Hyde Windlass Co.....Bath, Me.
Marine Mfg. & Supply Co.....
.....New York.

CEMENT, IRON FOR REPAIRING LEAKS.

Smooth-On Mfg. Co.....
.....Jersey City, N. J.

CHAIN SURVEYORS, HOISTS.

Brown-Hoisting Machinery Co.....
.....Cleveland.
General Electric Co.....
.....Schenectady, N. Y.

CHAIN HOISTS.

Boston & Lockport Block Co.....
.....Boston, Mass.

CHARTS.

Penton Publishing Co....Cleveland.

CHECK VALVES.

Scoville Check Valve Co., Ashtabula, O.

CLOCKS (Marine and Ship's Bell) AND CHRONOMETERS.

Ritchie, E. S. & Sons.....
.....Brookline, Mass.

CLOTHING, WATERPROOF.

Armstrong, E. A. Mfg. Co...Chicago.

COAL PRODUCERS AND SHIPPERS.

Hanna, M. A. & Co.....Cleveland.
Pickands, Mather & Co....Cleveland.
Pittsburg Coal Co.....Cleveland.

COAL AND ORE HANDLING MACHINERY.

Brown-Hoisting Machinery Co.....
.....Cleveland.

COMPASSES.

Ritchie, E. S. & Son.....
.....Brookline, Mass.

CONDENSERS.

Great Lakes Engineering Works....
.....Detroit.
Wheeler Condenser & Engineering
Co.....New York.

CONTRACTORS FOR PUBLIC WORKS.

Breymann Bros., G. H.....Toledo.
Buffalo Dredging Co.....Buffalo.
Dunbar & Sullivan Dredging Co....
.....Buffalo.
Great Lakes Dredge & Dock Co....
.....Chicago.
Hickler Bros.....
.....Sault Ste. Marie, Mich.
Hubbell Co., H. W..Saginaw, Mich.
Smith Co., L. P. & J. A..Cleveland.
Starke Dredge & Dock Co., C. H..
.....Milwaukee.
Standard Contracting Co..Cleveland.
Sullivan, M.....Detroit.

CORDAGE.

Baker & Co., H. H.....Buffalo.
Upson-Walton Co.....Cleveland.

"The Peer of Boiler Cleansers"

This preparation has met with wonderful success the past season in the Marine, Railroad and stationary boiler. MR. VESSEL OWNER, it will pay you to investigate our goods, and before laying up your boat for the winter, see that your boiler is treated with METLA-COTA.

It will certainly save many times its cost. Once tried you will continue to use it. Write for booklet with full information.

STATE MANUFACTURING CO.

Manufacturers of the celebrated METLA-COTA.

36 Michigan St., CLEVELAND, OHIO.



DEARBORN DRUG & CHEMICAL WORKS

WM. H. EDGAR, Founder

DEARBORN FEED-WATER TREATMENT


Made to suit the water as per analysis, used regularly, keeps boilers free from scale and prevents any corrosive action the boiler water may have on the iron.

Economy of operation is possible only with clean boilers.

20 Branch Offices in the U. S.

226-234 Postal Telegraph Bldg.,
CHICAGO

299 Broadway,
NEW YORK



ROPP'S NEW CALCULATOR

And Short Cut Arithmetic

Sustains the same relation to the BUSINESS WORLD as Webster's Dictionary to the LITERARY WORLD. If you do any "figgering" here's something you can't let go. YOU NEED IT. It's a calculator that positively calculates, in the wink of an eye too. IT'S THE THING.

Here are a FEW of the time-saving features:-

Trade Discount Tables.

Discounted at 207 different Rates and Discounts—from 1-16 of 1% to 90 and 40% off.

The Percentage Tables.

Show the equivalent of several successive discounts, etc., etc.

The Interest Tables.

Show at a glance the exact interest on any sum at all rates, for years, months and days, computed on both the 360 and 365 day bases.

The Short-Cut Arithmetic.

Contains all the rules and principles of higher arithmetic, concisely and clearly stated, illustrated by practical examples.

Commercial Law in Brief.


Explains over 70 points of law, with reference to commercial transactions.

Can you afford to miss it?

Place one on Your Desk.

195 pages, 50 illustrations. Postpaid \$1.00.

BOOK DEPARTMENT
THE PENTON PUBLISHING CO.
CLEVELAND.



The UPSON-WALTON CO., Cleveland

Atlantic Mutual Insurance Company

Atlantic Building, 51 Wall Street, New York

Insures against marine and inland transportation risk and will issue policies making loss payable in Europe and Oriental countries.

Chartered by the State of New York in 1842, was preceded by a stock company of a similar name. The latter company was liquidated and part of its capital, to the extent of \$100,000, was used, with consent of the stockholders, by the Atlantic Mutual Insurance Company and repaid, with a bonus and interest, at the expiration of two years.

During its existence the company has insured property to the value of - - - \$21,108,343,494.00
Received premiums thereon to the extent of - - - 224,197,211.06
Paid losses during that period - - - 127,760,071.08
Issued certificates of profits to dealers - - - 81,310,840.00
Of which there have been redeemed - - - 73,744,440.00
Leaving outstanding at present time - - - 7,566,400.00
Interest paid on certificates amounts to - - - 19,469,981.85
On Dec. 31, 1905, the assets of the company amounted to 12,716,427.62

The profits of the company revert to the assured and are divided annually upon the premiums terminated during the year, thereby reducing the cost of insurance.

For such dividends, certificates are issued subject to dividends of interest until ordered to be redeemed, in accordance with the charter.

ANTON A. RAVEN, Pres. THEO. P. JOHNSON, 2nd Vice-Pres.
CORNELIUS ELDERT, Vice-Pres. JAS. L. LIVINGSTON, 3rd Vice-Pres.
G. STANTON FLOYD-JONES, Secretary.

Buyers' Directory of the Marine Trade.—Continued.

CORK JACKETS AND RINGS.

Armstrong Cork Co., Pittsburgh, Pa.
Kahnweiler's Sons, D....New York.

CRANES, TRAVELING.

Brown-Hoisting Machinery Co.....
.....Cleveland.

CUTTING OFF MACHINES.

Cleveland Punch & Shear Works
Co.Cleveland.

DIVING APPARATUS.

Morse, A. J. & Son.....Boston.
Schrader's Son, Inc., A..New York.

DREDGING CONTRACTORS.

Breyman & Bros., G. H....Toledo.
Buffalo Dredging Co.....Buffalo.
Dunbar & Sullivan Dredging Co....
.....Buffalo.

Great Lakes Dredge & Dock Co..
.....Chicago.

Hickler Bros.Sault Ste. Marie, Mich.
Hubbell Co., H. W..Saginaw, Mich.

Starke Dredge & Dock Co., C. H..
.....Milwaukee.

Sullivan, M.....Buffalo.

DREDGING MACHINERY.

Quintard Iron Works Co.New York.
Superior Iron Works...Superior, Wis.

DRILLING MACHINES.

Cleveland Punch & Shear Works
Co.Cleveland.

DRY DOCKS.

American Ship Building Co.....
.....Cleveland.

Atlantic Works ..East Boston, Mass.

Buffalo Dry Dock Co.....Buffalo.

Chicago Ship Building Co.....
.....Chicago.

Cramp, Wm. & Sons..Philadelphia.

Detroit Ship Building Co.....
.....Detroit.

Great Lakes Engineering Works...
.....Detroit.

Lockwood Mfg. Co.....
.....East Boston, Mass.

Milwaukee Dry Dock Co.....
.....Milwaukee.

Newport News Ship Building Co..
.....Newport News, Va.

Superior Ship Building Co.....
.....Superior, Wis.

Tietjen & Lang Dry Dock Co.....
.....Hoboken, N. J.

Toledo Ship Building Co.....Toledo.

DYNAMOS.

General Electric Co.....
.....Schenectady, N. Y.

ELECTRIC HOISTS AND**CRANES.**

General Electric Co.....
.....Schenectady, N. Y.

ELECTRIC LIGHT AND POWER
PLANTS.

General Electric Co.....
.....Schenectady, N. Y.

ENGINE BUILDERS, MARINE.

American Blower Co., Detroit, Mich.
American Ship Building Co.....
.....Cleveland.

Atlantic Works, East Boston, Mass.
Briggs, Marvin.....New York.

Chicago Ship Building Co., Chicago.
Chase Machine Co.....Cleveland.

Cramp, Wm. & Sons, Philadelphia.
Detroit Ship Building Co., Detroit.

Fletcher, W. & A. Co., Hoboken, N. J.
Fore River Shipbuilding Co.....
.....Quincy, Mass.

Great Lakes Engineering Works...
.....Detroit, Mich.

Hall Bros.Philadelphia.

ENGINE BUILDERS—Continued.

Lockwood Mfg. Co.....
.....East Boston, Mass.

Maryland Steel Co.....
.....Sparrows Point, Md.

Milwaukee Dry Dock Co., Milwaukee.

Mosher, Chas. D.....New York.

Newport News Ship Building Co....
.....Newport News, Va.

New York Ship Building Co.....
.....Camden, N. J.

Northwestern Steam Boiler & Mfg.
Co.Duluth, Mich.

Quintard Iron Works Co., New York.

Roach's Ship Yard.....Chester, Pa.

Sheriffs Mfg. Co.....Milwaukee.

Superior Ship Building Co.....
.....Superior, Wis.

Thropp, J. E. & Sons Co.....
.....Trenton, N. J.

Toledo Ship Building Co.....Toledo.

Trout, H. G.....Buffalo.

ENGINE ROOM TELEGRAPH**CALL BELLS, ETC.**

Cory, Chas. & Son.....New York.
Marine Mfg. Supply Co., New York.

ENGINEERING SPECIALTIES**AND SUPPLIES.**

Lunkenheimer Co.Cincinnati.
Northwestern Steam Boiler & Mfg.
Co.Duluth, Minn.

**ENGINEERS, MARINE,
MECHANICAL, CONSULTING.**

Furstenau, M. C.....Philadelphia.
Hynd, AlexanderCleveland.

Hunt, Robt. W. & Co.....Chicago.

Kidd, Joseph.....Duluth, Minn.

Mosher, Chas. D.....New York.

Nacey, JamesCleveland.

Roelker, H. B.....New York.

Wood, W. J.....Chicago.

FANS.

American Blower Co., Detroit, Mich.

FEED WATER PURIFIERS AND
HEATERS.

Ross Valve Co.....Troy, N. Y.
Wheeler Condenser & Engineering
Co.New York.

FIXTURES FOR LAMPS, OIL OR
ELECTRIC.

General Electric Co.....
.....Schenectady, N. Y.

FORGINGS FOR CRANK, PRO-
PELLER OR THRUST

SHAFTS, ETC.

Cleveland City Forge & Iron Co....
.....Cleveland.

Fore River Shipbuilding Co.....
.....Quincy, Mass.

Ohio Machine & Boiler Co.....
.....Cleveland.

FLUE WELDING.

Fix's S. Sons.....Cleveland.

**FUELING COMPANIES AND
COAL DEALERS.**

Hanna, M. A. & Co.....Cleveland.

Parker Bros. Co., Ltd.....Detroit.

Pickands, Mather & Co., Cleveland.

Pittsburg Coal Co.....Cleveland.

Smith, Stanley B., & Co., Detroit.

Toledo Fuel Company,Toledo, O.

FURNACES FOR BOILERS.

Continental Iron Works, New York

GAS BUOYS.

Safety Car Heating & Lighting Co..
.....New York.

GAS AND GASOLINE ENGINES.
Chase Machine Co.....Cleveland.

GAUGES, STEAM AND VACUUM.
Lunkenheimer Co.Cincinnati.

GAUGES, WATER.

Lunkenheimer Co.....Cincinnati, O.

GENERATING SETS.

General Electric Co.....
.....Schenectady, N. Y.

GRAPHITE.

Dixon Crucible Co., Joseph.....
.....Jersey City, N. J.

HAMMERS, STEAM.

Chase Machine Co.....Cleveland.
Cleveland Punch & Shear Works
Co.Cleveland.

HEATING AND VENTILATING
APPARATUS.

American Blower Co., Detroit, Mich.

HOISTS FOR CARGO, ETC.

American Ship Building Co.....
.....Cleveland.

Brown Hoisting Machinery Co.....
.....Cleveland.

Chase Machine Co.....Cleveland.

Dake Engine Co.....
.....Grand Haven, Mich.

General Electric Co.....New York.

Hyde Windlass Co.....Bath, Me.

Marine Iron Co.....Bay City.

HOLLOW STAYBOLT IRON.

Falls Hollow Staybolt Co.....
.....Cuyahoga Falls, O.

HYDRAULIC DREDGES.

Great Lakes Engineering Works...
.....Detroit.

HYDRAULIC TOOLS.

Watson-Stillman Co., The.....
.....New York.

ICE MACHINERY.

Great Lakes Engineering Works...
.....Detroit.

Roelker, H. B.....New York.

INJECTORS.

American Injector Co.....Detroit.

Jenkins Bros.....New York.

Lunkenheimer Co.Cincinnati.

Penberthy Injector Co.....
.....Detroit, Mich.

INSURANCE, MARINE.

Atlantic Mutual Insurance Co.....
.....New York.

Belcher, Fred P.....Winnipeg.

Elphicke, C. W. & Co.....Chicago.

Gilchrist & Co., C. P....Cleveland.

Hawgood & Co., W. A., Cleveland.

Helm & Co., D. T.....Duluth.

Hutchinson & Co.....Cleveland.

McCarthy, T. R.....Montreal.

McCurdy, Geo. L.....Chicago.

Mitchell & Co.....Cleveland.

Parker Bros. Co., Ltd.....Detroit.

Peck, Chas. E. & W. F.....
.....New York and Chicago.

Prindiville & Co.....Chicago.

Richardson, W. C.....Cleveland.

Sullivan, D. & Co.....Chicago.

Vance & Joys Co.....Milwaukee.



You can take the Machine to the work,


and save almost any amount of labor over cutting and threading pipe by hand with a cutter and stock.

Armstrong's Pipe Cutting and Threading Machines are light, strong, compact and portable up to 4".

This means dollars in your pocket and you ought to investigate. Interesting and complete catalogue free.

THE ARMSTRONG MFG. CO.

314 Knowlton St., Bridgeport, Conn.



MARINE MFG. & SUPPLY CO.

157 and 158 South St., New York.

SHIP FITTINGS AND SUPPLIES


CAPSTANS, WINDLASSES,
STEERING APPARATUS, ENGINE
ROOM TELEGRAPHS, BRASS
AIR PORTS, DEAD LIGHTS,
PUMPS, ETC.

Catalogue A—Air Ports, Ventilators, etc.

Catalogue B—Windlasses, Pumps, etc.

Catalogue C—Steering Apparatus.

Others in course of preparation.



The Braender
Bilge Syphon
Always on Watch.

The BRAENDER AUTOMATIC BILGE SYPHON

when once set in place, will, without any care or attention, do its work with intelligence and promptness, as it does not waste steam when not in operation, and begins to work upon the least accumulation of water in the hold. It is simple in construction, automatic in its nature, not liable to get out of order, made of the best steam metal, and is guaranteed to keep the hold of a vessel properly dry, and do all that is claimed for it.

This automatic device has received commendation from all leading engineers throughout the country. Its simplicity of construction, durability, and entire freedom from possible disarrangement, together with its pronounced success in removing large quantities of water at a nominal cost of operation, has won for it the approval of ship-owners and seamen everywhere. With all these advantages, its moderate cost places it within the reach of every one. By giving the BRAENDER BILGE SYPHON a trial you will be convinced that it does everything we claim for it.

PHILIP BRAENDER

143 West 125th Street, New York

Iron and Brass Foundry
in Connection

Phone, Main 785
Bell 135 W


McLaughlin Iron Works

Engines, Boilers, Mill
Machinery and
General Repairing

Marine Repair Work a specialty
Let us figure on yours

180 Center Street

ASHTABULA, OHIO



Lucas' Questions and Answers for Marine Engineers

Second Revised Edition.

More than a
Hundred Illustrations.

In this second edition, in response to numerous requests, the publishers have added several subjects under the headings "Various Principles of Mathematics useful to the Engineer and Machinist," the United States regulations relating to the examination of Engineers for licenses as Chief, First, Second and Third Engineers, prescribed by the Board of Supervising Inspectors, an introduction relating to the Qualifications and Opportunities for entering the Government and Mercantile Marine Engine Room Service.

Price \$2.00 Postpaid to any address.
Money refunded if book is not entirely satisfactory.

Marine Review - Cleveland, O.

Automatic Self-Grinding Check Valves

Have you heard It?

Descriptive circular sent
on request

THE SCOVILLE CHECK VALVE CO.

ASHTABULA, OHIO

LATEST PATENT ANCHOR

THE NATIONAL

APPROVED BY LLOYDS.

Manufactured by

L. M. BOWERS & CO.,

Binghamton, N. Y.

Catalogue on Application.

The National and International

ANCHORS.

Furnished to the Lake Trade
by

The Upson-Walton Co.,

CLEVELAND, O.



Buyers' Directory of the Marine Trade---Continued.

IRON ORE AND PIG IRON.

Bourne-Fuller Co.....Cleveland, O.
Hanna, M. A. & Co.....Cleveland.
Pickands, Mather & Co., Cleveland.

LAUNCHES—STEAM, NAPHTHA, ELECTRIC.

Truscott Boat Mfg. Co.....
.....St. Joseph, Mich.

LIFE PRESERVERS, LIFE BOATS, BUOYS.

Armstrong Cork Co.....Pittsburg.
Carley Life Float Co.....
.....New York, N. Y.
Drein, Thos. & Son.....
.....Wilmington, Del.
Kahnweiler's Sons, D.....New York.

LOGS.

Nicholson Ship Log Co., Cleveland.
Walker & Sons, Thomas.....
.....Birmingham, Eng.

LUBRICATING GRAPHITE.

Dixon Crucible Co., Joseph.....
.....Jersey City, N. J.

LUBRICATORS.

Lunkenheimer Co. Cincinnati.

LUMBER.

Martin-Barriss Co. Cleveland.

MACHINISTS.

Chase Machine Co.....Cleveland.
Hickler Bros., Sault Ste. Marie, Mich.
Lockwood Mfg. Co.....
.....East Boston, Mass.
McLaughlin Iron Works, Ashtabula, O.
Ohio Machine & Boiler Co.....
.....Cleveland.
Superior Iron Works, Superior, Wis.

MACHINE TOOLS (WOOD WORKING).

Atlantic Works, Inc.....Philadelphia.

MARINE RAILWAYS

Hickler Bros., Sault Ste. Marie, Mich.

MARINE RAILWAYS, BUILDERS OF,

Crandall & Son, H. I.....
.....East Boston, Mass.

MARINE TORCHES.

Marine Torch Co.....Baltimore.

MATTRESSES, CUSHIONS, BEDDING.

Fogg, M. W.....New York

MECHANICAL DRAFT FOR BOILERS.

American Blower Co.,Detroit.
American Ship Building Co.....Cleveland.
Detroit Ship Building Co., Detroit.
Great Lakes Engineering Works.....
.....Detroit.

METALLIC PACKING.

Katzenstein, L. & Co., New York.

MOTORS, GENERATORS—ELECTRIC.

General Electric Co.....
.....Schenectady, N. Y.

NAUTICAL INSTRUMENTS.

Ritchie, E. S., & Sons.....
.....Brookline, Mass.

NAVAL ARCHITECTS.

Curr, RobertCleveland
Hynd, AlexanderCleveland
Kidd, JosephDuluth, Minn.
Mosher, Chas. D.....New York.
Nacey, JamesCleveland
Wood, W. J.....Chicago

OAKUM.

Stratford, Oakum Co.....
.....Jersey City, N. J.

OILS AND LUBRICANTS.

Dixon Crucible Co., Joseph.....
.....Jersey City, N. J.

PACKING.

Jenkins Bros.....New York.
Katzenstein, L. & Co...New York.

PAINTS.

Baker, Howard H. & Co....Buffalo.
Upson-Walton Co.....Cleveland.

PATTERN SHOP MACHINERY.

Atlantic Works, Inc. ..Philadelphia.

PILE DRIVING AND SUBMARINE WORK.

Buffalo Dredging Co.....Buffalo.
Dunbar & Sullivan Dredging Co....
.....Buffalo.
Great Lakes Dredge & Dock Co....
.....Chicago.
Hickler Bros., Sault Ste. Marie, Mich.
Hubbell Co., H. W...Saginaw, Mich.
Parker Bros. Co., Ltd.....Detroit.
Starke Dredge & Dock Co., C. H...
.....Milwaukee.
Sullivan, M.....Detroit.

PIPE, WROUGHT IRON.

Bourne-Fuller Co.....Cleveland, O.

PLANERS.

Cleveland Punch & Shear Works
Co. Cleveland.

PLANING MILL MACHINERY.

Atlantic Works, Inc....Philadelphia.
Cleveland Punch & Shear Works
Co. Cleveland.

PLATES—SHIP, STRUCTURAL, ETC.

Bourne-Fuller Co.....Cleveland, O.
Otis Steel Co.....Cleveland.

PRESSURE REGULATORS.

Ross Valve Co.....Troy, N. Y.

PROPELLER WHEELS.

American Ship Building Co.....
.....Cleveland.
Atlantic Works ..East Boston, Mass.
Cramp, Wm. & Sons..Philadelphia.
Detroit Ship Building Co.....Detroit.
Fore River Shipbuilding Co.....
.....Quincy, Mass.
Great Lakes Engineering Works....
.....Detroit.
Hyde Windlass Co.....Bath, Me.
Lockwood Mfg. Co.....
.....East Boston, Mass.
Milwaukee Dry Dock Co.....
.....Milwaukee.
Newport News Ship Building Co...
.....Newport News, Va.
Roelker, H. B.....New York.
Sheriffs Mfg. Co.....Milwaukee.
Superior Ship Building Co.....
.....Superior, Wis.
Thropp & Sons Co., J. E.....
.....Trenton, N. J.
Toledo Ship Building Co.....Toledo.
Trout, H. G.....Buffalo.

PROJECTORS, ELECTRIC.

General Electric Co.....
.....Schenectady, N. Y.

PUNCHES AND SHEARS.

Cleveland Punch & Shear Works
Co. Cleveland.

PUMPS FOR VARIOUS PURPOSES.

Great Lakes Engineering Works...
.....Detroit.
Kingsford Foundry & Machine
WorksOswego, N. Y.
Wheeler Condenser & Engineering
Co.New York.
Roelker, H. B.....New York.

REGISTER FOR CLASSIFICATION OF VESSELS.

Great Lakes Register.....Cleveland.

RIVETS, STEEL FOR SHIPS AND BOILERS.

Bourne-Fuller Co.....Cleveland, O.
Great Lakes Engineering Works....
.....Detroit.

SAFETY VALVES.

Lunkenheimer Co.....Cincinnati.

SAIL MAKERS.

Baker, Howard H. & Co....Buffalo.
Upson-Walton Co.....Cleveland.

SALVAGE COMPANIES.

See Wrecking Companies.

SEARCH LIGHTS.

General Electric Co.....
.....Schenectady, N. Y.

SHEARS.

See Punches, and Shears.

SHIP AND BOILER PLATES AND SHAPES.

Bourne-Fuller Co.....Cleveland, O.
Otis Steel Co.....Cleveland.

SHIP BUILDERS.

American Ship Building Co.....
.....Cleveland.
Atlantic Works ..East Boston, Mass.
Buffalo Dry Dock Co.....Buffalo.
Collingwood Shipbuilding Co.....
.....Collingwood, Ont.
Cramp, Wm. & Sons..Philadelphia.
Chicago Ship Building Co..Chicago.
Detroit Ship Building Co....Detroit.
Fore River Ship Building Co.....
.....Quincy, Mass.
Great Lakes Engineering Works....
.....Detroit.
Lockwood Mfg. Co.....
.....East Boston, Mass.
Maryland Steel Co.....
.....Sparrow's Point, Md.
Milwaukee Dry Dock Co.....
.....Milwaukee.
Newport News Ship Building Co...
.....Newport News, Va.
New York Shipbuilding Co.....
.....Camden, N. J.
Roach's Ship Yard.....Chester, Pa.
Toledo Ship Building Co.....Toledo.

SHIP CHANDLERS.

Baker, Howard H. & Co....Buffalo.
Marine Mfg. & Supply Co.....
.....New York
Upson-Walton Co.....Cleveland.

SHIP DESIGNERS.

Kidd, JosephDuluth.
Steel, Nacey, & Hynd....Cleveland.
Wood, W. J.....Chicago.

SHIP FLOORING.

Clemente, The C., Co....Cleveland.



The Marine Iron Company

BAY CITY, MICH.

DREDGING MACHINERY

**Centrifugal Pumps, Hoisting Engines,
Marine Engines, Machinery for All Uses.**

Boom and Crane Castings, Propeller Wheels, etc.
We shall be pleased to quote prices upon application.

Buffalo Dredging Co.

**GENERAL CONTRACTORS
—ON—
SUBMARINE WORK**

Office
D. S. Morgan Bldg.

BUFFALO, N. Y.

G. H. Breymann & Bro's

**CONTRACTORS FOR
PUBLIC WORKS**

Dredging, Dock Building, Etc.

5, 6 AND 7 MARINE BUILDING
TOLEDO, OHIO.

**Dunbar and Sullivan
DREDGING
Company**
BUFFALO, N. Y.

**REMOVE SUBMARINE
ROCK OR EARTH**

Hickler Brothers

SAULT STE. MARIE, MICH.

MARINE RAILWAY

Capacity, 1,000 tons. Draft, 7½ ft.
forward, 13½ ft. aft. Length on
keel blocks, 180 ft.; over all, 190 ft.

Machine Shop, Foundry and Steam Forge,
Dredges, Drill Boats and Derrick Scows.

C. H. STARKE DREDGE & DOCK CO.,

Contractors for Public Works.

**DREDGING, PILE DRIVING,
—AND—
SUBMARINE PIPE LAYING.**

Canal Street, West of First Avenue,
Milwaukee, - - Wisconsin.

H. W. HUBBELL CO.

**Submarine Work
of all kinds**

Dredging Hard Material a Specialty.

SAGINAW

MICH.

Buyers' Directory of the Marine Trade---Continued.

SHIP LANTERNS AND LAMPS.

Upson-Walton Co.....Cleveland.

SHIP TIMBER.

Martin-Barriss Co.....Cleveland.

SHOES.

Emerson Shoe Co.Cleveland.

SIGNALS—SUBMARINE.

Submarine Signal Co.....Boston

SMOOTH-ON COMPOUND, FOR REPAIRS.Smooth-On Mfg. Co.....
.....Jersey City, N. J.**STAYBOLT IRON OR STEEL BARS, HOLLOW OR SOLID.**Falls Hollow Staybolt Co.....
.....Cuyahoga Falls, O.**STEAM VESSELS FOR SALE.**

Holmes, SamuelNew York.

McCarthy, T. R.....Montreal, Can.

STEAMSHIP LINES, PASS, AND FREIGHT.

American LineNew York.

Boston SteamshipBoston.

C. & B. Transit Co.....Cleveland.

International Mercantile Marine Co.
.....Philadelphia.

Mallory LineNew York.

New York & Cuba Mail S. S. Co..
.....New York.

Red Star LineNew York.

Ward LineNew York.

STEEL CASTINGS.

Otis Steel Co.....Cleveland.

STEERING APPARATUS.

American Ship Building Co.....

.....Cleveland.

Chase Machine Co.....Cleveland.

Dake Engine Co.....

.....Grand Haven, Mich.

Detroit Ship Building Co....Detroit.

Hyde Windlass Co.....Bath, Me.

Marine Mfg. & Supply Co.....

.....New York.

Sheriffs Mfg. Co.....Wilwaukee.

SUBMARINE DIVING APPARATUS.

Morse & Son, A. J.....Boston.

Schrader's Son, Inc. A....New York.

SURVEYORS, MARINE.

Hynd, AlexanderCleveland.

Parker Bros. Co., Ltd.....Detroit.

Nacey, JamesCleveland.

SURVEYORS, MARINE—Continued.

Steel, AdamCleveland.

Wood, W. J.....Chicago.

SYPHONS.

Philip Braender....New York City.

TESTS OF MATERIALS.

Hunt, Robert W. & Co....Chicago.

Lunkenheimer Co.....Cincinnati, O.

THERMITGoldschmidt Thermit Co.,
.....New York City.**THREAD CUTTING TOOLS.**

Armstrong Manufacturing Co.

.....Bridgeport, Conn.

TOOLS, METAL WORKING, FOR SHIP AND ENGINE WORKS.

Watson-Stillman Co.....New York.

TOOLS, WOOD WORKING.

Atlantic Works, Inc....Philadelphia.

TOWING MACHINES.

American Ship Windlass Co.....

.....Providence, R. I.

Chase Machine Co.....Cleveland

TOWING COMPANIES.Donnelly Salvage & Wrecking Co..
.....Kingston, Ont.

Great Lakes Towing Co..Cleveland.

TRUCKS.Boston & Lockport Block Co.....
.....Boston.**TUBING, SEAMLESS.**

Shelby Steel Tube Co.Pittsburg, Pa.

VALVES, STEAM SPECIALTIES, ETC.

Jenkins Bros.New York

Lunkenheimer Co.....Cincinnati.

Ross Valve Co.....Troy, N. Y.

VALVES FOR WATER AND GAS.

Ashton Valve Co.....Boston.

Lunkenheimer Co.....Cincinnati.

Ross Valve Co.....Troy, N. Y.

Scoville Check Valve Co.....

.....Ashtabula, O.

VESSEL AND FREIGHT AGENTS.

Billett, T. R.....Winnipeg.

Boland, John J.....Buffalo.

Douglas, G. L. Jr.....Duluth

Elphicke, C. W. & Co.....Chicago.

Hall, John B.....Buffalo.

Helm & Co., D. T.....Duluth.

VESSELS AND FREIGHT AGENTS—Con.

Hawgood & Co., W. A....Cleveland.

Holmes, SamuelNew York.

Hutchinson & Co.....Cleveland.

McCarthy, T. R.....Montreal.

Mitchell & Co.....Cleveland.

Parker Bros. Co., Ltd.....Detroit.

Prindiville & Co.....Chicago.

Richardson, W. C.....Cleveland.

Sullivan, D. & Co.....Chicago

WATER GAUGES.

Lunkenheimer Co.....Cincinnati, O.

WHISTLES, STEAM.

Lunkenheimer Co.....Cincinnati.

WILFORD'S WATERPROOF CLOTH.

Bunker, E. A.....New York.

WIRE ROPE AND WIRE ROPE FITTINGS.

Baker, H. H. & Co.....Buffalo.

Upson-Walton Co.....Cleveland.

WINDLASSES.

American Ship Windlass Co.....

.....Providence, R. I.

American Ship Building Co.....

.....Cleveland.

Dake Engine Co.....

.....Grand Haven, Mich.

Hyde Windlass Co.....Bath, Me.

Marine Mfg. & Supply Co.....

.....New York.

WINCHES.

American Ship Windlass Co.....

.....Providence, R. I.

Hyde Windlass Co.....Bath, Me.

WOOD WORKING MACHINERY.

Atlantic Works, Inc....Philadelphia.

WRECKING AND SALVAGE COMPANIES.Donnelly Salvage & Wrecking Co..
.....Kingston, Ont.

Great Lakes Towing Co..Cleveland.

Parker Bros. Co., Ltd.....Detroit.

YACHT AND BOAT BUILDERS.

Drein, Thos. & Son.....

.....Wilmington, Del.



Truscott Boat Mfg. Co.....

.....St. Joseph, Mich.

YAWLS.

Drein, Thos. & Son.....

.....Wilmington, Del.

**GASOLENE MARINE ENGINES**Suitable for all Boats from 3½ to 200 HP.
Over 100 in successful use.Also the well known and always
reliable Woolters Gas or Gasolene
Stationary Engines.**HOISTING ENGINES**Of all kinds and sizes, and
for all purposes, especially
for ship use.Docking and Hauling Engines
and Wire Rope Windlasses.**AUTOMATIC TOWING MACHINES**Somewhat the cheapest, and
altogether the best. Positively
guaranteed.Automatic Fog Whistle Machines
Steam Steering Engines.

FOR THESE AND OTHER WELL KNOWN SPECIALTIES ADDRESS ALL INQUIRIES TO.

THE CHASE MACHINE CO. Engineers and Machinists, CLEVELAND, OHIO.

M. SULLIVAN

DREDGING OF ALL KINDS

THE REMOVING OF DEEP
WATER EARTH AND ROCK
A SPECIALTY. - - -

721 West Ferry St.
BUFFALO, - - - N. Y.

THE
Standard Contracting Co.

ENGINEERS AND CONTRACTORS

For Railroads, Dredging, Dock Build-
ing, Concrete, Submarine work, &c.

Wade Building

Cleveland, Ohio

**CATALOGS
WANTED.**

We are requested to in-
form the INDUSTRIALS
of all branches that our
French contemporary,
"LE MOIS SCIENTIFIQUE ET INDUS-
TRIEL" of 8 rue Nouvelle
at PARIS, 9°, has estab-

lished an Information Branch from which particulars on any
question may be obtained.

It is of great interest for all manufacturers to send
regularly their "Catalogues" to "Le Mois Scientifique et
Industriel" from where they will be forwarded to every one
interested in the line.

Do not delay to send them and note the address is

LE MOIS SCIENTIFIQUE ET INDUSTRIEL
8 rue Nouvelle at Paris--9°


Ask for a specimen notice free on application.

The Toledo Fuel Co.

Toledo, Ohio

Steamboats sup-
plied with West
Va. and Ohio
coals from docks
or lighter.

A. M. DONOVAN,
PRES. & GEN. MGR.

**Steamboat Fuel at Ashtabula**

Large Supplies of Best Quality.



Lighter Carrying Different
Grades at All Times.


Fuel Scow with elevators and discharging spouts. Storage of 800 tons.
Discharges 250 tons an hour into steamers while unloading cargo.

M. A. Hanna & Co., Miners and Shippers.

Main Office, Perry-Payne Bldg., Cleveland.

PICKANDS, MATHER & CO.

FUEL LIGHTERS at Buffalo, Erie, Ashtabula and Cleveland.



A. Detour, Mich., a Fuel Dock
equipped with shute capacity of
600 tons. Best quality Pittsburgh
coal furnished at any time during
Day or Night.

Western Reserve Building,

CLEVELAND, O.

OTIS STEEL

SHIP PLATES

FLANGE PLATES

TANK PLATES

STEEL CAR AXLES

FORGINGS OF ALL KINDS

"Otis" Fire Box Plates a Specialty.

STEEL CASTINGS FROM 100 TO 100,000 LBS.

OTIS STEEL CO., Ltd., Head Office and Works, **CLEVELAND, O.**

New York: Thorpe, Platt & Co., 97 Cedar St.
Montreal: Homer Taylor, 183 St. James St.

AGENCIES.


Detroit: George W. House, Union Trust Building.

St. Louis: C. A. Thompson, 516 N. Third St
San Francisco: John Woodlock, 154-156 First St.

Ashton Highest Grade Pop Safety Valves and Steam Gages

Guaranteed to give
Unequalled Efficiency, Durability and Perfect Satisfaction.

Special Features in valves.



Outside Pop Regulation.

Cam Lever Attachment.

Jessops Steel Spring.

Gages have
Non-Corrosive Movements.

Accurately Graduated Dials.

Seamless Drawn Springs.



Specify the Ashton and Get the Best.

THE ASHTON VALVE COMPANY.

271 Franklin St. - BOSTON, MASS.

Branches : New York. Chicago. Philadelphia. San Francisco.

Smith's Coal Dock

DETROIT RIVER
DETROIT MICH.,

**12 Pockets. Platform.
Low Dock.**

Operated by

STANLEY B. SMITH & CO.

G

Wrecking Steamer FAVORITE

Located at St. Ignace this Year.

The Wrecking Steamer FAVORITE, Alex. Cuning, Master, will be stationed during season 1906 at ST. IGNACE, MICH. A Long-Distance Telephone has been installed on board the steamer. When at her home dock, the steamer can be reached by telephone any time day or night, 'Phone Number 63, and in absence of steamer full information as to the steamer may be obtained by telephoning to residence of Capt. Cuning, St. Ignace.

The Favorite and her equipment were thoroughly overhauled during the past winter, and are in first class condition to do outside work.

WARD LINE

THE NEW YORK & CUBA MAIL
STEAMSHIP CO.

POPULAR ROUTE TO

CUBA, NASSAU, MEXICO

FINEST AND LARGEST STEAMSHIPS SAILING
FROM NEW YORK TO OTHER THAN EUROPEAN
PORTS. HOLDERS OF THE RECORD BETWEEN
HAVANA AND NEW YORK — 1,240 MILES IN 61
HOURS.

FOUR SAILINGS EACH WEEK BETWEEN
NEW YORK and HAVANA.

WEEKLY SERVICE TO GUANTANAMO, SANTIAGO, MANZANILLO
AND CIENFUEGOS, CUBA, PROGRESO, VERA CRUZ
AND TAMPICO, MEXICO.

SEMI-MONTHLY SAILINGS TO

Nassau, N. P. Bahamas.

LOW RATES OF FREIGHT AND PASSAGE.

SEND FOR OUR SCHEDULES, RATES AND DESCRIPTIVE MATTER.

James E. Ward & Co.

GENERAL AGENTS

90 Wall Street, NEW YORK.

AMERICAN LINE

PLYMOUTH
CHERBOURG
SOUTHAMPTON

Sailing From New York Every Saturday at 9.30 a. m.

St. Louis
(11,629 tons)
New York
(10,798 tons)

St. Paul
(11,629 tons)
Philadelphia
(10,786 tons)

Special Express Train from Plymouth and Southampton
to London and between Cherbourg and Paris.

RED STAR LINE

NEW YORK
ANTWERP
LONDON
PARIS

CALLING AT DOVER FOR LONDON AND PARIS.

Sailing Wednesday from Pier 14, North River, N. Y.

Finland
(12,760 tons)

Kronland
(12,760 tons)

Vaderland
(12,017 tons)

Zeeland
(11,905 tons)

One of the Shortest Routes to LONDON, PARIS, BELGIUM, HOLLAND,
GERMANY, THE RHINE, SWITZERLAND and ITALY.

9 Broadway, New York.

1819 Walnut St., Philadelphia.
India Building, 84 State St., Boston.
1906 F St., N. W., Washington, D. C.
219 St. Charles St., New Orleans.
90-96 Dearborn St., Chicago.
900 Locust St., St. Louis.
121 South Third St., Minneapolis.
207 Monadnock Bldg., San Francisco.
9 East Sixth St., St. Paul.
41 King St., East Toronto.
17 St. Sacramento St., Montreal.

PIERS: 14 & 15 NORTH

RIVER, FOOT OF FUL-

TON ST., NEW YORK.

"MALLORY LINE"

(New York & Texas Steamship Company)

Steamers Leave Piers New 15, 16 East River, NEW YORK

For GALVESTON, TEXAS

Every WEDNESDAY and SATURDAY, taking FREIGHT for all Points in
TEXAS, MEXICO, NEW MEXICO, ARIZONA, UTAH, KANSAS, OKLA-
HOMA, MISSOURI, COLORADO and CALIFORNIA.

Saturday's Steamer touches at Key West, Fla.

For MOBILE, ALA.

A Steamer sails every FRIDAY, 3 p. m., taking FREIGHT for ALABAMA,
MISSISSIPPI, MISSOURI and the SOUTHWEST.

For BRUNSWICK, GA.

A Steamer sails every FRIDAY, 3 p. m., taking FREIGHT for all Points in
GEORGIA, FLORIDA, ALABAMA, LOUISIANA and the SOUTH and
SOUTHWEST.

PASSENGER DEPARTMENT

Six days Ocean voyage to GALVESTON, Texas, thence by rail to All points
South-west. Six days to MOBILE, Ala., through tickets to NEW
ORLEANS. 66 hours to BRUNSWICK, Ga., thence rail to Interior South-
eastern Points.

An especially attractive route through famous "SEA ISLANDS" to
JACKSONVILLE, Florida.

Through Bill of Lading. Insurance at lowest rates.

C. H. MALLORY & CO., General Agents,

129 Front Street

Branch Office, 385 Broadway, New York.

BOSTON STEAMSHIP CO.

S. S. "SHAWMUT" S. S. "TREMONT" S. S. "LYRA"

Japan, South China and Manila Steamship Line

Operated in connection with the

**Northern Pacific and Great Northern
Railway Companies.**

Monthly Passenger and Freight Service from
Tacoma and Seattle, Washington.

New Twin-screw American Steamships of
10,000 tons register. Exceptionally large
staterooms, all outside.

OWING TO THE GREAT SIZE OF THE SHIPS,
AND THE IMMENSE CARGOES CARRIED IT HAS
NEVER BEEN NECESSARY TO USE RACKS ON
THE DINING TABLES.

Rates at any office of

NORTHERN PACIFIC RAILWAY,
GREAT NORTHERN RAILWAY,
CHICAGO, BURLINGTON & QUINCY RAILWAY,
THOMAS COOK & SONS, Tourists Agents.

A. WINSOR, PRES.
Boston, Mass.

F. WATERHOUSE, AGENT,
Seattle, Wash.



THE CLEVELAND & BUFFALO

TRANSIT COMPANY

UNPARALLELED NIGHT SERVICE

The Twin Flyers of The Lakes

"CITY OF BUFFALO" "CITY OF ERIE"

Both together being, without doubt, in all respects the finest and fast-
est that are run in the interest of the traveling
public in the United States.

TIME CARD.—DAILY INCLUDING SUNDAY. CENTRAL STANDARD TIME.

Leave CLEVELAND 8 p. m. Arrive BUFFALO 6:50 a. m.

" BUFFALO 8 p. m. " CLEVELAND 6:30 a. m.

Connections made at Buffalo for all Eastern and Canadian points;
at Cleveland for Toledo, Detroit and all points West and Southwest.

Tickets reading over L. S. & M. S. Ry. will be accepted

on this Company's Steamers without extra charge.

Special Low Rates Cleveland to Buffalo and Niagara Falls every
Saturday Night, also Buffalo to Cleveland. Ask Ticket Agents for
tickets via C. & B. Line. Send four cents for illustrated pamphlet.

W. F. HERMAN, G. P. A., Cleveland, O.

VESSEL AND INSURANCE AGENTS.

FRED P. BELCHER,
Vessel and Insurance Agent,
430 Grain Exchange,
WINNIPEG, MAN.
P. O. Box 230.

T. R. BILLET, T,
Vessel Agent
811 Union Bank Building,
WINNIPEG.

JOHN J. BOLAND & CO.,
Vessel and Insurance Agents.
800-804 Prudential Bldg.
Both Phones. BUFFALO, N. Y.

G. L. DOUGLASS, JR.,
Vessel Agent.
DULUTH, MINN.
Telephones: Office { Bell 878.
Residence. { Zenith 14.
Bell 561.

C. W. Elphicke. J. J. Rardon.
C. W. ELPHICKE & CO.
Vessel and Insurance Agents.
No. 6 Sherman St. CHICAGO, ILL.
Telephone, Harrison 1194.

JOHN B. HALL,
Vessel Agent.
17 Exchange Bldg., 202 Main St.,
Telephone, Seneca 892.
BUFFALO, N. Y.

W. A. Hawgood. Arthur H. Hawgood.
W. A. HAWGOOD & CO.
Vessel and Insurance Agents.
220-21 Perry-Payne Bldg., Cleveland, O.
Telephones: { Office, Main 2395.
{ Res. W. A. Hawgood, Doan 84-J.
{ Res. A. H. Hawgood, Doan 841-J.

D. T. HELM & CO.
Vessel and Insurance Agents.
Telephones—Office 263.
—Res. 381-3.
DULUTH, - - - MINN.

SAMUEL HOLMES,
Steamship Offices,
For Selling, Chartering and Building all
Classes Steam Vessels.
Steam Vessel Circulars.
Weekly Freight Circulars.
Morris Bldg., 66-8 Broad St., New York.

1906
Nautical Almanacs
PRICE 50c
Order from THE MARINE REVIEW

VESSEL AND INSURANCE AGENTS.

C. L. Hutchinson. W. H. McGean.
HUTCHINSON & CO.
Vessel and Insurance Agents.
Phones: { Office, Main 2453.
{ Res. C. L. Hutchinson, Lake 244.
{ Res. W. H. McGean, Doan 274.
1408 Rockefeller Bldg. Cleveland.

FRANK MAYTHAM,
Attorney and Counsellor at Law
Proctor in Admiralty.
10 Marine Exchange Bldg., BUFFALO, N. Y.

T. R. MCCARTHY,
Steamship and Freight Broker.
Chartering, Forwarding and General Com-
mission Agent; and Broker for the Sale,
Purchase and Construction of Steamers
and Sailing Vessels.
Cable Address, "Macarthy, Montreal."
(Watkins', Scott's Liebers and A. B. C.
Codes Used.)
Shipping Agent to The Asbestos & Asbestic
Co., Ltd., of Asbestos Que. The Belgo
Canadian Pulp & Paper Co., Ltd., of
Shawinigan Falls, Que. Edward Lloyd, Ltd.
Paper Manufacturer, of London (Eng.).
404 Board of Trade Bldg., MONTREAL, CAN.
Correspondence Invited and Agencies
Solicited.

J. Mitchell. J. F. Wedow. A. Mitchell.
MITCHELL & CO.
Vessel and Insurance Agents
1504-6-8 Rockefeller Bldg., Cleveland, O.
Office Tel. M. 767. Res. John Mitchell, Doan 341.
John F. Wedow, Doan 141-J.
Alfred Mitchell, Doan 218.

PARKER BROS. CO., LTD.,
Vessel, Marine Insurance and Wreck-
ing Agents. Marine Surveyors.
Office Tel. Main 5314. Night: Main 290
Night: Grand 1723 J.
15 Atwater St. West, DETROIT, MICH.

W. C. RICHARDSON,
Vessel Owner and Broker and
Marine Insurance Agent.
420-421 Perry Payne Building,
CLEVELAND, O.
Office Tel. 338. Residence Tel. 2938.

D. Sullivan. F. J. Sullivan.
D. SULLIVAN & CO.
Vessel Agents.
Marine Insurance.
2-4 Sherman St., CHICAGO, ILL.
Office Tel., Harrison 2847. Res. Ashland 2483.

VANCE & JOYS CO.
Vessel and Insurance Agents
No. 21 NEW INSURANCE BUILDING,
TELEPHONE MAIN 99.
MILWAUKEE, WIS.

MARINE INSURANCE,
by
WILLIAM GOW.
Price, \$1.50.
THE PENTON PUB. CO.,
Cleveland, O.

PROCTORS IN ADMIRALTY.

ALBERT J. GILCHRIST,
Proctor in Admiralty.
Rockefeller Building,
CLEVELAND, O.

GOULDER, HOLDING &
MASTEN,
Law Offices.
H. D. Goulder. S. H. Holding. F. S. Masten.
Perry-Payne Building,
CLEVELAND, O.

HOYT, DUSTIN & KELLEY,
Lawyers and Proctors in Admiralty.
Offices, 702 Western Reserve Bldg.,
CLEVELAND, O.

JENKINS, RUSSELL
& EICHELBERGER,
Attorneys-at-Law
and Proctors in Admiralty.
1520 Rockefeller Bldg. CLEVELAND.

C. E. KREMER,
Counselor at Law and
Proctor in Admiralty.
Suite 1505-1506-1507 Fort Dearborn Bldg.,
CHICAGO, ILL.

RAY G. MacDONALD,
Attorney-at-Law and
Proctor in Admiralty.
1018 Hartford Building,
Telephone, Central 2484 CHICAGO, ILL.

SHAW, WARREN, CADY &
OAKES,
Attorneys-at-Law.
and Proctors in Admiralty.
Union Trust Bldg., Detroit, Mich.

WHITE, JOHNSON,
McCASLIN & CANNON,
Attorneys-at-Law and
Proctors in Admiralty.
Williamson Bldg., CLEVELAND, O.

NAVAL ARCHITECTURE,
by
THOS. H. WATSON.
A manual on laying off iron and steel
vessels. Valuable for naval architects as
well as beginners in ship yards.
Price, \$5.00.

Order from
THE PENTON PUB. CO.,
Cleveland, O.

PROFESSIONAL.

ROBERT W. HUNT & CO.,

*Bureau of Inspection.
Tests and Consultation.*

1121 The Rookery, CHICAGO.
Monong. Bank Bldg., PITTSBURG.
66 Broadway, NEW YORK.

Inspectors of shipbuilding material and machinery. Inspectors of all materials. Duty tests of engines and boilers. Physical and chemical laboratories.

PROFESSIONAL.

James Nacey. Alexander Hynd.

NACEY & HYND,
*Marine Architects,
Mechanical Draughtsmen,
Consulting Engineers.*

Specifications and designs for all descriptions of marine vessels, engines and boilers. Supervision of construction and repairs. Damage and other surveys carefully attended to.

Agents for Marine Specialties.

208-9 Western Reserve Building,
CLEVELAND, O.
Phone, Main 3339 J.

PROFESSIONAL.

W. J. WOOD,

Naval Architect, Consulting Engineer.

Prepares designs or working drawings and specifications for all classes of vessels and superintends construction and repairs. Surveys damaged property and estimates cost of repairs. Arbitrator and court expert.

FIRE BOATS A SPECIALTY.

Complete Plans furnished for Steel, Composite or Wooden Vessels.

543 Postal Telegraph Bldg.
Tel. Harrison 1020. CHICAGO.

JOSEPH KIDD,

*Marine Architect and Surveyor.
Consulting Ship Builder and Engineer*

Over thirty years' experience. Specifications, designs and estimates. Superintendence of construction and repairs. Damage and other surveys carefully attended to. Negotiations for the building, charter or sale of all kinds of vessels and machinery.

610 Board of Trade,
DULUTH, MINN.

M. C. FURSTENAU

*Consulting Marine Engineer and
Naval Architect*

All classes of vessels and machinery designed. Tests and surveys made.

308 Walnut St.
Tel. Lombard 279A PHILADELPHIA, PA.

JUST PUBLISHED

CLASS BOOK OF
NAVAL ARCHITECTURE

BY W. J. LOVETT Price \$2.50
Illustrated Order from Marine Review, Cleveland.

ROBERT CURR,

Naval Architect and Surveyor.

Specifications and Designs furnished for all types of vessels. Supervision of Construction and Repairs. Damage and other surveys carefully attended to. Piece work price lists and cost of labor a specialty.

1024 Rockefeller Bldg., CLEVELAND, OHIO

NAVAL ARCHITECTS' AND
ENGINEERS' DATA BOOK,

By T. H. WATSON.

Price, \$1.50.
THE PENTON PUB. CO.,
Cleveland, O.

Weekly. Illustrated. Price 6d.

"The Shipping World"

Written by Experts. Illustrated by Artists.

DEVOTED TO THE INTERESTS
OF A SHIP AND HER CARGO

SPECIAL FEATURES:

Current Events, by the Editor.
Special Articles on TRADE, COMMERCE, SUBVENTIONS,
and all SHIPPING QUESTIONS.
Shipping in Parliament.
Shipping and the Law.
Ship Sales and Contracts.
Neptune's Mail, with exclusive News and Notes.
Notes by a Naval Architect, written by Practical Scholars.
Reports on Freight and Marine Insurance.
Trade and Finance.
Board of Trade Notes.
Reviews.
Prices Current.
Launches and Trial Trips.

Orders for subscription to "The Shipping World" are received at the office of the MARINE REVIEW.

ANNUAL SUBSCRIPTION:
United Kingdom, 21s. Foreign Countries, 28s.

THE "SHIPPING WORLD," LTD.,
EFFINGHAM HOUSE, ARUNDEL STREET, STRAND,
LONDON, W. C.

Prindiville & Company

INCORPORATED

**AVERAGE ADJUSTERS
AND
INSURANCE BROKERS**

234 La Salle St.

Chicago, Ill.

Representing
Johnson & Higgins
New York

Foreign Representatives
Willis Faber & Co., Ltd., London.
John D. Tyson & Co., Liverpool.

HAWKINS' WORKS FOR
ENGINEERS

Popular among young men in the engine departments of ships is
"Engineers' Examinations with Questions and Answers"
Sells at \$2.00, which is the cost delivered, of the following works:

Hawkins' New Catechism of Electricity
Hawkins' Maxims and Instructions for the Boiler Room.
Hawkins' Hand Book of Calculations for Engineers.
Hawkins' New Catechism of the Steam Engine.

THE MARINE REVIEW, CLEVELAND.

WRITE US
FOR ANY BOOK ON
MECHANICAL SUBJECTS.
The Penton Publishing Co.
Cleveland.

PATENTS
TRADEMARKS AND COPYRIGHTS.
25 Years Practice.

Specialty: "Working on the Failures of Others"
SIGGERS & SIGGERS PATENT LAWYERS
Suite 11, National Union Ins. Bldg., Washington, D. C.

FALLS HOLLOW STAYBOLT Co.
 ANY SIZE OUTSIDE OR INSIDE DIAMETER.
 AVERAGE LENGTH OF HOLLOW BARS
 EIGHT TO TEN FEET.
STAYBOLT BARS
 BOTH HOLLOW AND SOLID.
 MADE OF BEST QUALITY DOUBLE REFINED CHARCOAL
 IRON OR STEEL. CUYAHOGA FALLS, O. U.S.A.

Safety and Coal Economy
 are realized by our Hollow Stay Bolts. Steam from the center of a broken Hollow bolt always gives positive warning, hence

SAFETY
 Air passing into the firebox through the hollow bolt helps combustion, hence

ECONOMY
 Tell-tale holes clog up. Hollow stays "never." Passage of air always keeps the holes open.
Send for free literature.

Falls Hollow Staybolt Company
 Cuyahoga Falls, Ohio


GEO. STRATFORD OAKUM CO.
 JERSEY CITY, NEW JERSEY. Established 1860

Manufacturers of all grades of **Oakum**
 Spun Cotton

GEO. STRATFORD OAKUM CO.
 JERSEY CITY, N. J.
BEST OAKUM

FOR SALE AT SHIP CHANDLERS EVERYWHERE.

TRUSCOTT
 The Dependable Marine Motor



Made to withstand the most severe and continuous service. A practical design characterized by the accessibility, compactness and simple ignition gas producing and oiling features. Perfect control.

Four cycle type, two and four cylinders, from 8 to 65 H.P. Smaller sizes of the two cycle type.

Catalogue and copy of The Launch for the asking.
 Department 46.

Truscott Boat Mfg. Co.
 ST. JOSEPH, MICHIGAN.

Going to Pittsburg

- 1 The Erie Railroad is the only road that sterilizes and purifies, through a process invented by its own chemist, its Passenger coaches, Parlor cars, Cafe cars, Dining cars and Sleepers, a very essential safe-guard to its patrons, for it kills all poisonous germs and makes traveling in such sterilized cars absolutely safe in preventing disease infection.
- 2 The Erie Railroad has the largest passenger locomotives in the world—only eleven words but they mean a good deal.
- 3 The Erie Railroad has built and uses a steel Baggage car—something new on steam roads.
- 4 The Erie Railroad is the road that runs every day (not every day except Sunday, but every day). Seven fine passenger trains from Cleveland to Pittsburg and seven from Pittsburg to Cleveland—that's fourteen fine passenger trains daily between the two cities.
- 5 The following may surprise you—The Erie Railroad—was the first railroad in the world to run sleeping cars. The Company built two cars, known by the names of "Ontario" and "Erie", remember please that this was before Pullman or Wagner Cars existed.
- 6 Patrons of the Erie Cafe Club cars Cleveland to Pittsburg have FREE use of the spacious lounging and smoking parlors of the car.

FERRALL'S HUB HOISTER AND Sheave for Same.



The sheaves of these hoisters are fitted with Star Metaline Bushings and Side Bearings, which keep the sheaves from heating, make them run true and together with the rounded edges of the shells, soon save more than their cost, by preserving the rope.

BOSTON & LOCKPORT BLOCK CO.
 BOSTON - MASS.

Ritchie Liquid Compass



The Standard Liquid Compass used exclusively by the U. S. Navy for over 35 years. Over 32,000 used in Merchant Service.

Made in all sizes and styles, from 2 to 12 inches diameter of card. All compasses made by us have our name printed below the North point or prominently upon the card. **None other are genuine.** Latest form with four or six needles, the best instrument for iron ships. For sale by ship chandlers and nautical instrument dealers. Catalogue free.

E. S. RITCHIE & SONS, Brookline, Mass., U. S. A.
 MANUFACTURERS OF NAUTICAL AND PHYSICAL APPARATUS.

ALPHABETICAL INDEX OF ADVERTISERS IN THE MARINE REVIEW.

The star (*) indicates that the advertisement appears alternate weeks. For addresses see advertisements on page noted.
The dagger (+) indicates that advertisement appears once a month.

Akers Steering Gear Co. 11	Detroit Ship Building Co. 4	Lake Erie Boiler Wks. 51	Safety Car Heating & Lighting Co. 15
Almy Water Tube Boiler Co. 51	Dixon Crucible Co., Joseph 49	Le Mois Scientifique et Industriel 59	Scherzer Rolling Lift Bridge Co., 14
American Blower Co. 68	Donnelly Salvage & Wrecking Co. 65	Lockwood Mfg. Co. 66	Schrader's Son, Inc., A. 66
American Injector Co. 13	Douglas, G. L., Jr. 62	Lunkenheimer Co. 13	Scoville Check Valve Co. 55
American Line 61	Dreih, Thos., & Son 65		Shaw, Warren, Cady & Oakes 62
American Ship Building Co. 2	Dunbar & Sullivan Dredging Co. 57		*Shelby Steel Tube Co. 14
American Ship Windlass Co. 4			Sheriffs Mfg. Co. 49
Armstrong Cork Co. 68	Elphicke, C. W., & Co. 62	MacDonald, Ray G. 62	Shipping World Year Book. 63
Armstrong Mfg. Co. 55	Emerson Shoe Co. 15	Mallory Line 61	Siggers & Siggers 63
Armstrong Mfg. Co., E. A. 15	Erle Railroad Co. 64	Marine Torch Co., The. 49	Smith Coal & Dock Co., Stanley B. 60
*Ashton Valve Co. 80		Marine Iron Co. 57	Smooth-On Mfg. Co. 67
Atlantic Mutual Ins. Co. 48	Falls Hollow Staybolt Co. 64	*Marine Mfg. & Supply Co. 55	Standard Contracting Co. 59
Atlantic Works 65	Fix's, S., Sons 66	Martin-Barriss Co. 65	Starke, C. H., Dredge & Dock Co. 57
*Atlantic Works, Inc. 14	Fletcher, W. & A., Co. 65	Maryland Steel Co. 10	Stratford Oakum Co., Geo. 64
	Fogg, M. W. 66	Maytham, Frank 62	*State Manufacturing Co. 53
Baker, Howard H., & Co. 68	Fore River Shipbuilding Co. 65	McCarthy, T. R. 62	*Submarine Signal Company 9
Belcher, Fred P. 62	Furstenau, M. C. 63	McCurdy, Geo. L. 47	Sullivan, M. 59
Big Four Route 53		McLaughlin Iron Works. 55	Sullivan & Co. 62
Billett, T. R. 62	General Electric Co. 68	Milwaukee Dry Dock Co. 5	Superior Iron Works 51
Boland, J. J. 62	Gilchrist, Albert J. 11	Mitchell & Co. 62	Superior Ship Building Co. 4
Boston & Lockport Block Co. 64	*Goldschmidt Thermit Co. 11	Morse & Son, A. J. 49	
Boston Steamship Co. 61	Gould's Nautical School 48	Mosher Water-Tube Boiler Co. 51	
Bourne-Fuller Co. 3	Goulder, Holding & Masten 62		
Bowers, L. M., & Co. 56	Great Lakes Dredge & Dock Co. 16	Nacey & Hynd 63	
Braender, Philip 56	Great Lakes Engineering Works 16	Newport News Ship Building & Dry Dock Co. 6	
Breyman & Bros., G. H. 57	Great Lakes Register 48	New York & Cuba Mail S. S. Co. 61	
Briggs, Marvin 48	*Great Lakes Towing Co. 60	New York Shipbuilding Co. 7	
*Brown Hoisting Machinery Co. 8		*Nicholson Ship Log Co. 2	
Buffalo Dredging Co. 57	Hall, John B. 62	Northwestern Steam Boiler & Mfg. Co. 51	
Buffalo Dry Dock Co. 6	Hanna, M. A., & Co. 59		
Bunker, E. A. 68	Hawgood, W. A., & Co. 62	Ohio Machine & Boiler Co. 47	
	Helm, D. T., & Co. 62	Otis Steel Co. 59	
*Carley Life Float Co. 15	Hickler Bros. 57		
Chase Machine Co. 58	Holmes, Samuel 62	Parker Bros. Co. 62	
Chicago Nautical School 49	Hoyt, Dustin & Kelley. 57	Peck, Chas. E. & W. F. 48	
Chicago Ship Building Co. 4	Hubbell Co., H. W. 57	Penberthy Injector Co. 13	
Clemente, The C. Co. 65	Hunt, Robert W., & Co. 63	Pickands, Mather & Co. 59	
Cleveland & Buffalo Transit Co. 61	Hutchinson & Co. 62	Pittsburg Coal Co. 66	
Cleveland City Forge & Iron Co. 67	Hyde Windlass Co. 47	Prindiville & Co. 63	
Cleveland Punch & Shear Works Co. 12	International Mercantile Marine Co. 61		
Collingwood Shipbuilding Co. 5		Quintard Iron Works Co. 9	
Continental Iron Works 2	Jenkins Brothers 68	Red Star Line 61	
Cory, Chas. & Son 66	Jenkins, Russell & Eichelberger. 62	Richardson, W. C. 62	
Cramp, Wm. & Sons, S. & E. B. Co. 8	Kahnweiler's Sons, David 67	*Ritchie & Sons, E. S. 64	
Curr, Robert. 93	Katzenstein, L., & Co. 67	Roberts Safety Water-Tube Boiler Co. 9	
Dake Engine Co. 49	Kidd, Joseph 63	Roeiker, H. B. 66	
Dearborn Drug & Chemical Wks. 63	Kingsford Foundry & Machine Works 51	Ross Valve Co. 66	
Delaware River Iron S. B. & E. Works 67	Kremer, C. E. 62		

SHIP FLOORING

Sawdust (made of wood fiber, and mineral substances) can be applied to steel decks cheaply. It is fire proof, water proof, dust proof, and vermin proof. Can be colored any tint and is practically indestructible and monolithic. Samples submitted and estimates furnished.

The C. Clemente Company

1722 Oregon Ave.
CLEVELAND

FORE RIVER SHIPBUILDING CO.

QUINCY, MASSACHUSETTS
SHIP and ENGINE BUILDERS
CURTIS MARINE TURBINES
HIGH GRADE STEEL FORGINGS

W. & A. FLETCHER CO.

NORTH RIVER IRON WORKS

PARSONS MARINE TURBINES

Contractors for Vessels Complete. Marine Engines, Boilers and Machinery of all kinds

Enlarged Facilities

HOBOKEN, N. J.

The Atlantic Works, EAST BOSTON, Massachusetts.

BUILDERS OF
Steamships, Steam Yachts, Tow Boats, Etc.

Marine Engines, Boilers and Tanks.
Heavy Machinery and Plate Iron Work.
THREE MARINE RAILWAYS.

The Martin-Barriss Co.

654 Seneca Street CLEVELAND, OHIO

IMPORTERS AND MANUFACTURERS OF

MAHOGANY


WHITE MAHOGANY

and all Native Cabinet Woods

High Grades of Kiln Dried Woods for Cabin Work and Inside Trim

WHITE OAK TIMBERS AND PLANK

Constantly on Hand and Sawed to Order on Short Notice



THOS. DREIN & SON

BUILDERS of Metallic Life Boats and Rafts, Government and Pleasure Boats, Block and Granulated Cork Life Preservers, Outfits for Lake Steamers a specialty. Tall St. below Railroad.

WILMINGTON, DEL.

John Donnelly, Sr., Pres.
H. B. Folger, Treas.

John Donnelly, Jr., Vice-Pres.
Thos. Donnelly, Secy.

THE

DONNELLY SALVAGE & WRECKING CO., LTD.

KINGSTON, ONT.

DIVERS, STEAM PUMPS, TUGS, ETC.
SUPPLIED ON SHORTEST NOTICE.



Chas. Cory & Son

Manufacturers of

Mechanical and Electrical
Telegraphs and Indicators.
Engine Bells and Electric
Call Bells.

286 Spring St., near Hudson,
NEW YORK CITY.

Water Filters, Regulators and Engines.

We make **Pressure Regulating
Valves** for all purposes, steam or
water.

Our **Feed-Water Filter** will keep
oil out of your boiler.

We can interest you if you use a condenser.

Water Engines for Pumping Organs



**Water Works
Regulating Valve**
Has no peer. Ask for
list of Water Works
using our valves.

THE **ROSS VALVE CO.** TROY
N. Y.

QUINTARD IRON WORKS CO. MARINE TURBINES

ENGINES, BOILERS AND MACHINERY

Office 742 E. 12th St., NEW YORK

The Lockwood Manufacturing Co.

EAST BOSTON, MASS.

ENGINEERS AND MACHINISTS.

Builders of Steamships, Tow Boats and Marine Engines.

Repairing of Hulls and Machinery.

Tietjen & Lang Dry Dock Co.

HOBOKEN, N. J.

EIGHT DRY DOCKS

600, 800, 1,000, 1,200, 1,400, 1,800, 2,000, 10,000 TONS

General Repairs on Wooden and Iron Vessels

FT. OF 17th STREET

Telephone 700 Hoboken

HOBOKEN, N. J.

Practical Marine Engineering

By PROF. W. F. DURANT

For Marine Engineers and Students, with aids for applicants
for marine engineers' license.

PRICE \$8.00

FOR SALE BY

THE MARINE REVIEW, Cleveland

THE ALLEN DENSE-AIR ICE MACHINE

Contains no chemicals, only air. Proven by many years' service in
the tropics on United States men-of-war, steam yachts and passenger
steamers. A hundred are in daily service on steamers.

H. B. ROELKER, 41 Maiden Lane, NEW YORK.

Consulting and Con-
structing Engineer.

Designer and Manufacturer
of Screw Propellers.



Established 1844
A. SCHRADER'S SON, Inc.
32 Rose Street, NEW YORK
Manufacturer of

Submarine Armor and Diving Apparatus

We carry a complete stock of Dresses, Hose and
Repair Sundries.

Improved Bolt Helmet All orders filled day received Write for our prices

ORAM FIX

ESTABLISHED 1860

J. W. FIX

S. FIX'S SONS

SUCCESSORS TO S. FIX & SON.

Steam Flue Welding Works

Our work stands government test. Our Welds are perfectly smooth.
Write us for prices.

COR. LEONARD AND WINTER STS

CLEVELAND, O.

M. W. FOGG

Mattresses
and Cushions



202 Front St.

NEW YORK CITY.

PITTSBURG COAL COMPANY

GENERAL OFFICE, LAKE DEPARTMENT, ROCKEFELLER BUILDING, CLEVELAND, OHIO

Steamboat Fueling Facilities at Various Points on the Great Lakes

CLEVELAND HARBOR { 4 Car Dumpers.
3 Lighters.

FAIRPORT HARBOR { 1 Car Dumper.
1 Lighter.

ERIE HARBOR { 1 Car Dumper.
Fuel Lighter.

ASHTABULA HARBOR { 1 Car Dumper.
1 Lighter.

DETROIT RIVER BRANCH { Docks and Pockets at
Sandwich and Amherstburg.

SAULT RIVER BRANCHES { Dock—Pittsburgh Landing.
Dock and Pockets at Sault Ste. Marie. (The Port Royal Dock Co.)

WE FURNISH ONLY THE BEST GRADE OF

PITTSBURG AND YOUGHIOGHENY COAL



WATSON-STILLMAN HYDRAULICS



We build many Hydraulic Tools for Marine Service.

Our independent Pump Hydraulic Jack is specially adapted for operations requiring the use of a powerful Tool where the space is too confined to work a lever or to place a regular pattern Jack.

Send for our Catalog "Marine Hydraulic Tools," Edition N.

WATSON-STILLMAN CO.

Offices: 26 Cortlandt Street, NEW YORK.
453 The Rookery, CHICAGO.



Katzenstein's Self-Acting Metal Packing

For PISTON RODS, VALVE STEMS, etc. of every description for Steam Engines, Pumps, etc., etc. Adopted and in use by the principal Iron Works and Steamship Companies in this and foreign countries.

FLEXIBLE TUBULAR METALLIC PACKING, for slip-joints on Steam Pipes, and for Hydraulic Pressure.

For full particulars and reference, address

L. KATZENSTEIN & CO.

General Machinists.


358 West Street,

New York.



IRON OR STEEL FORGINGS FINISHED COMPLETE, ROUGH MACHINED OR SMOOTH FORGED ONLY, OF ANY WEIGHT. COUPLING LINKS AND PINS. PRESSED WROUGHT IRON TURNBUCKLES. CAR IRON SPECIALTIES.

ROACH'S SHIP YARD.



Ship
Building
in all its
Branches

BUILDERS OF
STEAMSHIP AND MARINE MACHINERY.
Delaware River Iron Ship Building & Engine Works
CHESTER, PA.

SMOOTH-ON

TRADE MARK-REG. U.S. PAT. OFF.

SCREW THREAD JOINTS.



Smooth-On Elastic Cement makes permanent screw-thread joints.

They never leak. Just the thing for large screw-thread joints.

Sold in 1, 5 and 10-lb. gray labeled cans. Get acquainted with all Smooth-On specialties. New illustrated instruction book free.

Smooth-On Manufacturing Co.

JERSEY CITY, N. J.

VREELAND TOMPKINS, Chemist and Manager.

Neversink Cork Jackets and Life Belt

Warranted 24 pounds. Buoyancy and full weight of Cork, as required by U. S. Inspectors.

Safest Consolidated Cork Life Preservers. Cheapest Ring Buoys and Fenders.

Approved and adopted by U. S. Board of Supervising Inspectors. Also adopted by the principal Ocean, Lake and River Steamer Lines as the only Reliable Life Preserver. Awarded four Medals by World's Columbian Exposition.



**Metallic and
Wooden
Life Boats.**

Metallic Life Rafts. Marine Drags.

Manufacturers of Woolsey's Patent Life Buoy—the lightest, cheapest and most compact life raft known.

DAVID KAHNWEILER'S SONS,
Fox Building, Cor. Franklin Sq. and Dover Street,
NEW YORK CITY.





Wilford's Waterproof Cloth is made of pure twisted flax thread. It is stronger and more durable than cotton, and on account of its light weight is most desirable for Hatch, Boat or Sail covers, Tarpaulins, Side Cloth or Roofing. It will not crack and is positively impenetrable by salt or fresh water. Our customers know this—from others we solicit a trial order.

EDWARD A. BUNKER

Sole Agent for the United States and Canada

P. O. BOX 1579, NEW YORK

Jenkins Bros. Valves



are all carefully tested and inspected before leaving the factory, hence every purchaser is assured of receiving first-class quality and workmanship. Should cause for complaint ever arise, write to the makers, for all genuine Jenkins Bros. Valves are absolutely guaranteed, and bear Trade Mark shown in the cut.

JENKINS BROS., New York, Boston, Philadelphia, Chicago, London.

6

General Electric Company

Marine wiring supplies of every description. Made of bronze and German silver, non-corrosive and waterproof.

853

Principal Office:
SCHENECTADY, N. Y.

Sales Offices
in all large cities.

LIFE PRESERVERS—BUOYS

ACME. SOLID CORK. Each Preserver stamped by U. S. Inspector guaranteeing proper buoyancy. Cork Filled Yacht Fenders. Cork Mooring Buoys. Material and Finish Guaranteed.

Orders filled promptly.

ARMSTRONG CORK COMPANY

Boston	New York	Philadelphia	Pittsburg
Chicago	St. Louis	Baltimore	Cincinnati

HOWARD H. BAKER & CO.
SHIP CHANDLERS
and SAIL MAKERS

18 to 26 Terrace, BUFFALO, N. Y.



Tietjen & Lang Dry Dock Co.

HOBOKEN, N. J.

EIGHT DRY DOCKS

600, 800, 1,000, 1,200, 1,400, 1,800, 2,000, 10,000 TONS.

General Repairs on Wooden and Iron Vessels.

FT. OF 17th STREET

Telephone 700 Hoboken

HOBOKEN, N. J.